

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS
GENERAL NOTES
SUMMARY OF QUANTITIES
STATE STANDARDS
- 3 TC- 17

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS (NORTH)	2009-082 I	VARIOUS	3	2

CONTRACT 60124

SUMMARY OF QUANTITIES

CODE NUMBER	DESCRIPTION	UNIT	TOTAL	Y003	Y003
				CONTRACT MAINT	FORMAL CONTRACTS
X0326702	PRAIRIE WEED CONTROL	ACRE	20	20	0
X0326701	WEED CONTROL, BROADLEAF IN TURF	POUND	11	0	11
25000750	MOWING	ACRE	522	522	0
67100100	MOBILIZATION	L SUM	1	1	0
X0322324	WEED CONTROL, TEASEL	POUND	12	0	12
X0322326	WEED CONTROL, THISTLE	POUND	48	0	48
X0322856	WEED CONTROL, NON-SEL. AND NON-RESIDUAL	GALLON	30	30	0
X0325896	WEED CONTROL, TOTAL VEGETATION	GALLON	90	90	0

GENERAL NOTES

ALL SPRAY LOCATIONS WILL BE DIRECTED BY THE ENGINEER.

TELAR XP AND OVERDRIVE ARE TO BE TANK MIXED TOGETHER AND SPRAYED ON TEASEL AND THISTLE INFESTED AREAS.

HERBICIDE PLATEAU FOR PRAIRIE WEED CONTROL AND WEED CONTROL, BROADLEAF IN TURF WILL BE PROVIDED BY IDOT.

FOR EXPRESSWAYS THE CONTRACTOR SHALL CONTACT THE BUREAU OF TRAFFIC FOR TRAFFIC CLEARANCE NO LATER THAN 11:00 A.M THE DAY BEFORE WORK BEGINS.

CONTRACTOR SHALL REPLACE ANY SIGNAGE, REFLECTORS, AND PAVEMENT MARKINGS, THAT ARE AFFECTED BY THIS PROJECT, TO ITS ORIGINAL CONDITION AND LOCATION. THIS WORK SHALL BE RESTORED AT THE CONTRACTOR'S OWN EXPENSE. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

STATE STANDARDS

- 701101-02
- 701311-03
- 701426-03
- 701901-01

ILLINOIS DEPARTMENT OF TRANSPORTATION

WEED CONTROL & MOWING

Rev 1