

# SUMMARY OF QUANTITIES

801.FED./201.STATE

801.FED./201.STATE

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2843	3249B-R	COOK	64	4

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

CONTRACT NO. 62539

CODE NO.	ITEM	UNIT	TOTAL QTY	CONSTRUCTION TYPE FUND CODE			
				ROADWAY	BRIDGE	RET-WALL	FLOSSMOOR
				1000-2A	X071-2A	Y007	Y060 VILLAGE-100%
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	285	285			
*** 55039700	STORM SEWERS TO BE CLEANED	FOOT	330	330			
56104000	DUCTILE IRON WATER MAIN, MECHANICAL JOINT 10"	FOOT	410				410
56109000	TAPPING VALVES AND SLEEVES 10"	EACH	2				2
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	2				2
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2				2
58700300	CONCRETE SEALER	SQ FT	3480		3480		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	335		180	155	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	330		220	110	
60107700	PIPE UNDERDRAINS 6"	FOOT	110	110			
60228110	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4				4
60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2				2
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8			
60603000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	5	5			
60614600	PAVED DITCH (SPECIAL)	FOOT	400	400			
* 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9' POSTS	FOOT	312	312			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
63200310	GUARD RAIL REMOVAL	FOOT	412	412			
66400305	CHAIN LINK FENCE, 6'	FOOT	180		180		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12			
67100100	MOBILIZATION	L SUM	1	0.5	0.5		
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.5	0.4	0.1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	50	50			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2100	2100			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3816	3816			
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1022	1022			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	88	88			
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	24	24			
* 78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	50	50			
* 78200405	GUARDRAIL MARKERS	EACH	43	43			

CODE NO.	ITEM	UNIT	TOTAL QTY	CONSTRUCTION TYPE FUND CODE			
				ROADWAY	BRIDGE	RET-WALL	FLOSSMOOR
				1000-2A	X071-2A	Y007	Y060 VILLAGE-100%
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
78300105	PAVEMENT MARKING REMOVAL	FOOT	1344	1344			
* 81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	692		692		
* 81301110	JUNCTION BOX EMBEDDED IN STRUCTURE, STAINLESS STEEL, 12"x8"x6"	EACH	4		4		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	500	500			
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	600	600			
X0324243	SEDIMENT CONTROL, SILT CURTAIN	L SUM	1	1			
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	3400		3400		
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	14258	14258			
X0325837	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 6 INCH	FOOT	321	321			
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	144	144			
X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	731	731			
X0426200	DEWATERING	L SUM	1				1
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1			
X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1			
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1		
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1		
XX004782	TEMPORARY BITUMINOUS PAVEMENT	SQ YD	779	779			
XX005656	INLET FILTER CLEANING	EACH	2	2			
XX007864	SANITARY SEWER, DUCTILE IRON 8"	FOOT	221				221
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	5200	5200			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
*** Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4			
Z0022800	FENCE REMOVAL	FOOT	120	120			
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2			
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2			
X0326673	CASING PIPE TO BE JACKED AND BORED IN PLACE - 16"	FOOT	110				110
0 Z0076600	TRAINEES	HOUR	1000		1000		
X0326674	CASING PIPE TO BE JACKED AND BORED IN PLACE - 20"	FOOT	55				55

\* SPECIALTY ITEM  
 0 Y060  
 \*\*\* NON PARTICIPATING ITEM

**RME** Rubinos & Mesia Engineers, Inc.  
 200 S. Michigan Ave, Suite 1500 Chicago, IL 60604-2482  
 T: 312 870 6800 F: 312 663 1473

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.U. 2843 DIXIE HIGHWAY  
 OVER BUTTERFIELD CREEK  
 SUMMARY OF QUANTITIES  
 (2 OF 2)

SCALE: VERT. NONE  
 HORIZ. NONE  
 DATE 6-25-09  
 DRAWN BY AW  
 DESIGNED BY AW  
 CHECKED BY MF