

# SUMMARY OF QUANTITIES

PAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
332/816	2002-113R	WILL	242	10
STA.	TO STA.		EXISTING CONDITIONS:	

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL	ACF			100% CRETE			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	QUANTITIES	ACF ROADWAY I000-2A	ACBHF BRIDGE X071-2A	TRAFFIC SYGNAL GOODENOW RD Y031-1F	TRAFFIC SIGNAL IL-394 Y031-1F	TRAFFIC SIGNAL INTERCONNECT Y031-1F	CRETE TOWNSHIP FIRE DEPT Y031-3D	100% STATE LIGHTING Y030-1E	ACBHF NOISE WALL 80% FED./20% STATE I000-2A				
* MX871055	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	METER	954.4					954.4							
* MX873030	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	METER	224.3						224.3						
* MX877020	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 16.76 METER	EACH	3			1	2								
* MX878030	CONCRETE FOUNDATION, TYPE E 900MM DIAMETER	METER	36.8			18.4	18.4								
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	16890	16890											
△ MZ014800	CULVERT TO BE CLEANED	METER	17	17											
MZ064800	SELECTIVE CLEARING	UNIT	14	14											
* X0322141	REMOVE TEMPORARY WOOD POLE	EACH	1							1					
* X0322314	WEED CONTROL, BROADLEAF IN TURF	GALLON	30	30											
* X0322323	WEED CONTROL, TEASEL	GALLON	1	1											
* X0326760	REMOVE EXISTING LIGHTING CONTROLLER AND SALVAGE	EACH	1							1					
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	1		1										
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	2		2										
△ X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	24	24											
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	12									12			
* X0324311	TEMPORARY WOOD POLE, 18.30 METER, WITH 4.5 METER MAST ARM (INSTALL ONLY)	EACH	36					36							
* X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	10							10					
* X0325705	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	2					2							
* X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1			1									
X2800105	TEMPORARY DITCH CHECKS, URETHANE FOAM/ GEOTEXTILE	EACH	170	170											
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	2			1	1								
* X8250110	LIGHTING CONTROLLER, RADIO CONTROL, DUPLEX CONSOLE TYPE, WITH SCADA	EACH	1							1					
* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	2			1	1								
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.75	0.25										
<del>X0326024</del>	<del>SHRUB, RHUS TYPHINA (STAGHORN SUMAC), 2' HEIGHT, CONTAINER</del>	<del>EACH</del>	<del>610</del>	<del>610</del>											
* M6300101	STEEL PLATE BEAM GUARDRAIL, TYPE A, 1.83 M POSTS	METER	96	96											
* M6320020	STEEL PLATE BEAM GUARDRAIL REMOVAL	METER	173	173											
* MX033790	TEMPORARY WOOD POLE, 18.30 METER, CLASS 4	EACH	1							1					
* MX033791	TEMPORARY WOOD POLE, 18.30 METER, CLASS 4, 4.45 METER MAST ARM	EACH	14							14					
* MX033792	LIGHT POLE FOUNDATION, METAL, 381 MM BOLT CIRCLE, 254 mm X 2.44 mm	EACH	15							15					
* MX877905	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 7.31 METER AND 15.85 METER	EACH	1			1									
* MX877906	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 6.7 METER AND 15.24 METER	EACH	1			1									
* MX877907	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 9.14 METER AND 16.47 METER	EACH	1			1									
* MX877908	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 10.36 METER AND 16.47 METER	EACH	1			1									

△ - Non-participating  
\* Specialty Items