

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	00-00242-00-CH	COOK	129	10
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES					1000-2A ROADWAY SKOKIE 70% STU 30% STATE	1000-2A ROADWAY IN-LINE DETENTION 70% STU \$40K STATE 30%-\$40K LA	Y030-1E LIGHTING SKOKIE 70% STU 30% LA	Y031-1F SIGNALS FOSTER 70% STU 15% STATE 15% LA	Y031-1F SIGNALS GOLF 70% STU 30% STATE	Y031-1F SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	Y031-1F SIGNALS INTERCONNECT 70% STU 30% STATE	Y060 WATER SKOKIE NON-PART 100% LA	Y031-1F SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY										
X8210015	• TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, 400 WATT	EACH	16										
X8210451	• LUMINAIRE, STREET LIGHTING, HIGH PRESSURE SODIUM VAPOR, 400 WATT, 240 VOLT	EACH	16										
X8250090	• COMBINATION POLE LIGHTING CONTROLLER	EACH	2										
X8710020	• FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	5,113								5,113		
X8730027	• ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,771					465	1,306				
X8730250	• ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1,299										1,299
X8900010	• TEMPORARY TRAFFIC SIGNAL INTERCONNECT	EACH	2								2		
XX000613	MODULAR BLOCK RETAINING WALL	SQ FT	1,195	1,195									
XX002113	• TEMPORARY LIGHTING CONTROLLER	EACH	1										1
XX002948	TEMPORARY ACCESS WALK	EACH	15	15									
XX003451	• LIGHTING CONTROLLER, PAD MOUNTED	EACH	1										1
XX003668	PRECONSTRUCTION VIDEO TAPING	L SUM	1	1									
X8420020	• UNINTERRUPTABLE POWER SUPPLY	EACH	2						1	1			
XX006937	• GROUND ROD, 5/8" DIA. X 10 FT.	EACH	16										16
D2005716	• TREE, PYRUS CALLERYANA "CHANTICLEER", (C (CHANTICLEER FLOWERING PEAR), 2" CALIPER, BALLED AND BURLAPPED	EACH	6	6									
Z0004900	BITUMINOUS MIXTURE FOR PATCHING POTHoles (HOT MIX)	TON	20	20									
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1									
Z0019600	DUST CONTROL WATERING	UNIT	100	100									
Z0045000	* PRESSURE CONNECTION 12" X 6"	EACH	1										1
Z0045002	* PRESSURE CONNECTION 12" X 8"	EACH	1										1
Δ Z0076600	TRAINEES	hour	2,000	2,000									
X6020102	MANHOLES, TYPE A, 9'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1										1
X6020101	MANHOLES, TYPE A, 9'-DIAMETER, TYPE 1 FRAME, CLOSED LID (SPECIAL)	EACH	1										1
XX001382	* CUT AND CAP EXISTING WATER MAIN, 6"	EACH	2										2
XX006886	* CUT AND CAP EXISTING WATER MAIN, 8"	EACH	2										2
XX004707	* CONNECTION TO EXISTING WATER MAIN, 4"	EACH	1										1
X0324440	* CONNECTION TO EXISTING WATER MAIN, 8"	EACH	2										2
XX005733	* CONNECTION TO EXISTING WATER MAIN, 12"	EACH	1										1
X8770415	• STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 18 FT. AND 38 FT.	EACH	1							1			
X8770420	• STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 22 FT. AND 54 FT.	EACH	1							1			
X8770425	• STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 30 FT. AND 54 FT.	EACH	1							1			
66900200	* NON-SPECIAL WASTE DISPOSAL	CU YD	4	4									
66900450	* SPECIAL WASTE PLANS AND REPORT	L SUM	1	1									
66900530	* SOIL DISPOSAL ANALYSIS	EACH	1	1									

Δ Y080
 • SPECIALTY ITEM

Δ Revised 10-26-09

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SKOKIE BOULEVARD (U.S. ROUTE 41)
 SUMMARY OF QUANTITIES
 DATE 11-14-08
 DRAWN BY
 CHECKED BY

PLOT DATE = 11/14/2008
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = 015578