

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	00-00242-00-CH	COOK	129	5
STA.		TO STA.		
FED. ROAD DIST. NO. 7 ILLINOIS		FED. AID PROJECT		

SUMMARY OF QUANTITIES				1000-2A ROADWAY SKOKIE 70% STU 30% STATE	1000-2A ROADWAY IN-LINE DETENTION 70% STU \$40K STATE 30%-\$40K LA	Y030-1E LIGHTING SKOKIE 70% STU 30% LA	Y031-1F SIGNALS FOSTER 70% STU 15% STATE 15% LA	Y031-1F SIGNALS GOLF 70% STU 30% STATE	Y031-1F SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	Y031-1F SIGNALS INTERCONNECT 70% STU 30% STATE	Y060 WATER SKOKIE NON-PART 100% LA	Y031-1F SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY									
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,211	2,211								
42001300	PROTECTIVE COAT	SQ YD	4,633	4,633								
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	72	72								
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	16,252	16,252								
42400800	DETECTABLE WARNINGS	SQ FT	262	262								
44000100	PAVEMENT REMOVAL	SQ YD	16,342	16,342								
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	5,009	5,009								
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	91	91								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,318	3,318								
44000600	SIDEWALK REMOVAL	SQ FT	12,953	12,953								
44003100	MEDIAN REMOVAL	SQ FT	15,975	15,975								
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SQ YD	579	84	238						257	
44201337	CLASS C PATCHES, TYPE I, 9 INCH	SQ YD	4	4								
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	16	16								
44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	71	32							39	
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	489	33	238						218	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	451	451								
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	186	186								
550A0830	STORM SEWERS, CLASS A, TYPE 3 78"	FOOT	609		609							
550A1050	STORM SEWERS, CLASS A, TYPE 4 36"	FOOT	70		70							
55100300	STORM SEWER REMOVAL 8"	FOOT	185	185								
55100500	STORM SEWER REMOVAL 12"	FOOT	83	83								
56100600	* WATER MAIN 6"	FOOT	115								115	
56100700	* WATER MAIN 8"	FOOT	95								95	
56100900	* WATER MAIN 12"	FOOT	747								747	
56105000	* WATER VALVES 8"	EACH	1								1	
56105200	* WATER VALVES 12"	EACH	2								2	
56106600	* ADJUSTING WATER MAIN 12"	FOOT	60	60								
56400500	* FIRE HYDRANTS TO BE REMOVED	EACH	4								4	
56400820	* FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	4								4	
60107600	PIPE UNDERDRAINS 4"	FOOT	340	340								
60201330	CATCH BASINS, TYPE A, 4"-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	28	28								
60203240	CATCH BASINS, TYPE A, SPECIAL, 4"-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	3	3								
60208230	CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE	EACH	8	8								

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SKOKIE BOULEVARD (U.S. ROUTE 41)
 SUMMARY OF QUANTITIES
 DATE 11-14-08
 DRAWN BY CEC
 CHECKED BY DWB

PLOT DATE = 11/14/2008
 FILE NAME = WFILEL8
 USER NAME = RUSERS