

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	00-00242-00-CH	COOK	129	7
STA.	TO STA.			
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES					1000-2A ROADWAY SKOKIE 70% STU 30% STATE	1000-2A ROADWAY IN-LINE DETENTION 70% STU \$40K STATE 30%-\$40K LA	Y030-1E LIGHTING SKOKIE 70% STU 30% LA	Y031-1F SIGNALS FOSTER 70% STU 15% STATE 15% LA	Y031-1F SIGNALS GOLF 70% STU 30% STATE	Y031-1F SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	Y031-1F SIGNALS INTERCONNECT 70% STU 30% STATE	Y060 WATER SKOKIE NON-PART 100% LA	Y031-1F SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY										
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12		12								
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,588		1,588								
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	7,191		7,191								
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	174,666		174,666								
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	18,555		18,555								
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	876		876								
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3,396		3,396								
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	26,741		26,741								
72000100	* SIGN PANEL - TYPE 1	SQ FT	175.0		175.0								
72000200	* SIGN PANEL - TYPE 2	SQ FT	18.8		18.8								
72400100	* REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	9		9								
72400500	* RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1		1								
72900100	* METAL POST - TYPE A	FOOT	225		225								
72900200	* METAL POST - TYPE B	FOOT	119.5		119.5								
78008200	* POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	1,092		1,092								
78008210	* POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	3,763		3,763								
78008230	* POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	6,306		6,306								
78008240	* POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	400		400								
78008250	* POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	117		117								
78008270	* POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	626		626								
78100100	* RAISED REFLECTIVE PAVEMENT MARKER	EACH	455		455								
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3,417		3,417								
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	363		363								
81000600	* CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	2,509				42	817	318	1,332			
81000700	* CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	109					109					
81000800	* CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	54				43	11					
81001000	* CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	14				4	10					
81018500	* CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	2,246			1,205	564	477					
81018900	* CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	1,000				416	584					
81400100	* HANDHOLE	EACH	13			1	4	7	1				
81400200	* HEAVY-DUTY HANDHOLE	EACH	9				4	4	1				
81400300	* DOUBLE HANDHOLE	EACH	4				2	2					
81603090	* UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	4,158			4,158							
81603160	* UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (EPR-TYPE RHW), 1" DIA. POLYETHYLENE	FOOT	937			937							

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SKOKIE BOULEVARD (U.S. ROUTE 41)

SUMMARY OF QUANTITIES

DATE 11-14-08  
DRAWN BY CEC  
CHECKED BY DWB