

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	00-00242-00-CH	COOK	129	44
STA. 100+00 TO STA. 112+00				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				



LEGEND

- SODDING, SALT TOLERANT TOPSOIL FURNISH AND PLACE, 4" NITROGEN, PHOSPHORUS, AND POTASSIUM FERTILIZER
- P** TEMPORARY FENCE, PRUNING, AND ROOT PRUNING
- X** TREE REMOVAL

SKOKIE BOULEVARD

FOSTER STREET

EX ROW

PROJECT BEGINS  
SKOKIE BOULEVARD  
(U.S. ROUTE 41)  
STATION 105+83.67

MATCH LINE STATION 112+00  
SEE SHEET NO. 45

TEMPORARY EROSION CONTROL NOTES

1. THE ENGINEER SHALL CONDUCT A FIELD REVIEW FOR EROSION AND SEDIMENT CONTROL WITH THE PRIME AND SUBCONTRACTORS PRIOR TO ANY EARTHWORK OPERATIONS TO DETERMINE TIMING ADVANCEMENT OF CONTROL MEASURES.
2. THE CONTRACTOR WILL BE REQUIRED TO IMPLEMENT AND MAINTAIN EROSION CONTROL MEASURES IMMEDIATELY AFTER STRIPPING OF EXISTING VEGETATION.
3. NO CONCENTRATED RUNOFF FLOW FROM STRIPPED AREAS SHALL LEAVE THE SITE WITHOUT BEING TREATED. THE CONTRACTOR SHALL ADJUST HIS OPERATIONS AND IMPLEMENT EROSION CONTROL MEASURES ACCORDINGLY.
4. THE FILTERS SHALL BE PROVIDED ON ALL PROPOSED INLETS AND CATCH BASINS WITHIN THE PROJECT LIMITS. SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING WILL BE REQUIRED DURING THE CONSTRUCTION PERIOD AS NEEDED. AN ESTIMATED QUANTITY OF 2 ADDITIONAL CLEANINGS HAS BEEN INCLUDED IN THE QUANTITIES.
5. EROSION CONTROL MEASURES SHALL BE INSPECTED BY THE CONTRACTOR AND ENGINEER AT LEAST ONCE EVERY SEVEN DAYS WITHIN 24 HOURS OF ANY STORM EXCEEDING 1/2" OF PRECIPITATION OR EQUIVALENT SNOWFALL.
6. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PREVENT POLLUTION OF STORM WATER AND SHALL FOLLOW IEPA & IDOT CONSTRUCTION MEMORANDUM NO. 06-60.
7. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICAL, BUT NO MORE THAN 14 DAYS AFTER CONSTRUCTION ACTIVITY HAS CEASED IN AN AREA WHERE CONSTRUCTION ACTIVITY WILL NOT OCCUR FOR A PERIOD OF 21 OR MORE CALENDAR DAYS.

PR ROW

PR ROW

PR TEMP EASEMENT

THEATER ENTRANCE

TREE REPLACEMENT					
IDOT CODE	SCIENTIFIC NAME	COMMON NAME	STATION	OFFSET	
FOSTER STREET					
D2002788	PINUS NIGRA	AUSTRIAN PINE	106+31	84	RT
D2002788	PINUS NIGRA	AUSTRIAN PINE	106+40	88	RT
A2004616	GLEDITSIA TRIACANTHES INERMIS	THORNLESS COMMON HONEY LOCUST	106+45	115	RT

PLOT DATE = 11/13/2008  
FILE NAME = 111408.DWG  
USER NAME = SAG

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SKOKIE BOULEVARD (U.S. ROUTE 41)  
SKOKIE BOULEVARD  
LANDSCAPING & EROSION CONTROL  
STA. 100+00 TO STA. 112+00

DATE 11-14-08  
DRAWN BY SAG  
CHECKED BY DWB

50' 0 50'  
HORIZ. 1"=50'