



ILLINOIS ROUTE 59
SOUTH OF 111TH STREET TO 87TH STREET
STA 3557+00 TO STA 3777+00

LEGEND

- ① EXISTING COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24
- ② EXISTING GROUND LINE (GRASS)
- ③ FURNISHING AND PLACING TOPSOIL, 4"
- ④ PORTLAND CEMENT CONCRETE SIDEWALK, 5"
- ⑤ AGGREGATE BASE COURSE TYPE B, 2"

NOTE:
THE CITY OF NAPERVILLE STANDARD DETAIL PVMT 3 IS INCLUDED AS A REFERENCE AND SHALL GOVERN FOR THE PROPOSED IMPROVEMENTS.

ILLINOIS ROUTE 59 SIDEWALK	SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION			
	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SUBGRADE	FURNISHED EXCAVATION
PROJECT SUBTOTAL (CU. FT.)	97,580	0	0	41,457
PROJECT SUBTOTAL (CU. YD.)	3,614	198	198	1,535
SHRINKAGE FACTOR ADJUSTMENT (15%)	-	-	-	x 1.15
PROJECT TOTAL (CU. YD.)	3,614	198*	198*	1,766

* CONTINGENCY QUANTITY OF 198 CU YD OF REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL AND POROUS GRANULAR EMBANKMENT, SUBGRADE HAS BEEN PROVIDED (ASSUMING 10% OF THE SIDEWALK WILL NEED UNDERCUT) TO BE USED IN THE FIELD AT THE DIRECTION OF THE ENGINEER.

