

**SUMMARY OF QUANTITIES**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
• 09-00046-00-RS	WILL		12	3
STA.	TO STA.			
FED. ROAD DIST. NO. C-91-725-09	ILLINOIS	FED AID PROJECT ARA-9003-(396)		

•FAU 0349 WALLIN DRIVE  
CONTRACT NO. 63226

CODE NO.	PAY ITEM	UNIT	CONSTRUCTION CODE 1000 TOTAL QUANTITY
20201006	GRADING AND SHAPING SHOULDERS	UNIT	43
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1576
40600300	AGGREGATE (PRIME COAT)	TON	32
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	680
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	176
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1360
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	155
48101200	AGGREGATE SHOULDERS, TYPE B	TON	668
67100100	MOBILIZATION	LSUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	LSUM	1
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE, 4"	FOOT	15847
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE, 6"	FOOT	618
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE, 12"	FOOT	119
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE, 24"	FOOT	32
• 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	35
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	90

• INDICATES SPECIALTY ITEM

PROJECT # 2008-01 BAXTER & WOODMAN, INC. ...  
 STATE # 09-00046-00-RS ...  
 LICENSE NO. 384-00121 - EXPIRES 4/30/2009 ...  
 8/27/2009 2:56:39 PM



USER NAME = 566bed	DESIGNED - JGH	REVISED - IDOT REVIEW 6-29-09
FILE NAME = 090439-500.sht	DRAWN - BCD	REVISED -
PLOT DATE = 8/27/2009	CHECKED - NJP	REVISED -
	DATE - 05-22-09	REVISED -

**VILLAGE OF PLAINFIELD, ILLINOIS  
FAU ROUTE 0349 WALLIN DRIVE  
LAPP IMPROVEMENTS**

**SUMMARY OF QUANTITIES**

SCALE: NONE

STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
• 09-00046-00-RS	WILL		12	3
FED. ROAD DIST. NO.	ILLINOIS	CONTRACT NO. 63226		
		FED. AID PROJECT		