

INDEX OF SHEETS

- 1. COVER SHEET
- 2. INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
- 3. SUMMARY OF QUANTITIES & GENERAL NOTES
- 4. TYPICAL CROSS SECTIONS
- 5.-11. PLAN SHEETS
- 12.-15. DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS
- 16.-19. TRAFFIC SIGNALS
- 20.-24. DETAILS
- 25.-35. CROSS SECTIONS

GENERAL NOTES

THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007 BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION, SHALL GOVERN THIS WORK.

BEFORE ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)

10 FOOT TRANSITIONS SHALL BE USED TO MATCH THE PROPOSED CURB AND GUTTER AND MEDIANS TO EXISTING CURBS AND GUTTERS AND MEDIANS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED.

THE CONTRACTOR SHALL COORDINATE THE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF BRIDGEVIEW.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON VILLAGE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE VILLAGE.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIAL

THE CONTRACTOR SHALL INFORM THE CCHD DESIGN ENGINEER AT (312) 603-1730 PRIOR TO THE START OF ANY WORK ON THE CONTRACT. A MINIMUM OF FIVE (5) WORKING DAYS ADVANCE NOTICE IS REQUIRED.

THE EXACT LOCATIONS OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE THE INSTALLATION OF ANY COMPONENTS OF THE TRAFFIC SIGNAL SYSTEM. FOR THE LOCATIONS OF THE UTILITIES, CALL JULIE TOLL FREE AT 1-800-892-0123.

IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE EXISTING TRAFFIC SIGNAL CABLES AND CONDUITS.

ALL ELECTRICAL CABLE SHALL HAVE A POLYVINYL CHLORIDE JACKET.

THE TYPE OF LED MODULES THAT ARE TO BE INSTALLED AT THIS INTERSECTION MUST BE OF THE "GELCORE" BRAND TO MATCH THE EXISTING LED MODULES ALREADY IN USE

11 AUTUMN MAPLE TREES HAVE BEEN PROVIDED IN THE CONTRACT AND THE EXACT LOCATION OF THESE TREES WILL BE DETERMINED IN THE FIELD THROUGH COORDINATION WITH THE VILLAGE OF BRIDGEVIEW AND THE RESIDENT ENGINEER.

THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT 1-847-705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

STATE STANDARDS

- 420001-07 PAVEMENT JOINTS
- 424001-05 CURB RAMPS FOR SIDEWALK
- 606001-04 CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
- 701701-06 URBAN LANE CLOSURE, MULTILANE, INTERSECTION
- 701801-04 LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
- 701901-01 TRAFFIC CONTROL DEVICES
- 720001-01 SIGN PANEL MOUNTING DETAILS
- 720006-02 SIGN PANEL ERECTION DETAILS

FILE NAME = 09201-INDX-01 - IDOT P01	USER NAME =	DESIGNED -- RJW	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SIDEWALK IMPROVEMENTS INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES			F.A.U. RTE. 2757/1537	SECTION 09-00060-00-SW	COUNTY COOK	TOTAL SHEETS 35	SHEET NO. 2
	PLOT SCALE =	DRAWN -- PS	REVISED --		SCALE:	SHEET NO. 2	OF 35 SHEETS	STA.	TO STA.	CONTRACT NO. 63228		
	PLOT DATE = 08-20-09	CHECKED -- AG	REVISED --		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(325)							