

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE						
					1000-2A	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031-1F	Y080
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	106	106						
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	77	77						
	20200100	EARTH EXCAVATION	CU YD	2454	2454						
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	100	100						
	20800150	TRENCH BACKFILL	CU YD	281	281						
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	880	880						
	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	200	200						
*	25200700	SODDING, SPECIAL	SQ YD	880	880						
	28000300	TEMPORARY DITCH CHECKS	EACH	10	10						
	28000400	PERIMETER EROSION BARRIER	FOOT	819	819						
	28000510	INLET FILTERS	EACH	20	20						
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1157	1157						
	31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	2918	2918						
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2914	2914						
	40600300	AGGREGATE (PRIME COAT)	TON	27	27						
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	193	193						
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1						
	40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	520	520						
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	531	531						
	40701831	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 7 1/2 INCH	SQ YD	145	145						
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	10413	10413						
	42400800	DETECTABLE WARNINGS	SQ FT	48	48						
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	364	364						
	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	4574	4574						
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	47	47						
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	111	111						
	44000600	SIDEWALK REMOVAL	SQ FT	4882	4882						
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	137	137						
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	265	265						
*	56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1						
*	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	1	1						
	60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	472	472						
	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1						
	60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	5	5						
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1FRAME, CLOSED LID	EACH	3	3						
	60255410	CATCH BASINS TO BE CLEANED	EACH	20	20						
	60255500	MANHOLES TO BE ADJUSTED	EACH	5	5						
	60260050	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	1	1						
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3	3						
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	2	2						
	60266910	VALVE BOXES TO BE REMOVED	EACH	1	1						
	60500060	REMOVING INLETS	EACH	1	1						
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1492	1492						
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6						
	67100100	MOBILIZATION	L SUM	1	1						
	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1						
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1500	1500						
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1700	1700						
	70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	500	500						

\* - INDICATES SPECIALTY ITEMS

FILE NAME = 08659-QUAN-01 - P01

USER NAME =	DESIGNED -- MRS	REVISED --
	CHECKED -- PKB	REVISED --
PLOT SCALE =	DRAWN -- PS	REVISED --
PLOT DATE = 8-28-09	CHECKED -- AG	REVISED --

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

US ROUTE 6 (162ND STREET) & WAUSAU AVENUE  
INTERSECTION IMPROVEMENTS  
SUMMARY OF QUANTITIES

F.A.P. RTE. 351	SECTION 09-00086-00-CH	COUNTY COOK	TOTAL SHEETS 43	SHEET NO. 3
SCALE: SHEET NO. 3 OF 43 SHEETS STA. TO STA.			CONTRACT NO. 63261	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(330)				