



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 13, 2009

SUBJECT: FAU Route 1329 (Main Street)
Project No. ARA-9003(376)
Section 09-00282-00-RS (Skokie)
Cook County
Contract No. 63281
Item 110, Addendum A
November 6, 2009 Letting

TO PROSPECTIVE BIDDERS:

To clarify information it is necessary to revise the following:

1. Remove existing page 2 of the special provisions and replace it with the attached revised page 2.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are printed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Charles Ingersoll
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

Special Provisions
080857.40

Village of Skokie
Main Street
Section No.: 09-00282-00-RS
Project No.: ARA-9003(376)
Job No.: C-91-713-09

STATUS OF UTILITIES:

No Conflicts Anticipated.

Contractor must secure Cook County Highway Department Permit for work near the Crawford Avenue and Main Street intersection. Cook County has assigned this project permit number 09-08-1193-C. Cost of permit shall be included with the contract.

*
Added
10-13-09

NOTE: All underground utilities shall be located by the Contractor prior to the start of construction. Call J.U.L.I.E. at 1-800-892-0123 48 hours prior to digging. **Watch and Protect all utilities.**

The above represents the best information available to the Village and is included for the convenience of the bidder. Utility relocation startup date is assumed to be from the date the R.O.W. is staked and permits are secured unless otherwise noted. The applicable Articles 105.07, 107.20 and 107.31 of the Standard Specifications for Road and Bridge Construction shall apply.

HOT-MIX ASPHALT SURFACE COURSE:

Work shall be according to Section 406, except as modified herein:

CONSTRUCTION REQUIREMENTS

406.06 Placing. (e) Spreading and Finishing.

Add the following to the end of this Article to read:

“The days paving operation should result in a single transverse joint. Any cold longitudinal joints will not be accepted. Providing a single transverse joint shall be accomplished by paving one lane of sufficient length that will allow for the paving of the adjacent lane in the same day.”

406.13 Method of Measurement. Add the following to the end of this Article to read:

“This work will be measured for payment in place in tons. Adjustments shall comply with the method of measurement included in this Article.”

406.14 Basis of Payment: Revise the second paragraph of this Article to read:

“406.14 Basis of Payment. This work will be paid for at the contract unit price per tom for HOT-MIX ASPHALT SURFACE COURSE, MIX “D”, N70 of the thickness specified, which price shall include installation as outlines above.”