

P.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2324	09-00017-00-RS	KANE	11	3
CONTRACT NO. 63295				

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	CONST. CODE 1000 TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11,322
40600300	AGGREGATE (PRIME COAT)	TON	55
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	60
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,270
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	410
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2,540
42400800	DETECTABLE WARNINGS	SQ FT	312
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	22,643
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	337
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	4,156
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	10,530
60255500	MANHOLES TO BE ADJUSTED	EACH	18
60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	15
60266600	VALVE BOXES TO BE ADJUSTED	EACH	21
67100100	MOBILIZATION	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	300
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,568
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	100
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	213.8
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10,439
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,524
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	158
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	133
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	11
X0321558	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	7
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	70
XX006425	RESTORATION	SQ YD	155
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

* INDICATES SPECIALTY ITEMS

Printed: August 12, 2009 @ 9:24 AM By: Terri Seider-Johnson - Tab: 03 Quantities 22-34

Path: \\S:\PROJ\HA0871\DWG\DWG_FINAL\ENG\HA0871-CVR

COPYRIGHT © 2009 ENGINEERING ENTERPRISES, INC.

Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60554
630.466.6700 / www.eelweb.com

VILLAGE OF HAMPSHIRE
KANE COUNTY, ILLINOIS

NO.	DATE	REVISIONS

STATE STREET
LAPP IMPROVEMENTS

SUMMARY OF QUANTITIES

DATE:	MAY 2009
PROJECT NO:	HA0871
FILE:	HA0871-CVR
SHEET	3 OF 11