

SUMMARY OF QUANTITIES

CODE	PAY ITEM DESCRIPTION	UNT	1000	1000	NON PARTICIPATING	
			TOTAL QUANTITY	100% FEDERAL 0% LOCAL	Y060 100% VILLAGE OF BROOKFIELD	
~	20800150	TRENCH BACKFILL	CU YD	75		75
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	500	500	
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10	
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10	
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10	
	25200100	SODDING	SQ YD	500	500	
	25200200	SUPPLEMENTAL WATERING	UNIT	10	10	
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	60	60	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5,500	5,500	
	40600300	AGGREGATE (PRIME COAT)	TON	60	60	
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40	
	40600725	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	1,275	1,275	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	400	400	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MX "D", N50	TON	3,300	3,300	
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	20	20	
	42101300	PROTECTIVE COAT	SQ YD	750	750	
	42300300	PORLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	50	50	
	42300400	PORLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	160	160	
	42400200	PORLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4,000	4,000	
	42400800	DETECTABLE WARNINGS	SQ FT	600	600	
~	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	27,000	27,000	
~	44000100	PAVEMENT REMOVAL	SQ YD	160	160	
~	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	70	70	
~	44000600	SIDEWALK REMOVAL	SQ FT	4,000	4,000	
~	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,500	1,500	
~	44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	10	10	
~	44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	125	125	
~	44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	80	80	
~	44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	500	500	
~	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	4	
~	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1	
~	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	48	48	
~	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1	
~	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	52	52	
~	60266610	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	2	2	
~	67100100	MOBILIZATION	L SUM	1	1	
~	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	
~	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	900	900	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150	150	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12,500	12,500	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,350	1,350	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,000	1,000	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	500	500	
~*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	400	400	
~*	X0325207	TELEVISION INSPECTION OF SEWER	FOOT	1,900		1,900
~*	XX000690	SANITARY SEWER REMOVAL AND REPLACEMENT 10"	FOOT	11		11
~*	XX001464	SANITARY SEWERS, PVC, 6"	FOOT	40		40
~*	XX005634	12"x6" PVC SEWER SERVICE CONNECTIONS	EACH	1		1
~*	XX006449	12" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	6		6
~*	XX006451	10"x6" PVC SEWER SERVICE CONNECTIONS	EACH	2		2
~*	XX006815	8"x6" PVC SEWER SERVICE CONNECTIONS	EACH	5		5
~*	XX008190	8" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	70		70
~*	XX104100	CONNECTION TO EXISTING MANHOLE	EACH	1		1
~	Z0004900	BITUMINOUS MIXTURE FOR PATCHING POTHOLES (HOT MIX)	TON	40	40	
~	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

* DENOTES SPECIALTY ITEM
 ~ DENOTES SPECIAL PROVISION HAS BEEN PROVIDED

Drawing file: W:\Projects\12509095 - Profile Ave LAPP\SUMMOI.dwg Aug 28, 2009 - 8:48am

HANCOCK ENGINEERING
 Civil Engineers
 Municipal Consultants
 Established 1911

USER NAME	DESIGNED - WOP	REVISED
	DRAWN - LEV/MK	
PLOT SCALE	CHECKED - JG	
PLOT DATE	DATE - 8-17-09	

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE: NONE	SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2732	09-00124-00-RS	COOK	22	4
CONTRACT NO. 63296			PROJECT ARA-9003 (302)	