

CODE NUMBER	PAY ITEM	UNIT	TOTAL	GARFIELD STREET		FIRST STREET	PARK AVENUE
				PARTICIPATING (100% FEDERAL A.R.R.A. FUNDS)	NON-PARTICIPATING (100% VILLAGE OF HINSDALE FUNDS)	NON-PARTICIPATING (100% VILLAGE OF HINSDALE FUNDS)	NON-PARTICIPATING (100% VILLAGE OF HINSDALE FUNDS)
				1000	Y060-	Y060-	Y060-
550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	344	344			
550A2720	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 3 12"	FOOT	22	22			
550A2740	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 3 18"	FOOT	518	518			
56104800	WATER VALVES 4"	EACH	1				1
56105000	WATER VALVES 8"	EACH	4		2	1	1
56105200	WATER VALVES 12"	EACH	3			1	2
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	6		4	2	
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	6		4	2	
60200205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	1	1			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11	11			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11	11			
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3			
60228110	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1		
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	7	7			
60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5		2	1	2
60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3			1	2
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	12	12			
60266500	VALVE VAULTS TO BE REMOVED	EACH	8		2	2	4
60266910	VALVE BOXES TO BE REMOVED	EACH	1		1		
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	16	16			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	60	60			
67100100	MOBILIZATION	L SUM	1	1			
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1			
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	400	400			
70300725	TEMPORARY PAINT PAVEMENT MARKING 4" WHITE	FOOT	8,980	8,812		84	84
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	609	609			
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37	37			
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	986	736		250	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	613	613			
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	116	116			
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	990	870			120
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	260	234		13	13
78300100	PAVEMENT MARKING REMOVAL	SQ FT	544	513			31
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1			
88600600	DETECTOR LOOP REPLACEMENT	FOOT	220	220			
X0323840	WATER MAIN LINE STOP 6"	EACH	3		3		
X0323841	WATER MAIN LINE STOP 8"	EACH	2			1	1

⊙ SPECIALTY ITEM \* SEE SPECIAL PROVISIONS, PLAN DETAILS, OR PLAN NOTE FOR CLARIFICATION.



USER NAME = sjohnson	DESIGNED -	REVISED -
PLOT SCALE = NONE	DRAWN - SVJ	REVISED -
PLOT DATE = 8/20/2009	CHECKED - GT	REVISED -
	DATE - 8/20/09	REVISED -

**VILLAGE OF HINSDALE  
DUPAGE COUNTY, ILLINOIS  
GARFIELD STREET, FIRST STREET, & PARK AVENUE**

SUMMARY OF QUANTITIES			
SCALE: NONE	SHEET NO. 4 OF 65 SHEETS	STA.	TO STA.

F.A.U. RTE. 2678	SECTION NO. 08-00086-00-RS	COUNTY DUPAGE	TOTAL SHEETS 65	SHEET NO. 4
CONTRACT NO. 63297				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

PROJECT CONTACT: S. PETERSON, P.E. SEC GROUP, INC. 1800 PROFESSIONAL DESIGN FIRM # 188-888108