

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	CONST. CODE
			1000 TOTAL QUANTITY
Δ 21400100	GRADING AND SHAPING DITCHES	FOOT	280
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6,042
40600300	AGGREGATE (PRIME COAT)	TON	121
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,692
40600895	CONSTRUCTING TEST STRIP	EACH	1
Δ 40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	412
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3,384
42400800	DETECTABLE WARNINGS	SQ FT	32
Δ 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	893
Δ 44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	145
Δ 44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	17
Δ 44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	74
Δ 44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	2,548
Δ 48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,325
67100100	MOBILIZATION	L SUM	1
Δ 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8,160
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37,643
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,721
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37,643
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	106
Δ X0322052	ASPHALT REJUVENATING AGENT	GALLON	3,021
Δ X0324096	HOT IN-PLACE RECYCLING	SQ YD	30,210
Δ XX006425	RESTORATION	SQ YD	473
Δ XX006806	HOT-MIX ASPHALT DRIVEWAY PAVEMENT	SQ YD	617

Δ SEE SPECIAL PROVISIONS
* SPECIALTY ITEMS

Printed: August 17, 2009 @ 7:19 AM By: Kris Fung - Tab: 03 Sum of Quant 22x34

COPYRIGHT © 2009 ENGINEERING ENTERPRISES, INC.



Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60554
630.466.6700 / www.eeiweb.com

VILLAGE OF SUGAR GROVE
KANE COUNTY, ILLINOIS

NO.	DATE	REVISIONS

PRAIRIE STREET
LAPP IMPROVEMENTS

SUMMARY OF QUANTITIES

DATE:	AUGUST 2009
PROJECT NO:	SG0909
FILE:	SG0909-CVR
SHEET	3 OF 12

Path: \\SUGARPRO\SG0909\DWG\DWG_FINAL\ENG\SG0909-CVR