

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2508	09-00041-00-RS	KANE/KENDALL	17	3
CONTRACT NO. 63299				

CODE NO.	PAY ITEM	UNIT	CONST. CODE	KANE COUNTY	KENDALL COUNTY
			1000 TOTAL QUANTITY		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,195	1,883	2,312
40600300	AGGREGATE (PRIME COAT)	TON	84	38	46
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,175	528	647
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.5	0.5
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	189	43	146
40600990	TEMPORARY RAMP	SQ YD	253	147	106
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,350	1,055	1,295
Δ 42400800	DETECTABLE WARNINGS	SQ FT	314	154	160
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	20,975	9,413	11,562
Δ 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,510	768	742
Δ 44002400	CURB REMOVAL (SPECIAL)	FOOT	110	55	55
Δ 44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	2,885	1,093	1,792
Δ 44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	471	227	244
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3,140	2,168	972
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	0
67100100	MOBILIZATION	L SUM	1	0.5	0.5
Δ 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	0.5	0.5
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	3	3
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,504	1,225	1,279
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	541	78	463
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9,466	4,569	4,897
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,105	100	1,005
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	803	18	785
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	203	32	171
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	835	408	427
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	541	78	463
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,466	4,569	4,897
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,105	100	1,005
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	803	18	785
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	203	32	171
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	245	116	129
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	245	116	129
Δ * 81400115	HANDHOLE TO BE ADJUSTED	EACH	3	0	3
Δ * 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,434	171	1,263
Δ X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	2	2	0
Δ XX006425	RESTORATION	SQ YD	468	223	245
Δ XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	19	19	0

Δ SEE SPECIAL PROVISIONS  
\* SPECIALTY ITEMS

Plotted: August 14, 2009 @ 10:48 AM By: Kris Ping - Tab: 03\_Sum of Quant 22x34

COPYRIGHT © 2009 ENGINEERING ENTERPRISES, INC.

**Engineering Enterprises, Inc.**  
CONSULTING ENGINEERS  
52 Wheeler Road  
Sugar Grove, Illinois 60554  
630.466.6700 / www.eeiweb.com

**VILLAGE OF MONTGOMERY**  
Kane & Kendall Counties, Illinois

NO.	DATE	REVISIONS

**DOUGLAS ROAD  
LAPP IMPROVEMENTS**

**SUMMARY OF QUANTITIES**

DATE:	AUGUST 2009
PROJECT NO:	M00762
FILE:	M00762-CVR
SHEET	<b>3</b> OF <b>17</b>

Path: H:\5858\PROJ\M00762\DWG\DWG\_FINAL\_ENG\M00762-CVR