# SCHEDULE OF QUANTITIES

44213200 SAW CUTS

| FEET | LOCATION | | | | | | REMARKS |
|---|---|---|---|---|---|---|---|
| 850 | LT/RT | 1418+ | 56 | TO | 1425 + | 14 | SN 037-0015 contingency pavement TBD by RE |
| 813 | LT/RT | 1419 + | 28 | TO | 1425 + | 49 | SN 037-0016 contingency pavement TBD by RE |
| 1033 | LT/RT | 1625 + | 70 | TO | 1634 + | 11 | SN 037-0017 contingency pavement TBD by RE |
| 988 | LT/RT | 1626 + | 54 | TO | 1634 + | 50 | SN 037-0018 contingency pavement TBD by RE |
| 3684 | TOTAL | | | | | | |

542D5473 PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"

| FOOT | LOCATION | | | | | | REMARKS |
|---|---|---|---|---|---|---|---|
| 54 | RT. STA | 17+ | 43 | TO | 17 + | 97 | FE - Pipe set at 30' LT |
| 54 | RT. STA | 21+ | 40 | TO | 21 + | 94 | FE - Pipe set at 28.5' LT |
| 108 | TOTAL | | | | | | |

54213447 END SECTIONS 12"

| EACH | LOCATION | | REMARKS |
|---|---|---|---|
| 2 | LT STA | 1421+ 26.00 | TBD necessary by RE |
| 2 | RT Sta | 1421 + 25.63 | TBD necessary by RE |
| 4 | TOTAL | | |

54215763 METAL END SECTIONS, EQUIVALENT ROUND-SIZE 18"

| EACH | LOCATION | | REMARKS |
|---|---|---|---|
| 1 | LT. STA. | 17+ 43 | Field Entrance - Ophiem Rd |
| 1 | LT. STA. | 17 + 97 | Field Entrance - Ophiem Rd |
| 1 | LT. STA. | 21+ 40 | Field Entrance - Ophiem Rd |
| 1 | LT. STA. | 21 + 94 | Field Entrance - Ophiem Rd |
| 4 | TOTAL | | |

60108000 PIPE UNDERDRAINS 12"

| FOOT | LOCATION | | REMARKS |
|---|---|---|---|
| 50 | LT STA | 1421+ 26.00 | Inside - 25', Outside 25' (TBD necessary by RE) |
| 65 | RT Sta | 1421 + 25.63 | Inside - 25', Outside 40' (TBD necessary by RE) |
| 115 | TOTAL | | |

60900115 TYPE B INLET BOX, STANDARD 609001

| EACH | LOCATION | | REMARKS |
|---|---|---|---|
| 1 | RT STA | 1421+ 25.68 | Inside Shoulder - use HS 609001 |
| 1 | LT STA | 1421 + 26.11 | Inside Shoulder - use HS 609002 |
| 2 | TOTAL | | |

60900330 TYPE D INLET BOX, STANDARD 609001

| EACH | LOCATION | | REMARKS |
|---|---|---|---|
| 1 | RT STA | 1421+ 25.63 | Outside Shoulder - use HS 609001 |
| 1 | LT STA | 1421 + 26.11 | Outside Shoulder - use HS 609002 |
| 2 | TOTAL | | |

63000130 STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)

| FOOT | LOCATION | | | | | | REMARKS |
|---|---|---|---|---|---|---|---|
| 262.5 | LT. STA. | 18+ | 28.90 | TO | 20 + | 91.44 | Ophiem Rd. |
| 50.0 | LT/RT | 1420+ | 87.68 | TO | 1421+ | 00.18 | I-74 (SN 037-0015) |
| 50.0 | LT/RT | 1418+ | 00.18 | TO | 1418 + | 12.68 | I-74 (SN 037-0016) |
| 50.0 | LT/RT | 1423 + | 39.68 | TO | 1423 + | 52.18 | I-74 (SN 037-0017) |
| 50.0 | LT/RT | 1628 + | 70.45 | TO | 1628 + | 82.95 | I-74 (SN 037-0018) Departing |
| 50.0 | LT/RT | 1631+ | 49.95 | TO | 1631 + | 62.45 | I-74 (SN 037-0018) |
| 512.5 | TOTAL | | | | | | |

63100215 TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)

| EACH | LOCATION | | | | | | REMARKS |
|---|---|---|---|---|---|---|---|
| 2 | LT/RT | 1421+ | 00.18 | TO | 1421 + | 50.18 | SN 037-0015 |
| 2 | LT/RT | 1422+ | 89.68 | TO | 1423+ | 39.68 | SN 037-0016 |
| 2 | LT/RT | 1628 + | 91.87 | TO | 1629 + | 41.87 | SN 037-0017 |
| 2 | LT/RT | 1628 + | 82.95 | TO | 1629 + | 32.95 | SN 037-0018 Departing |
| 2 | LT/RT | 1630 + | 99.95 | TO | 1631+ | 49.95 | SN 037-0018 |
| 10 | TOTAL | | | | | | |

63200310 GUARDRAIL REMOVAL

| FOOT | LOCATION | | | | | | REMARKS |
|---|---|---|---|---|---|---|---|
| 100 | LT/RT | 1421+ | 04 | TO | 1421 + | 54 | SN 037-0015 |
| 100 | LT/RT | 1422+ | 79 | TO | 1423+ | 29 | SN 037-0016 |
| 100 | LT/RT | 1629 + | 58 | TO | 1629 + | 08 | SN 037-0017 |
| 100 | LT/RT | 1629 + | 00 | TO | 1629 + | 50 | SN 037-0018 Departing |
| 100 | LT/RT | 1630 + | 84 | TO | 1631+ | 34 | SN 037-0018 |
| 500 | TOTAL | | | | | | |

63500105 DELINEATORS

| EACH | LOCATION | | REMARKS |
|---|---|---|---|
| 1 | LT. STA. | 18+ 04 | |
| 1 | LT. STA. | 21+ 16 | |
| 2 | TOTAL | | |

66600400 REMOVE AND RE-ERECT RIGHT-OF-WAY MARKERS

| EACH | LOCATION | | | | REMARKS |
|---|---|---|---|---|---|
| 1 | 17+ | 94.00 | @ | 40' RT. | Use if existing marker is disturbed |
| 1 | 20+ | 45.24 | @ | 40' LT. | Use if existing marker is disturbed |
| 1 | 20+ | 79.41 | @ | 40' LT. | Use if existing marker is disturbed |
| 3 | TOTAL | | | | |

66700305 PERMANENT SURVEY MARKERS, TYPE II

| EACH | LOCATION | REMARKS |
|---|---|---|
| 2 | 1422+ 17 | SN 037-0015 - See general notes |
| 2 | 1422 + 17 | SN 037-0016 - See general notes |
| 2 | 1630+ 16 | SN 037-0017 - See general notes |
| 2 | 1630 + 16 | SN 037-0018 - See general notes |
| 8 | TOTAL | |