



ITEM NO.	DESCRIPTION	FOOT	LOCATION	REMARKS
60100935	PIPE DRAINS 10"	10	RT Sta. 1350+15	
		10	TOTAL	
60100945	PIPE DRAINS 12"	10	RT Sta. 1350+70	
		10	TOTAL	
60100955	PIPE DRAINS 15"	10	RT Sta. 1359+05	
		10	TOTAL	
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	LOCATION	REMARKS
		1	RT Sta. 1350+15	
		1	RT Sta. 1350+70	
		1	RT Sta. 1359+05	
		3	TOTAL	
61140000	STORM SEWERS, SPECIAL 8"	FOOT	LOCATION	REMARKS
		80	RT Sta. 1350+15	
		80	TOTAL	
61140100	STORM SEWERS, SPECIAL 10"	FOOT	LOCATION	REMARKS
		55	RT Sta. 1350+70	
		55	TOTAL	
61140200	STORM SEWERS, SPECIAL 12"	FOOT	LOCATION	REMARKS
		55	RT Sta. 1359+05	
		55	TOTAL	
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6' POSTS	CU YD	LOCATION	REMARKS
		187.5	LT Sta. 1349+25.7 to 1351+44.4	Less rail attached to structure
		187.5	RT Sta. 1349+08.7 to 1351+27.4	Less rail attached to structure
		375	TOTAL	
63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	LOCATION	REMARKS
		37.5	LT Sta. 1350+07 to 1350+44.5	3'-1 1/2" MAX. POST SPACING
		37.5	RT Sta. 1350+15.3 to 1350+52.8	3'-1 1/2" MAX. POST SPACING
		75	TOTAL	
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	LOCATION	REMARKS
		1	RT Sta. 1348+59	
		1	LT Sta. 1348+76	
		1	RT Sta. 1351+84	
		1	LT Sta. 1352+01	
		4	TOTAL	
63200310	GUARDRAIL REMOVAL	FOOT	LOCATION	REMARKS
		103	SW SN 037-2003	
		168	SE SN 037-2003	
		168	NW SN 037-2003	
		102	NE SN 037-2003	
		542	TOTAL	
63500105	DELINEATORS	EACH	LOCATION	REMARKS
		2	RT Sta. 1348+17.62	
		1	RT Sta. 1348+59	
		1	LT Sta. 1348+76	
		1	RT Sta. 1351+84	
		1	LT Sta. 1352+01	
		6	TOTAL	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	LOCATION	REMARKS
		2	RT Sta. 1348+00	
		1	RT Sta. 1348+50	
		2	LT & RT Sta. 1349+00	
		2	LT Sta. 1349+75	
		1	RT Sta. 1350+00	
		1	LT Sta. 1350+75	
		2	LT & RT Sta. 1351+00	
		1	LT Sta. 1352+00	
		2	LT & RT Sta. 1353+00	
		1	RT Sta. 1356+00	
		1	RT Sta. 1359+00	
		1	LT Sta. 1360+00	
		2	RT Sta. 1361+00	
		1	LT Sta. 1362+00	
		20	TOTAL	

ITEM NO.	DESCRIPTION	EACH	LOCATION	REMARKS
66700305	PERMANENT SURVEY MARKERS, TYPE II	2	SN 037-2027	
		2	TOTAL	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	LOCATION	REMARKS
		5	SN 037-2027	
		5	TOTAL	
67100100	MOBILIZATION	L SUM	LOCATION	REMARKS
		1	SN 037-2027	
		1	TOTAL	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	LOCATION	REMARKS
		1	SN 037-2027	
		1	TOTAL	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	LOCATION	REMARKS
		1	SN 037-2027	
		1	TOTAL	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	LOCATION	REMARKS
		1	SN 037-2027	
		1	TOTAL	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	LOCATION	REMARKS
		2	SN 037-2027	
		2	TOTAL	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	LOCATION	REMARKS
		1	SN 037-2027	
		1	TOTAL	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	LOCATION	REMARKS
		68	Sta. 1346+73.5 to 1353+80.5	Yellow centerline striping
		396	Sta. 1348+12 to 1361+00	3 applications of yellow centerline striping
		32	RT Sta. 1348+12 to 1352+16	2 applications of white edgeline striping
		32	LT Sta. 1348+14 to 1352+38	2 applications of white edgeline striping
		528	TOTAL	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	LOCATION	REMARKS
		2576	LT & RT Sta. 1348+12 to 1361+00	White edgeline striping
		320	Sta. 1348+12 to 1361+00	Yellow skip-dash centerline striping
		345	Sta. 1348+57.50 to 1352+02.50	Stage I
		660	Sta. 1347+33.50 to 1353+70.50	Stage I
		345	Sta. 1348+57.50 to 1352+02.50	Stage II
		630	Sta. 1347+01.50 to 1353+14.50	Stage II
		4,876	TOTAL	
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	LOCATION	REMARKS
		13	Sta. 1346+73.50	Stage I
		13	Sta. 1353+80.50	Stage I
		26	TOTAL	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	LOCATION	REMARKS
		880	LT & RT Sta. 1348+12 to 1361+00	Edgeline striping
		261	Sta. 1348+12 to 1361+00	Centerline striping
		115	Sta. 1348+57.50 to 1352+02.50	Stage I
		220	Sta. 1347+33.50 to 1353+70.50	Stage I
		115	Sta. 1348+57.50 to 1352+02.50	Stage II
		211	Sta. 1347+01.50 to 1353+14.50	Stage II
		26	Sta. 1346+73.50	Stage II
		26	Sta. 1353+80.50	Stage II
		1,854	TOTAL	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	LOCATION	REMARKS
		675	Sta. 1348+42.5 to 1352+17.5	Stage I
		675	TOTAL	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	LOCATION	REMARKS
		350	Sta. 1348+67.5 to 1352+05	Stage II
		350	TOTAL	

ITEM NO.	DESCRIPTION	FOOT	LOCATION	REMARKS
78001110	PAINT PAVEMENT MARKING - LINE 4"	5152	LT & RT Sta. 1348+12 to 1361+00	White edgeline striping, 2 applications
		640	Sta. 1348+12 to 1361+00	Yellow skip-dash centerline striping, 2 applications
		5,792	TOTAL	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	LOCATION	REMARKS
		4	SN 037-2027, West	
		4	SN 037-2027, East	
		8	TOTAL	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	LOCATION	REMARKS
		1	RT Sta. 1348+59	
		1	LT Sta. 1348+76	
		1	RT Sta. 1351+84	
		1	LT Sta. 1352+01	
		4	TOTAL	
78300100	PAVEMENT MARKING REMOVAL	SO FT	LOCATION	REMARKS
		24.5	Sta. 1346+73.5 to 1349+67.5	Centerline striping, Stage I
		24	Sta. 1350+92.5 to 1353+80.5	Centerline striping, Stage I
		115	RT Sta. 1348+57.5 to 1352+02.5	Edgeline striping, Stage I
		45.5	LT Sta. 1348+57.5 to 1349+94	Edgeline striping, Stage II
		48	LT Sta. 1350+59 to 1352+02.5	Edgeline striping, Stage II
		257	TOTAL	
XX005381	SLOPED HEADWALL, TYPE 1	EACH	LOCATION	REMARKS
		1	RT Sta. 1350+15	
		1	RT Sta. 1350+70	
		1	RT Sta. 1359+05	
		3	TOTAL	
XX006929	REPLACE SECTION CORNER	EACH	LOCATION	REMARKS
		1	RT Sta. 1354+08.73, 28.10'	
		1	TOTAL	
Z0013798	CONSTRUCTION LAYOUT	L SUM	LOCATION	REMARKS
		1	SN 037-2027	
		1	TOTAL	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	LOCATION	REMARKS
		1	Sta. 1348+42.5	Stage I
		1	Sta. 1352+17.5	Stage I
		2	TOTAL	
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	LOCATION	REMARKS
		1	Sta. 1348+80	Stage I
		1	Sta. 1351+80	Stage I
		2	TOTAL	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	LOCATION	REMARKS
		1	Sta. 1348+67.5	Stage II
		1	Sta. 1352+05	Stage II
		2	TOTAL	

FILE NAME =	USER NAME = Fordjd	DESIGNED -	REVISED -
84-shr-schedule03.dgn		DRAWN -	REVISED -
PLOT SCALE = 0.0833' / IN.		CHECKED -	REVISED -
PLOT DATE = Mon Oct 26 14:13:34 2009		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

REVISIED SHEET 10/28/09

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			636	I29 BR	HENRY	42	7
			CONTRACT NO. 64A04				
			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				