

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)	
LOCATION	UNIT
STA. 1241+15.75, 43.1' LT	6
STA. 1241+16.76, 43.7 LT	6
STA. 1241+17.84, 43.7 LT	6
STA. 1241+20.08, 43.6' LT	6
STA. 1241+16.46, 42.0' LT	6
STA. 1241+16.59, 33.9' LT	6
STA. 1241+18.00, 32.3' LT	9
STA. 1241+21.65, 32.6' LT	10
STA. 1241+19.84, 31.8' LT	6
STA. 1241+19.25, 35.2' LT	10
STA. 1241+21.52, 36.2' LT	7
STA. 1241+41.70, 33.0' LT	6
STA. 1241+43.58, 36.1' LT	6
STA. 1241+35.57, 39.9' RT	9
TOTAL	99

20100500 TREE REMOVAL, ACRES	
LOCATION	ACRES
STA 1239+11.00 TO STA 1240+37.18, LT	0.10
STA 1239+39.28 TO STA 1241+39.89, RT	0.08
TOTAL	0.18

20101000 TEMPORARY FENCE	
LOCATION	FOOT
RECREATION TRAIL	
STA. 10+21.37 TO STA. 10+86.72, LT	65
STA. 10+21.82 TO STA. 10+86.46, RT	65
STA. 11+77.47 TO STA. 12+78.31, RT	100
STA. 11+77.69 TO STA. 12+76.82, LT	100
TOTAL	330

44000600 SIDEWALK REMOVAL	
LOCATION	SQ. FT.
STA. 10+88.59 TO STA. 11+51.31	618.6
TOTAL	619

44000100 PAVEMENT REMOVAL	
LOCATION	SQ. YD.
STA. 1240+98.50 - 1241+09.00	29.5
STA. 1242+62.11 - 1243+02.00	112.0
TOTAL	142

40600990 TEMPORARY RAMP	
LOCATION	SQ. YD.
STA. 1238+93.00 - 1238+98.00	14.4
STA. 1245+71.00 - 1245+76.00	14.4
STA. 1240+93.50 - 1240+98.50	14.4
STA. 1243+02.00 - 1243+07.00	14.4
TOTAL	58

25100630 EROSION CONTROL BLANKET	
LOCATION	SQ YD
STA. 1238+93.00 TO 1245+76.00	4352
TOTAL	4352

25000210 SEEDING, CLASS 2A	
LOCATION	ACRE
STA. 1238+93.00 TO 1245+76.00	0.90
TOTAL	0.90

28000400 PERIMETER EROSION BARRIER	
LOCATION	FOOT
ROADWAY	
STA. 1238+92.38 TO STA. 1241+25.72, LT	273
STA. 1239+20.12 TO STA. 1241+21.30, RT	221
STA. 1242+49.07 TO STA. 1245+76.07, LT	356
STA. 1242+41.78 TO STA. 1245+76.20, RT	342
PEDESTRIAN TRAIL	
STA. 10+49.34 TO STA. 11+82.40, RT	137
TOTAL	1329

35101400 AGGREGATE BASE COURSE, TYPE B	
LOCATION	TON
STA 1238+58.56 TO STA 1241+19.50, RT	76.8
STA 1242+74.50 TO STA 1245+76.00, RT	87.1
TOTAL	164

66700305 PERMANENT SURVEY MARKERS, TYPE II	
LOCATION	EACH
ENTIRE PROJECT	1
TOTAL	1

42001420 BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	
LOCATION	SQ. YD.
STA. 1240+98.50 - 1241+04.50	27.9
STA. 1242+89.50 - 1243+02.00	58.1
TOTAL	86

X0325864 BRIDGE APPROACH PAVEMENT REMOVAL	
LOCATION	SQ. YD.
STA. 1241+09.00 - 1241+29.81	72.7
STA. 1242+41.58 - 1242+62.11	72.2
TOTAL	145

42400300 PORTLAND CEMENT SIDEWALK 6 INCH	
LOCATION	SQ. FT.
RECREATIONAL TRAIL	1228.6
TOTAL	1229

BITUMINOUS SCHEDULE																		
RT. STA.	LT. STA.	RT. STA.	LT. STA.	RT. STA.	LT. STA.	RT. STA.	LT. STA.	REMARKS	LENGTH	PROPOSED SURFACE		40600625 LEVELING BINDER (MACHINE METHOD), N50	40603310 HMA SURFACE COURSE, MIX "C", N50	40603335 HMA SURFACE COURSE, MIX "D", N50				
										WIDTH	SQ YD	TON	TON	TON				
RT. STA. 1238		+		59	-			1241	+	19	SHOULDER	261	VAR.	303.0			42.4	
LT. STA. 1238		+		93	-			1241	+	19	SHOULDER	227	VAR.	270.5			37.9	
RT. STA. 1242		+		74	-			1245	+	76	SHOULDER	302	VAR.	348.2			48.7	
LT. STA. 1242		+		74	-			1245	+	76	SHOULDER	302	VAR.	347.2			48.6	
STA. 1238		+		93	-			1240	+	98	MAINLINE	206	26	593.7		33.2		49.9
STA. 1243		+		2	-			1245	+	76	MAINLINE	274	26	791.6		44.3		66.5
TOTALS												78		178		116		

70106700 TEMPORARY RUMBLE STRIP	
LOCATION	EACH
ENTIRE PROJECT	3
TOTAL	3

70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS	
LOCATION	EACH
ENTIRE PROJECT	1
TOTAL	1

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STA. 1239+69.46, RT	1
STA. 1243+92.81, RT	1
TOTAL	2

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STA. 1239+31.95, LT	1
STA. 1244+47.57, LT	1
TOTAL	2

70400100 TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
STA. 1239+31.95 TO STA. 1244+47.57	512.5
TOTAL	512.5

44000158 HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	
LOCATION	SQ. YD.
STA. 1238+93.00 TO STA. 1240+98.50	575.6
STA. 1243+02.00 TO STA. 1245+76.00	769.7
TOTAL	1345

70400200 RELOCATE TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
STA. 1239+69.46 TO STA. 1243+92.81	425.0
TOTAL	425.0

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
STA. 1238+93.00 TO STA. 1245+76.00	10
TOTAL	10

78100100 RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
STA. 1238+93.00 TO STA. 1240+98.50	3
STA. 1243+02.00 TO STA. 1245+76.00	4
TOTAL	7

X0712400 TEMPORARY PAVEMENT	
LOCATION	SQ. YD.
LT. STA. 1239+50.00 - 1241+10.00	72.1
LT. STA. 1242+62.06 - 1244+13.77	67.8
TOTAL	140

X0919000 TEMPORARY PAVEMENT REMOVAL	
LOCATION	SQ. YD.
LT. STA. 1239+50.00 - 1241+10.00	72.1
LT. STA. 1242+62.06 - 1244+13.77	67.8
TOTAL	140

48203019 HOT-MIX ASPHALT SHOULDERS, 5 1/2"	
LOCATION	SQ. YD.
STA 1238+58.56 TO STA 1241+19.50, RT	303.0
STA 1238+93.00 TO STA 1241+19.50, LT	270.5
STA 1242+74.50 TO STA 1245+76.00, RT	348.2
STA 1242+74.50 TO STA 1245+76.00, LT	347.2
TOTAL	1269

X0325519 DRAIN FOR AGGREGATE BASE COURSE	
LOCATION	SQ. FT.
STA. 1240+98.50, LT	0.83
STA. 1240+98.50, RT	1.57
TOTAL	2

20201400 SUB-BASE GRANULAR MATERIAL, TYPE A	
LOCATION	TON
STA. 1240+98.50, LT	36.9
STA. 1240+98.50, RT	8.2
TOTAL	45

78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	
LOCATION	EACH
STA. 1240+98.50 TO STA. 1243+02.00	3
TOTAL	3