

SEEDING SCHEDULE

SEEDING SCHEDULES				21101615 TOPSOIL FURNISH AND PLACE, 4" (SQ YD)	25000100 SEEDING CLASS 1 (ACRES)	25000210 SEEDING CLASS 2A (ACRES)	25000310 SEEDING CLASS 4 (ACRES)	25000350 SEEDING CLASS 7 (ACRES)	25100630 EROSION CONTROL BLANKET (SQ YD)	25000750 MOWING (ACRE)	25000400 NITROGEN FERT. NUTR. (POUND)	25000500 PHOSPHORUS FERT. NUTR. (POUND)	25000600 POTASSIUM FERT. NUTR. (POUND)
LOCATION													
STATION	TO	STATION	OFFSET										
549 + 80	TO	551 + 58	LT	281		0.06			281	0.06	5	5	5
551 + 00	TO	562 + 83	RT	4487		0.46	0.46		4487	0.93	83	83	83
551 + 68	TO	552 + 38	LT	136	0.03				136	0.03	3	3	3
552 + 55	TO	560 + 38	LT	3473		0.48	0.24		3473	0.72	65	65	65
560 + 62	TO	568 + 52	LT	5062		0.94	0.10		5062	1.05	94	94	94
563 + 08	TO	569 + 89	RT	3476		0.65	0.07		3476	0.72	65	65	65
586 + 26	TO	587 + 16	RT	122	0.03				122	0.03	2	2	2
569 + 21	TO	575 + 78	LT	3688		0.69	0.08		3688	0.76	69	69	69
570 + 49	TO	576 + 54	RT	2706		0.50	0.06		2706	0.56	50	50	50
576 + 24	TO	576 + 87	LT	95		0.02			95	0.02	2	2	2
576 + 78	TO	579 + 84	RT	1019		0.21			1019	0.21	19	19	19
577 + 10	TO	580 + 05	LT	750		0.15			750	0.15	14	14	14
579 + 84	TO	582 + 48	RT	249	0.05				249	0.05	5	5	5
580 + 41	TO	590 + 30	LT	2261		0.42	0.05		2261	0.47	42	42	42
582 + 73	TO	584 + 62	RT	201	0.04				201	0.04	4	4	4
584 + 78	TO	585 + 95	RT	143	0.03				143	0.03	3	3	3
587 + 47	TO	588 + 62	RT	137	0.03				137	0.03	3	3	3
588 + 92	TO	589 + 62	RT	45	0.01				45	0.01	1	1	1
589 + 94	TO	590 + 44	RT	53	0.01				53	0.01	1	1	1
590 + 54	TO	591+62	LT	320		0.03	0.03		320	0.07	6	6	6
591 + 83	TO	592 + 75	LT	210		0.02	0.02		210	0.04	4	4	4
554 + 00	TO	569 + 00	LT	2872				0.75	2872	0.75			
572 + 00	TO	580 + 00	LT	871				0.18	871	0.18			
581 + 00	TO	592 + 00	LT	1210				0.25	1210	0.25			
			TOTAL	33,867	0.2	4.6	1.1	1.2	33,867	7.2	538	538	538

FILE NAME =	H:\PROJECTS\2945\DGNS\09205507\2055075	USER NAME = #USER#	DESIGNED - AAF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US ROUTE 20 SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	CH.dgn		DRAWN - AAF	REVISED -			301	21 VBR	STEPHENSON	112	11	
	PLOT SCALE = 20,0000' / IN.		CHECKED - BAP	REVISED -			CONTRACT NO. 64D15					
	PLOT DATE = 8/7/2009		DATE - 8/7/2009	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

HOH	HARRY O. HEYER ASSOCIATES, INC. DESIGN AND CONSULTING ENGINEERS 55 East Jackson Blvd. Suite 800 Chicago, IL 60604 312-542-8131	PROJECT NUMBER 2945
------------	---	-------------------------------