

SUMMARY OF QUANTITIES

| PAY CODE # | LONG DESCRIPTION | UNITS | QUANTITIES | 100% STATE | |
|------------|--|--------|------------|-----------------|-------------------|
| | | | | ROADWAY J000 | BRIDGE SFTY-2A |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 45.00 | 45.00 | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 150.00 | 150.00 | |
| 44000157 | HOT-MIX ASPHALT SURFACE REMOVAL, 2" | SQ YD | 374.00 | 374.00 | |
| 48203005 | HOT-MIX ASPHALT SHOULDERS, 2" | SQ YD | 374.00 | 374.00 | |
| 50102400 | CONCRETE REMOVAL | CU YD | 427.20 | | 427.20 |
| 50104650 | SLOPE WALL REMOVAL | SQ YD | 11.70 | | 11.70 |
| 50157300 | PROTECTIVE SHIELD | SQ YD | 6,123.00 | | 6,123.00 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 611.60 | | 611.60 |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 1,479.00 | | 1,479.00 |
| 50300300 | PROTECTIVE COAT | SQ YD | 2,224.00 | | 2,224.00 |
| 50500105 | FURNISHING AND ERECTING STRUCTURAL STEEL | L SUM | 1.00 | | 1.00 |
| 50500505 | STUD SHEAR CONNECTORS | EACH | 4,312.00 | | 4,312.00 |
| 50501110 | STRUCTURAL STEEL REMOVAL | POUND | 155,620.00 | | 155,620.00 |
| 50501130 | STRUCTURAL STEEL REPAIR | POUND | 211,520.00 | | 211,520.00 |
| 50606701 | CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1 | L SUM | 1.00 | | 1.00 |
| 50800105 | REINFORCEMENT BARS | POUND | 7,106.00 | 7,106.00 | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 167,320.00 | | 167,320.00 |
| 51100100 | SLOPE WALL 4 INCH | SQ YD | 11.70 | | 11.70 |
| 52000110 | PREFORMED JOINT STRIP SEAL | FOOT | 1,636.00 | | 1,636.00 |
| 52100010 | ELASTOMERIC BEARING ASSEMBLY, TYPE 1 | EACH | 100.00 | | 100.00 |
| 59200100 | BRIDGE WASHING | EACH | 1.00 | | 1.00 |
| 63700275 | CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT | FOOT | 1,398.00 | 1,398.00 | |
| 63700805 | CONCRETE BARRIER TRANSITION | FOOT | 20.00 | 20.00 | |
| 63801205 | TEMPORARY MODULAR GLARE SCREEN | FOOT | 1,355.00 | 1,355.00 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 16.00 | | 16.00 |
| 67100100 | MOBILIZATION | L SUM | 1.00 | | 1.00 |
| 70100205 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 | EACH | 3.00 | 3.00 | |
| 70100207 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 | EACH | 2.00 | 2.00 | |
| 70100410 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701416 | EACH | 1.00 | 1.00 | |
| 70100420 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701411 | EACH | 1.00 | 1.00 | |
| 70100820 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701451 | L SUM | 1.00 | 1.00 | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 172.00 | 172.00 | |

• SPECIALITY ITEMS

△ REVISED 10/28/09

| | | | | | | | | | | | |
|--|-----------------------|------------|-----------|---|------------------------------|---------------------------|-------------|-------------|--------------|-----------|--|
| FILE NAME = | USER NAME = cushmanbw | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| cd:\pwork\FW\DOT\CUSHMANBW\d0149192\09409-shr-schedule.dgn | | DRAWN - | REVISED - | | | 80 | (81-1B) M-4 | ROCK ISLAND | 75 | 3 | |
| PLOT SCALE = 50.0000' / IN. | | CHECKED - | REVISED - | | | CONTRACT NO. 64F31 | | | | | |
| PLOT DATE = Thu Sep 17 13:13:51 2009 | | DATE - | REVISED - | | | ILLINOIS FED. AID PROJECT | | | | | |