

SCHEDULE OF QUANTITIES

25100630	EROSION CONTROL BLANKET					
	SQ_YD	LOCATION				
	45.00	16 + 69	to	17 + 20	SLOPE WALL - STATE OF IOWA	
	45.00	TOTAL				
28000400	PERIMETER EROSION BARRIER					
	EQOI	LOCATION				
	150.00	16 + 69	to	17 + 20	SLOPE WALL - STATE OF IOWA	
	150.00	TOTAL				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"					
	SQ_YD	LOCATION				REMARKS
	373.33	1492 + 00	to	1497 + 60	6' wide, see special provision	
	373.33	TOTAL				
48203005	HOT-MIX ASPHALT SHOULDERS, 2"					
	SQ_YD	LOCATION				REMARKS
	373.33	1492 + 00	to	1497 + 60	SEE GENERAL NOTES FOR MIX DESIGN	
	373.33	TOTAL				
50800105	REINFORCEMENT BARS					
	POUNDS	LOCATION				REMARKS
	7106.00	1492 + 00		1497 + 60	State of IOWA barrier wall	
	7,106.00	TOTAL				
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT					
	FOOT	LOCATION				REMARKS
		STAGE THREE				
	1397.50	51 + 72		65 + 69.50		
	1,397.50	TOTAL				
63700805	CONCRETE BARRIER TRANSITION					
	FOOT	LOCATION				REMARKS
		STAGE THREE				
	20.00	51 + 52		51 + 72.00		
	20.00	TOTAL				
63801205	TEMPORARY MODULAR GLARE SCREEN					
	FOOT	LOCATION				REMARKS
		STAGE TWO				
	600.00	51 + 50		57 + 50.00		
	755.00	78 + 00		85 + 00		
	1355.0	TOTAL				
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"					
	EQOI	LOCATION				REMARKS
		EASTBOUND				
	2225.00	1453 + 00	to	1475 + 25	Stage I - Yellow Inside	
	1025.00	75 + 25	to	85 + 50	Stage I - White CL	
	770.00	77 + 80	to	85 + 50	Stage I - White outside	
	770.00	77 + 80	to	85 + 50	Stage I - Yellow Inside	
	1320.00	77 + 80	to	91 + 00	Stage I - Yellow, Scenic overlook ramp	
	1440.00	1483 + 00	to	1497 + 40	Stage II - Yellow Inside	
	601.00	55 + 39	to	61 + 40	Stage II - White outside	
	1026.00	75 + 24	to	85 + 50	Stage II - White CL	
	770.00	77 + 80	to	85 + 50	Stage II - White outside	
	770.00	77 + 80	to	85 + 50	Stage II - Yellow Inside	
	1320.00	77 + 80	to	91 + 00	Stage II - Yellow, Scenic overlook ramp	
	7311.00	1483 + 00	to	75 + 00	Stage III - Yellow Inside	
	19348.00	Sub-Totd				
		WESTBOUND				
	2872.00	1497 + 00	to	44 + 61	Stage I - White outside	
	3538.00	47 + 62	to	83 + 00	Stage I - Yellow Inside	
	1618.00	77 + 82	to	94 + 00	Stage I - White outside	
	1425.00	61 + 65	to	75 + 90	Stage II - White outside	
	2135.00	61 + 65	to	83 + 00	Stage II - Yellow Inside	
	1618.00	77 + 82	to	94 + 00	Stage II - White outside	
	6891.00	1491 + 20	to	79 + 00	Stage III - Yellow Inside	
	20097.00	Sub-Totd				
		MISC				
	600.00	US 67 Eastbound			Stage I - Yellow	
	300.00	US 67 Westbound			Stage I - White	
	550.00	IL 84 Eastbound			Stage II - White	
	525.00	IL 84 Westbound			Stage II - Yellow	
	1975.00	Sub-Totd				
	41,420.0	TOTAL				

70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"					
	EQOI	LOCATION				REMARKS
		EASTBOUND				
	96.50	51 + 53	to	55 + 39	Stage II - Turkey tracks, 2' long, 6' between - White	
	96.50	TOTAL				
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"					
	EQOI	LOCATION				REMARKS
		WESTBOUND				
	163.93	63 + 50	to	73 + 20	Stage I - Diagonals, 16.9' long, 100' between - White	
	163.93	63 + 50	to	73 + 20	Stage II - Diagonals, 16.9' long, 100' between - White	
	163.93	63 + 50	to	73 + 20	Stage III - Diagonals, 16.9' long, 100' between - White	
	491.79	TOTAL				
70400100	TEMPORARY CONCRETE BARRIER					
	EQOI	LOCATION				REMARKS
		STAGE THREE				
	5,959.5	1487 + 07		68 + 50	EASTBOUND	
	6,447.0	1491 + 50		72 + 00	WESTBOUND	
	12,406.5	Sub-Totd				
		STAGE TWO				
	200.0	1496 + 05		1497 + 80	IN STATE OF IOWA	
	4,962.5	1491 + 88		73 + 00		
	1,260.0	73 + 00		85 + 00		
	6,422.5	Sub-Totd				
	18,829.0	TOTAL				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER					
	EQOI	LOCATION				REMARKS
		STAGE TWO				
	400.0	1486 + 20		1490 + 20		
	330.0					
	730.0	TOTAL				
X0321750	REMOVE TEMPORARY CONCRETE BARRIER, STATE OWNED					
	EQOI	LOCATION				REMARKS
		STAGE ONE				
	75.0				ON BRIDGE	
	62.5				ON BRIDGE	
		STAGE THREE				
	593.0	1491 + 88		1497 + 80		
	1,950.0	47 + 50		73 + 00		
	2,680.5	TOTAL				
78008210	POLYUREA PAVEMENT MARKING TYPE I • LINE 4"					
	EQOI	LOCATION				REMARKS
		EASTBOUND				
	5780.00	1440 + 00	to	1497 + 80	Left edge line - Yellow	
	2505.00	1440 + 00	to	1465 + 05	Right edge line - White	
	1731.00	1474 + 00	to	1491 + 31	Right edge line - White	
	1467.00	51 + 53	to	66 + 20	Left edge line - Yellow	
	821.00	57 + 99	to	66 + 20	Right edge line - White	
	1930.00	66 + 20	to	85 + 50	Left edge line - Yellow	
	163.00	66 + 20	to	67 + 83	Right edge line - White	
	14397.00	Sub-Totd				
		WESTBOUND				
	780.00	1440 + 00	to	1497 + 80	Left edge line - Yellow	
	182.00	1490 + 00	to	1491 + 82	Right edge line - White	
	1467.00	51 + 53	to	66 + 20	Left edge line - Yellow	
	368.00	62 + 52	to	66 + 20	Right edge line - White	
	1930.00	66 + 20	to	85 + 50	Left edge line - Yellow	
	697.00	66 + 20	to	73 + 17	Right edge line - White	
	451.00	80 + 99	to	85 + 50	Right edge line - White	
	5875.00	Sub-Totd				
	20,272.0	TOTAL				

▲ REVISSED SHEET 10/28/09

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\pwork\pwork\DOT\CUSHMANBW\d0149192\d0149192-sht-schedule.dgn	DRAWN -	REVISED -	80			(81-1B) M-4	ROCK ISLAND	75	9	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 64F31							
PLOT DATE = Tue Oct 20 16:46:34 2009	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
					SCALE:	SHEET NO. OF SHEETS		STA. TO STA.		