

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	1-HBR-2F	WINNEBAGO	29	7
FED. ROAD DIST. NO. 7	ILLINOIS	CONTRACT NO. 64F62		

SHEET NO. 5  
27 SHEETS

BEAM 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. S. Abut.	98+89.82	15.00	787.33	787.33
⊕ Brg. S. Abut.	98+92.95	15.00	787.35	787.35
A	99+02.95	15.00	787.40	787.41
B	99+12.95	15.00	787.45	787.46
C	99+22.95	15.00	787.50	787.51
⊕ Brg. Pier 1	99+36.95	15.00	787.57	787.57
D	99+46.95	15.00	787.62	787.63
E	99+56.95	15.00	787.67	787.69
F	99+66.95	15.00	787.72	787.74
G	99+76.95	15.00	787.77	787.79
H	99+86.95	15.00	787.82	787.82
⊕ Brg. Pier 2	99+95.45	15.00	787.86	787.86
I	100+05.45	15.00	787.91	787.92
J	100+15.45	15.00	787.96	787.98
K	100+25.45	15.00	788.01	788.04
L	100+35.45	15.00	788.06	788.08
M	100+45.45	15.00	788.11	788.12
⊕ Brg. Pier 3	100+53.95	15.00	788.15	788.15
N	100+63.95	15.00	788.20	788.21
O	100+73.95	15.00	788.25	788.26
P	100+83.95	15.00	788.30	788.31
⊕ Brg. N. Abut.	100+97.95	15.00	788.37	788.37
Bk. N. Abut.	101+01.09	15.00	788.39	788.39

DESIGNED	GUN / OAO
CHECKED	FCO
DRAWN	TCS / GUN
CHECKED	FCO

FOR INFORMATION ONLY  
TOP OF SLAB ELEVATIONS  
MERIDIAN ROAD OVER US 20  
F.A.P. 301 (US 20) - SEC. 1-HBR-2F  
WINNEBAGO COUNTY  
STATION 100+00  
STRUCTURE NO. 101-0096