

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QTY	ROADWAY 1000 90% FED. 10% STATE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	8	8
20400800	FURNISHED EXCAVATION	CU YD	28984	28984
21400100	GRADING AND SHAPING DITCHES	FOOT	600	600
* 25000300	SEEDING, CLASS 3	ACRE	0.81	0.81
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72.9	72.9
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72.9	72.9
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72.9	72.9
* 25101005	HEAVY DUTY EXCELSIOR BLANKET	SQ YD	3214	3214
* 25100115	MULCH, METHOD 2	ACRE	0.15	0.15
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	243	243
28000300	TEMPORARY DITCH CHECKS	EACH	2	2
28000400	PERIMETER EROSION BARRIER	FOOT	681	681
28000500	INLET AND PIPE PROTECTION	EACH	2	2
28100107	STONE RIPRAP, CLASS A4	SQ YD	5	5
28200200	FILTER FABRIC	SQ YD	5	5
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	12	12
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SQ YD	1904	1904
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	224	224
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	800	800
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	190	190
44000300	CURB REMOVAL	FOOT	240	240
44000186	HOT-MIX ASPHALT SURFACE REMOVAL, 9"	SQ YD	1626	1626
48203045	HOT-MIX ASPHALT SHOULDERS, 12"	SQ YD	696	696
48101200	AGGREGATE SHOULDERS, TYPE B	TON	60	60
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2	2
50300225	CONCRETE STRUCTURES	CU YD	2.85	2.85
35501351	HOT-MIX ASPHALT BASE COURSE, 17"	SQ YD	880	880

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QTY	ROADWAY 1000 90% FED. 10% STATE
50800105	REINFORCEMENT BARS	POUND	1548	1548
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1
550A1920	STORM SEWERS, CLASS A, TYPE 7 36"	FOOT	293	293
550A1950	STORM SEWERS, CLASS A, TYPE 7 48"	FOOT	315	315
X0326694	PLUG EXISTING STORM SEWERS	CU YD	96.3	96.3
55101600	STORM SEWER REMOVAL 36"	FOOT	240	240
60615910	PAVED DITCH, TYPE A-22	FOOT	233	233
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	432	432
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	930	930
63500105	DELINEATORS	EACH	2	2
64200105	SHOULDER RUMBLE STRIP	FOOT	2620	2620
66500105	WOVEN WIRE FENCE, 4'	FOOT	145	145
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	270	270
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	387	387
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1
67100100	MOBILIZATION	L SUM	1	1
70101005	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	EACH	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	314	314
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3140	3140
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	394	394
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2971	2971
70400100	TEMPORARY CONCRETE BARRIER	FOOT	860	860
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	764	764
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3140	3140
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	394	394
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	40	40
* 78200405	GUARDRAIL MARKERS	EACH	6	6
78300105	PAVEMENT MARKING REMOVAL	FOOT	4774	4774
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	40	40
X0325969	PORTABLE VEHICLE MOUNTED, CHANGEABLE MESSAGE BOARD	CAL DA	100	100
X7030100	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III	FOOT	11240	11240
X7010820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	L SUM	1	1
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	953	953
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2

*SPECIALTY ITEMS

REVISOR 10/22/09

FILE NAME =	USER NAME = braboypc	DESIGNED -	REVISOR -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\dot\braboypc\dms64344\038862-SHT-PLNPRF.dgn	DRAWN -	REVISOR -	.57			I(27-DVBR & VBR-11DM	FORD	28	3	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISOR -	CONTRACT NO. 66862							
PLOT DATE = Aug 27, 2009 - 09:54:32 AM	DATE -	REVISOR -	ILLINOIS FED. AID PROJECT							