



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 23, 2009

SUBJECT: FAI Route 80
Project ACBRF-ACNHI-080-2 (065) 062
Section 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]
Bureau County
Contract No. 66908
Item No. 175, November 6, 2009 Letting
Addendum C

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page iii of the Table of Contents to the Special Provisions.
3. Revised pages 9 & 10 of the Special Provisions.
4. Added page 200 to the Special Provisions.
5. Revised sheets 3, 4, 7, 11, 22, 23 & 49 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: George F. Ryan, Region 2, District 3; Bill Frey; R. E. Anderson; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66908

State Job # - C-93-049-09
 PPS NBR - 3-08006-0090
 County Name - BUREAU- -
 Code - 11 - -
 District - 3 - -
 Section Number - 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]

Project Number
 ACBRF-ACNHI-0802/065/062

Route
 FAI 80

*** REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0321468	PLUG EX DK DRAINS	EACH	14.000				
X0322729	MATL TRANSFER DEVICE	TON	23,876.000				
X0323644	PAVT MKING GROOVING	FOOT	6,896.000				
X0323830	DRAINAGE SCUPPR DS-11	EACH	17.000				
X0325305	STR REP CON DP = < 5	SQ FT	3.000				
X0325969	PORT VHMNT CH MSS BRD	CAL DA	200.000				
X0326208	ALTERNATE RTE SIGNING	L SUM	1.000				
X0326215	REMOVE TEMP LTG SYSTM	L SUM	1.000				
X4020800	AGG SURF CSE B 12	SQ YD	1,200.000				
X5020501	UNWAT STR EX PROT L1	EACH	1.000				
X5020502	UNWAT STR EX PROT L2	EACH	1.000				
X5020503	UNWAT STR EX PROT L3	EACH	1.000				
X5020504	UNWAT STR EX PROT L4	EACH	1.000				
X7010805	TR C-PROT 701401 SPL	L SUM	1.000				
X7030100	WET TEMP PM TAPE T3	FOOT	329,582.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66908

State Job # - C-93-049-09
 PPS NBR - 3-08006-0090
 County Name - BUREAU- -
 Code - 11 - -
 District - 3 - -
 Section Number - 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]

Project Number
 ACBRF-ACNHI-0802/065/062

Route
 FAI 80

*** REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X7200201	WIDTH RESTRICT SIGN	L SUM	1.000				
X8410102	TEMP LIGHTING SYSTEM	L SUM	1.000				
X8410118	MAINT TEMP LIGHT SYS	L SUM	1.000				
*** DELETED							
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0016200	DECK SLAB REP (PART)	SQ YD	56.100				
Z0017100	DOWEL BARS	EACH	360.000				
Z0018800	DRAINAGE SYSTEM	L SUM	1.000				
Z0030150	IMPACT ATTEN NRD TL3	EACH	20.000				
Z0075300	TIE BARS	EACH	40.000				
Z0076600	TRAINEES	HOUR	4,000.000		0.800		3,200.000
20100110	TREE REMOV 6-15	UNIT	1,944.000				
20100210	TREE REMOV OVER 15	UNIT	160.000				
20101400	NITROGEN FERT NUTR	POUND	648.000				
20101500	PHOSPHORUS FERT NUTR	POUND	648.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66908

State Job # - C-93-049-09
 PPS NBR - 3-08006-0090
 County Name - BUREAU- -
 Code - 11 - -
 District - 3 - -
 Section Number - 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]

Project Number
 ACBRF-ACNHI-0802/065/062

Route
 FAI 80

*** REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20101600	POTASSIUM FERT NUTR	POUND	648.000				
20200100	EARTH EXCAVATION	CU YD	1,242.000				
20201200	REM & DISP UNS MATL	CU YD	7,675.000				
20400800	FURNISHED EXCAV	CU YD	66,490.000				
20700400	POROUS GRAN EMB SPEC	CU YD	1,218.000				
25000300	SEEDING CL 3	ACRE	9.750				
25100635	HD EROS CONTR BLANKET	SQ YD	40,341.000				
28000250	TEMP EROS CONTR SEED	POUND	720.000				
28000300	TEMP DITCH CHECKS	EACH	32.000				
28000400	PERIMETER EROS BAR	FOOT	18,144.000				
28100107	STONE RIPRAP CL A4	SQ YD	8,383.000				
28100109	STONE RIPRAP CL A5	SQ YD	2,528.000				
28200200	FILTER FABRIC	SQ YD	11,177.000				
*** DELETED							
*** DELETED							

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66908

State Job # - C-93-049-09
 PPS NBR - 3-08006-0090
 County Name - BUREAU- -
 Code - 11 - -
 District - 3 - -
 Section Number - 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]

Project Number
 ACBRF-ACNHI-0802/065/062

Route
 FAI 80

*** REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*** 35100500	AGG BASE CSE A 6	SQ YD	6,182.000				
*** 35101100	AGG BASE CSE A 12	SQ YD	5,289.000				
40600115	P BIT MATLS PR CT	GALLON	31,493.000				
40600300	AGG PR CT	TON	418.000				
40600400	MIX CR JTS FLANGEWYS	TON	57.000				
40600555	LEV BIND HM N105	TON	94.000				
40600845	P LEV BIND MM N90	TON	1,050.000				
40600895	CONSTRUC TEST STRIP	EACH	1.000				
40600982	HMA SURF REM BUTT JT	SQ YD	1,068.000				
40600985	PCC SURF REM BUTT JT	SQ YD	2,520.000				
*** 40603085	HMA BC IL-19.0 N70	TON	1,185.000				
*** 40603240	P HMA BC IL19.0 N90	TON	3,776.000				
*** 40603245	P HMA BC IL19.0 N105	TON	814.000				
40603310	HMA SC "C" N50	TON	8,143.000				
*** 40603550	P HMA SC "D" N105	TON	24,217.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66908

State Job # - C-93-049-09
 PPS NBR - 3-08006-0090
 County Name - BUREAU- -
 Code - 11 - -
 District - 3 - -
 Section Number - 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]

Project Number
 ACBRF-ACNHI-0802/065/062

Route
 FAI 80

*** REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42001200	PAVEMENT FABRIC	SQ YD	54.000				
*** 42001420	BR APPR PVT CON (PCC)	SQ YD	267.000				
*** 42001430	BR APPR PVT CON (FLX)	SQ YD	53.000				
*** DELETED							
*** DELETED							
*** DELETED							
44000100	PAVEMENT REM	SQ YD	5,477.000				
44000182	HMA SURF REM 8	SQ YD	32,455.000				
*** 44000196	HMA SURF REM SPL	SQ YD	2,534.000				
44000198	HMA SURF REM VAR DP	SQ YD	10,668.000				
44001114	HMA SURFACE REM (ASB)	SQ YD	4,920.000				
44004250	PAVED SHLD REMOVAL	SQ YD	1,841.000				
44201053	CL B PATCH T4 17	SQ YD	54.000				
44201055	CL B PATCH T2 17	SQ YD	183.000				
44201057	CL B PATCH T3 17	SQ YD	48.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66908

State Job # - C-93-049-09
 PPS NBR - 3-08006-0090
 County Name - BUREAU- -
 Code - 11 - -
 District - 3 - -
 Section Number - 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]

Project Number
 ACBRF-ACNHI-0802/065/062

Route
 FAI 80

*** REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44213200	SAW CUTS	FOOT	996.000				
48101200	AGGREGATE SHLDS B	TON	5,429.000				
48203021	HMA SHOULDERS 6	SQ YD	3,782.000				
48203029	HMA SHOULDERS 8	SQ YD	32,455.000				
*** 48203045	HMA SHOULDERS 12	SQ YD	5,533.000				
*** DELETED							
50100100	REM EXIST STRUCT	EACH	8.000				
50157300	PROTECTIVE SHIELD	SQ YD	834.000				
50200100	STRUCTURE EXCAVATION	CU YD	2,497.000				
50300100	FLOOR DRAINS	EACH	102.000				
50300225	CONC STRUCT	CU YD	1,969.000				
50300255	CONC SUP-STR	CU YD	3,209.000				
50300260	BR DECK GROOVING	SQ YD	6,695.000				
50300280	CONCRETE ENCASEMENT	CU YD	61.000				
50300300	PROTECTIVE COAT	SQ YD	8,404.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66908

State Job # - C-93-049-09
 PPS NBR - 3-08006-0090
 County Name - BUREAU- -
 Code - 11 - -
 District - 3 - -
 Section Number - 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]

Project Number
 ACBRF-ACNHI-0802/065/062

Route
 FAI 80

*** REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50300530	FLOOR DRAIN EXTENSION	EACH	14.000				
50400745	F&E PPC BULB T-BM 72	FOOT	2,608.000				
50400805	F & E P P CON I-BM 36	FOOT	2,358.000				
50400905	F & E P P CON I-BM 42	FOOT	4,599.000				
50800205	REINF BARS, EPOXY CTD	POUND	863,780.000				
50800515	BAR SPLICERS	EACH	504.000				
51100100	SLOPE WALL 4	SQ YD	920.000				
51201600	FUR STL PILE HP12X53	FOOT	4,486.000				
51201800	FUR STL PILE HP14X73	FOOT	13,393.000				
51202305	DRIVING PILES	FOOT	17,879.000				
51203600	TEST PILE ST HP12X53	EACH	8.000				
51203800	TEST PILE ST HP14X73	EACH	20.000				
51205200	TEMP SHT PILING	SQ FT	523.000				
51500100	NAME PLATES	EACH	6.000				
52100010	ELAST BEARING ASSY T1	EACH	56.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66908

State Job # - C-93-049-09
 PPS NBR - 3-08006-0090
 County Name - BUREAU- -
 Code - 11 - -
 District - 3 - -
 Section Number - 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]

Project Number
 ACBRF-ACNHI-0802/065/062

Route
 FAI 80

*** REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
52100020	ELAST BEARING ASSY T2	EACH	28.000				
52100530	ANCHOR BOLTS 1 1/4	EACH	168.000				
52100540	ANCHOR BOLTS 1 1/2	EACH	16.000				
54215547	MET END SEC 12	EACH	8.000				
58700300	CONCRETE SEALER	SQ FT	820.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	549.000				
59300100	CONTR LOW-STRENG MATL	CU YD	2.500				
60100945	PIPE DRAINS 12	FOOT	349.000				
60109580	P UNDR FOR STRUCT 4	FOOT	859.000				
60900515	CONC THRUST BLOCKS	EACH	8.000				
61000115	TY E INLET BOX 610001	EACH	8.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	7,880.000				
63100045	TRAF BAR TERM T2	EACH	12.000				
63100085	TRAF BAR TERM T6	EACH	24.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	6.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66908

State Job # - C-93-049-09
 PPS NBR - 3-08006-0090
 County Name - BUREAU- -
 Code - 11 - -
 District - 3 - -
 Section Number - 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]

Project Number
 ACBRF-ACNHI-0802/065/062

Route
 FAI 80

*** REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63100169	TR BAR TRM T1 SPL FLR	EACH	12.000				
63200310	GUARDRAIL REMOV	FOOT	10,341.000				
63500105	DELINEATORS	EACH	236.000				
63500120	DELINEATOR REMOVAL	EACH	236.000				
* 63801205	TEMP MOD GLARE SCREEN	FOOT	78,929.000				
64200105	SHOULDER RUMBLE STRIP	FOOT	155,195.000				
66500105	WOV W FENCE 4	FOOT	7,875.000				
66502300	WOV W FENCE REMOV	FOOT	7,875.000				
67000400	ENGR FIELD OFFICE A	CAL MO	20.000				
67100100	MOBILIZATION	L SUM	1.000				
70100420	TRAF CONT-PROT 701411	EACH	1.000				
70101835	TRAF CONT-PROT BLR 22	L SUM	1.000				
70103700	TRAF CONT COMPL	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	200.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	30.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66908

State Job # - C-93-049-09
 PPS NBR - 3-08006-0090
 County Name - BUREAU- -
 Code - 11 - -
 District - 3 - -
 Section Number - 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]

Project Number
 ACBRF-ACNHI-0802/065/062

Route
 FAI 80

*** REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300100	SHORT-TERM PAVT MKING	FOOT	7,086.000				
70300220	TEMP PVT MK LINE 4	FOOT	152,585.000				
70300240	TEMP PVT MK LINE 6	FOOT	19,852.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	98,722.000				
* 70400100	TEMP CONC BARRIER	FOOT	78,929.000				
* DELETED							
70500100	TEMP SPBGR TY A	FOOT	1,500.000				
78000200	THPL PVT MK LINE 4	FOOT	152,585.000				
78004230	PREF PL PM TB INL L6	FOOT	19,073.000				
78008210	POLYUREA PM T1 LN 4	FOOT	6,235.000				
78008230	POLYUREA PM T1 LN 6	FOOT	779.000				
78100100	RAISED REFL PAVT MKR	EACH	1,918.000				
78100105	RAISED REF PVT MKR BR	EACH	84.000				
78200405	GUARDRAIL MARKERS	EACH	84.000				
78200500	BARRIER WALL MARKERS	EACH	32.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66908

State Job # - C-93-049-09
 PPS NBR - 3-08006-0090
 County Name - BUREAU- -
 Code - 11 - -
 District - 3 - -
 Section Number - 06-[7BR&BR-1,7VB-M,6BR&6,7ETC]

Project Number
 ACBRF-ACNHI-0802/065/062

Route
 FAI 80

*** REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78201000	TERMINAL MARKER - DA	EACH	12.000				
78300105	PAVT MARKING REMOVAL	FOOT	87,531.000				
78300200	RAISED REF PVT MK REM	EACH	1,918.000				

NOTIFICATION OF REDUCED WIDTH (BDE) 90

PAYMENTS TO SUBCONTRACTORS (BDE) 90

PAYROLLS AND PAYROLL RECORDS (BDE) 91

PERSONAL PROTECTIVE EQUIPMENT (BDE) 93

PLASTIC BLOCKOUTS FOR GUARDRAIL (BDE) 93

POLYUREA PAVEMENT MARKING (BDE) 93

RAISED REFLECTIVE PAVEMENT MARKERS (BDE) 100

RECLAIMED ASPHALT PAVEMENT (RAP) (BDE) 101

REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) 107

REINFORCEMENT BARS (BDE) 108

REINFORCEMENT BARS - STORAGE AND PROTECTION (BDE) 109

SEEDING (BDE) 109

SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE) 111

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE) 116

SILT FILTER FENCE (BDE) 117

STEEL PLATE BEAM GUARDRAIL (BDE) 117

STONE GRADATION TESTING (BDE) 117

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 118

TEMPORARY EROSION CONTROL (BDE) 118

THERMOPLASTIC PAVEMENT MARKINGS (BDE) 119

TRAINING SPECIAL PROVISIONS 120

WOVEN WIRE FENCE (BDE) 122

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) 122

FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 125

STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 129

TEMPORARY CONSTRUCTION/WATERWAY PERMITS #006-0024 (CORPS OF ENGINEERS) 133

TEMPORARY CONSTRUCTION/WATERWAY PERMITS #006-0026 (CORPS OF ENGINEERS) 133

TEMPORARY CONSTRUCTION/WATERWAY PERMITS #006-0028 (CORPS OF ENGINEERS) 134

404 PERMITS #s 170 & 171 135

404 PERMITS #s 172 & 173 139

404 PERMITS #s 174 & 175 143

NATIONWIDE PERMITS AND CONDITIONS 147

IEPA REGIONAL CONDITIONS 160

STORM WATER POLLUTION PREVENTION PLAN 178

PROJECT LABOR AGREEMENT 186

HOT MIX ASPHALT SURFACE REMOVAL,SPECIAL 200

Revised 10/23/2009

7P - PORTABLE VEHICLE MOUNTED CHANGEABLE MESSAGE BOARD

Effective August 7, 2008

Description. This item shall consist of one heavy duty vehicle fitted with a truck mounted attenuator and with a permanently mounted changeable message sign. The vehicle mounted message sign shall be required when Traffic Control and Protection, Standard 701401 (Special) is in place and the Contractor is working. The vehicle mounted message sign shall also be required when high volumes of traffic occur such as on weekends and holidays. Specific times will be determined by the Engineer.

The vehicle location shall be in advance of the lane closure taper and in advance of any stopped traffic on the interstate.

Construction Requirements. The Contractor shall provide a person who shall remain with the vehicle at all times. The person shall have in his/her possession a current driver's license. The person shall be capable of operating the vehicle and capable of promptly programming and/or reprogramming the message sign to provide the messages as directed by the Engineer.

The sign shall meet the applicable requirements of Article 701.15 of the Standard Specifications.

Equipment. The vehicle shall be fitted with a truck mounted attenuator and should have an actual weight of no less than 11,000 pounds and no greater than 26,000 pounds. Higher weights may be used when approved by the Engineer and the attenuator manufacturer.

The message sign shall meet the applicable requirements of Article 1106.02(i) of the Standard Specifications.

Method of Measurement. The vehicle with the mounted changeable message sign will be measured on a calendar day basis.

The person provided by the Contractor to operate the truck and message sign will not be paid for separately.

Basis of Payment. The vehicle and portable changeable message sign will be paid for at the contract unit price per calendar day **or fraction thereof** for PORTABLE VEHICLE MOUNTED CHANGEABLE MESSAGE BOARD. **The Contractor shall be paid a full Calendar Day for this pay item if he/she uses this board for any portion of the day.**

SEQUENCE OF OPERATIONS AND COMPLETION DATES

The Contractor shall adhere to the following sequence of operations.

No lanes of traffic shall be closed prior to March 1, 2010.

Pre-stage I Construction

Using Traffic Control and Protection, Standard 701401, the Contractor shall first place the HMA shoulders that will be used for Stage I Traffic Control in the eastbound lane.

Revised 10/23/2009

Stage I Construction

Using Traffic Control Complete in the Plans, the Contractor shall remove and replace three structures in the westbound lane.

The Contractor shall also remove the structure over the abandoned railroad, place embankment, and fill in the structure at the abandoned railroad. The westbound lane shall be completely patched and overlaid to the final plan configuration during this stage. Stage I shall be completed by **October 29**, 2010, and all lanes of traffic on I-80 kept open to traffic until March 1, 2011.

Stage II Construction:

Using Traffic Control Complete in the plans, the Contractor shall remove and replace the three structures in the eastbound lane and remove and fill in the structure at the abandoned railroad. The eastbound lane shall be completely patched and overlaid to the final plan configuration during this stage.

Stage II Construction shall be completed by September 2, 2011 and all lanes will be opened to traffic at this time.

CHANGEABLE MESSAGE SIGN

Effective December 1, 1999

In addition to the two message boards required in the detail for the Modification of Standard 701400 as shown in the plans and the portable message board as described in the Special Provision PORTABLE VEHICLE MOUNTED CHANGEABLE MESSAGE BOARD, the Contractor shall furnish 2 additional Changeable Message Signs for this project. The signs shall be operational two weeks prior to any lane closure and shall be located as directed by the Engineer. These message boards shall remain operational whenever one lane is closed to traffic on I-80 and any other time as determined by the Engineer. Any relocation of the signs directed by the Engineer during construction will not be paid for separately, but shall be included in the cost of the Changeable Message Sign.

These two message boards shall be paid for at the Contract Unit price per Calendar Month for Changeable Message Sign.

TRAFFIC CONTROL COMPLETE

This work shall include furnishing, installing, maintaining, replacing, relocating and removing all traffic control devices used for the purpose of regulating, warning, or directing traffic along I-80 during Stage 1 and Stage 2. Traffic control and protection shall be provided as called for on the Stage Construction plan sheets, the Standard Specifications, these Special Provisions, or as directed by the Engineer.

Revised 10/23/2009

HOT MIX ASPHALT SURFACE REMOVAL,SPECIAL

Description: This work shall consist of the removal of existing hot mix asphalt surface as depicted in the plan and profile drawings to a variable depth (0" to 3¾") in advance of hot mix asphalt surface placement for the purpose of profile correction. This work shall be performed in accordance with the applicable portions of Section 440 of the Standard Specifications, and as directed by the Engineer.

Method of Measurement: HOT MIX ASPHALT SURFACE REMOVAL SPECIAL will be measured for payment in place and the area computed in square yards.

Basis for Payment: This work will be paid for at the contract unit price per square yard for HOT MIX ASPHALT SURFACE REMOVAL SPECIAL which price shall be considered payment in full for all labor, equipment, materials, removal, and disposal as specified.

Added 10/23/2009