

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QTY 80% FED. 20% STATE	ACNHI RDWY 1000-2A	ACBRF			ACNHI		
					006-0170 006-0171 X581-5B	006-0172 006-0173 X081-2A	006-0174 006-0175 X081-2A	006-0133 SFTY-2A	006-0127 SFTY-2A	006-0129 SFTY-2A
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	8143	8143						
3 40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	24,217	24,217						
42001200	PAVEMENT FABRIC	SQ YD	54	54						
<del>42100300</del>	<del>CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 10"</del>	<del>SQ YD</del>	<del>3480</del>	<del>3480</del>						
3 42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	267	267						
<del>42100900</del>	<del>PAVEMENT REINFORCEMENT 10"</del>	<del>SQ YD</del>	<del>3480</del>	<del>3480</del>						
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	53	53						
<del>42101020</del>	<del>WIDE FLANGE BEAM TERMINAL JOINT COMPLETE 24"</del>	<del>EACH</del>	<del>2</del>	<del>2</del>						
3 44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	2,534	2,534						
44000100	PAVEMENT REMOVAL	SQ YD	5477	5477						
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	10668	10668						
44001114	HOT-MIX ASPHALT SURFACE REMOVAL (ASBESTOS)	SQ YD	4920		2116	1238	1566			
44000182	HOT-MIX ASPHALT SURFACE REMOVAL, 8"	SQ YD	32455	32455						
44213200	SAW CUTS	FOOT	996	996						
44004250	PAVED SHOULDER REMOVAL	SQ YD	1841	1841						
44201055	CLASS B PATCHES, TYPE II, 17 INCH	SQ YD	183	183						
44201057	CLASS B PATCHES, TYPE III, 17 INCH	SQ YD	48	48						
44201053	CLASS B PATCHES, TYPE IV, 17 INCH	SQ YD	54	54						
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5429	5429						
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	3782	3782						
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	32455	32455						
3 48203045	HOT-MIX ASPHALT SHOULDERS, 12"	SQ YD	5,533	5,533						
<del>48200500</del>	<del>PORTLAND CEMENT CONCRETE SHOULDERS 10"</del>	<del>SQ YD</del>	<del>2320</del>	<del>2320</del>						
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	8	2	2	2	2			
50157300	PROTECTIVE SHIELD	SQ YD	834		354				160	320
50200100	STRUCTURE EXCAVATION	CU YD	2497		975	500	1022			
50300100	FLOOR DRAINS	EACH	102		68	34				
50300225	CONCRETE STRUCTURES	CU YD	1969		834	513	622			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3209		1285	846	1078			
50300260	BRIDGE DECK GROOVING	SQ YD	6695		3324	1463	1908			
50300280	CONCRETE ENCASEMENT	CU YD	61		16	25	20			
50300300	PROTECTIVE COAT	SQ YD	8404		4199	1829	2376			
50300530	FLOOR DRAIN EXTENSION	EACH	14					12		2
50400745	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 72"	FOOT	2608				2608			
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	2358			2358				
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	4599		4599					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	863780		340800	215950	307030			

\* SPECIALTY ITEMS

3 REVISED 10/20/09

\*\*06-[7BR&BR-1,7VB-M,6BR&6,7 RS-1 & 1]

ILLINOIS FED. AID PROJECT