

SCHEDULE - TRAFFIC CONTROL FOR STAGE CONSTRUCTION						
LOCATION	TRAFFIC CONTROL INTERSTATE	TRAFFIC CONTROL & PROTECTION STANDARD 701201	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3
	L SUM	L SUM	FOOT	FOOT	EACH	EACH
NB DRIVE LANE	0.25	0.5	305		1	
NB PASSING LANE	0.25			305		1
SB DRIVE LANE	0.25	0.5		305		1
SB PASSING LANE	0.25			305		1
TOTALS	1	1	305	915	1	3

SCHEDULE - PAVEMENT MARKING			
LOCATION	PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"
	SQ FT	L SUM	L SUM
NB DRIVE LANE	512	375	775
NB PASSING LANE	124	375	
SB DRIVE LANE	512	375	775
SB PASSING LANE	124	375	
TOTALS	1272	1500	1550