



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 22, 2009

SUBJECT: FAP Route 71 (IL 54)  
Project ACBRF-0071 (117)  
Section (121BR) BR  
Dewitt County  
Contract No. 70429  
Item No. 70, November 6, 2009 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheet 4 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief  
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Joseph E. Crowe, Region 3, District 5; Bill Frey; R. E. Anderson;  
Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 70429

State Job # - C-95-073-04  
 PPS NBR - 5-52350-0000  
 County Name - DEWITT -  
 Code - 39 - -  
 District - 5 - -  
 Section Number - (121BR)BR

Project Number  
 ACBRF-0071/117/

Route  
 FAP 71

\* REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
XZ193300	SURVEY MARKER T1 SPL	EACH	1.000				
X0324865	DIAMOND GRIND BR SEC	SQ YD	724.000				
* DELETED							
* X5020501	UNWAT STR EX PROT L1	EACH	1.000				
X7200201	WIDTH RESTRICT SIGN	L SUM	1.000				
Z0001900	ASB BEARING PAD REMOV	EACH	39.000				
Z0002900	BASE CSE (OPTION)	SQ YD	384.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	2.000				
Z0030350	IMP ATTN REL NRD TL3	EACH	2.000				
Z0038700	PERMNT BENCH MARKS	EACH	1.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
20100110	TREE REMOV 6-15	UNIT	105.000				
20100210	TREE REMOV OVER 15	UNIT	166.000				
20200100	EARTH EXCAVATION	CU YD	1,860.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 70429

State Job # - C-95-073-04  
 PPS NBR - 5-52350-0000  
 County Name - DEWITT -  
 Code - 39 - -  
 District - 5 - -  
 Section Number - (121BR)BR

Project Number  
 ACBRF-0071/117/

Route  
 FAP 71

\* REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20700400	POROUS GRAN EMB SPEC	CU YD	134.000				
25000210	SEEDING CL 2A	ACRE	1.000				
25000300	SEEDING CL 3	ACRE	1.500				
25000400	NITROGEN FERT NUTR	POUND	225.000				
25000500	PHOSPHORUS FERT NUTR	POUND	225.000				
25000600	POTASSIUM FERT NUTR	POUND	225.000				
25100115	MULCH METHOD 2	ACRE	2.500				
25100630	EROSION CONTR BLANKET	SQ YD	1,635.000				
28000250	TEMP EROS CONTR SEED	POUND	250.000				
28000300	TEMP DITCH CHECKS	EACH	7.000				
28000400	PERIMETER EROS BAR	FOOT	1,760.000				
28100107	STONE RIPRAP CL A4	SQ YD	512.000				
28200200	FILTER FABRIC	SQ YD	512.000				
40600100	BIT MATLS PR CT	GALLON	377.000				
40600300	AGG PR CT	TON	8.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 70429

State Job # - C-95-073-04  
 PPS NBR - 5-52350-0000  
 County Name - DEWITT - -  
 Code - 39 - -  
 District - 5 - -  
 Section Number - (121BR)BR

Project Number  
 ACBRF-0071/117/

Route  
 FAP 71

\* REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600982	HMA SURF REM BUTT JT	SQ YD	633.000				
40600990	TEMPORARY RAMP	SQ YD	159.000				
40603080	HMA BC IL-19.0 N50	TON	279.000				
40603310	HMA SC "C" N50	TON	199.000				
40800010	BIT MATLS PR CT	GALLON	48.000				
40800030	AGG PR CT	TON	1.000				
40800050	INCIDENTAL HMA SURF	TON	73.000				
42001430	BR APPR PVT CON (FLX)	SQ YD	42.000				
44000100	PAVEMENT REM	SQ YD	94.000				
44000196	HMA SURF REM SPL	SQ YD	104.000				
44000700	APPROACH SLAB REM	SQ YD	182.000				
48101500	AGGREGATE SHLDS B 6	SQ YD	464.000				
50100100	REM EXIST STRUCT	EACH	1.000				
50102400	CONC REM	CU YD	33.600				
50200100	STRUCTURE EXCAVATION	CU YD	245.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 70429

State Job # - C-95-073-04  
 PPS NBR - 5-52350-0000  
 County Name - DEWITT - -  
 Code - 39 - -  
 District - 5 - -  
 Section Number - (121BR)BR

Project Number  
 ACBRF-0071/117/

Route  
 FAP 71

\* REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50300100	FLOOR DRAINS	EACH	20.000				
50300225	CONC STRUCT	CU YD	100.700				
50300255	CONC SUP-STR	CU YD	336.900				
50300260	BR DECK GROOVING	SQ YD	776.000				
50300280	CONCRETE ENCASEMENT	CU YD	12.100				
50300300	PROTECTIVE COAT	SQ YD	1,005.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	2,232.000				
50800205	REINF BARS, EPOXY CTD	POUND	84,780.000				
50800515	BAR SPLICERS	EACH	873.000				
51200959	FUR M S PILE 14X0.312	FOOT	839.000				
51202305	DRIVING PILES	FOOT	839.000				
51203200	TEST PILE MET SHELLS	EACH	3.000				
51205200	TEMP SHT PILING	SQ FT	1,172.000				
51500100	NAME PLATES	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 70429

State Job # - C-95-073-04  
 PPS NBR - 5-52350-0000  
 County Name - DEWITT -  
 Code - 39 - -  
 District - 5 - -  
 Section Number - (121BR)BR

Project Number  
 ACBRF-0071/117/

Route  
 FAP 71

\* REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
52100520	ANCHOR BOLTS 1	EACH	36.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	77.000				
60100060	CONC HDWL FOR P DRAIN	EACH	4.000				
60109580	P UNDR FOR STRUCT 4	FOOT	145.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	375.000				
63100045	TRAF BAR TERM T2	EACH	1.000				
63100085	TRAF BAR TERM T6	EACH	4.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	3.000				
63200310	GUARDRAIL REMOV	FOOT	921.000				
63300725	SPBGR (SHORT RADIUS)	FOOT	50.000				
66503400	BARB W FENCE REMOV	FOOT	515.000				
67000500	ENGR FIELD OFFICE B	CAL MO	7.000				
67100100	MOBILIZATION	L SUM	1.000				
70100405	TRAF CONT-PROT 701321	EACH	1.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 70429

State Job # - C-95-073-04  
 PPS NBR - 5-52350-0000  
 County Name - DEWITT -  
 Code - 39 - -  
 District - 5 - -  
 Section Number - (121BR)BR

Project Number  
 ACBRF-0071/117/

Route  
 FAP 71

\* REVISED : OCTOBER 22, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70106500	TEMP BR TRAF SIGNALS	EACH	1.000				
70300100	SHORT-TERM PAVT MKING	FOOT	90.000				
70300220	TEMP PVT MK LINE 4	FOOT	2,030.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	855.000				
70400100	TEMP CONC BARRIER	FOOT	512.500				
70400200	REL TEMP CONC BARRIER	FOOT	437.500				
78001110	PAINT PVT MK LINE 4	FOOT	2,030.000				
78100100	RAISED REFL PAVT MKR	EACH	12.000				
78200405	GUARDRAIL MARKERS	EACH	8.000				
78200500	BARRIER WALL MARKERS	EACH	5.000				
78201000	TERMINAL MARKER - DA	EACH	4.000				
78300100	PAVT MARKING REMOVAL	SQ FT	317.000				
78300200	RAISED REF PVT MK REM	EACH	12.000				