

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY RURAL TWO-LANE ROADWAY 80% FEDERAL 20% STATE X071-2A
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	105
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	166
20200100	EARTH EXCAVATION	CU YD	1860
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	134
* 25000210	SEEDING, CLASS 2A	ACRE	1.00
* 25000300	SEEDING, CLASS 3	ACRE	1.50
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	225
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	225
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	225
* 25100115	MULCH, METHOD 2	ACRE	2.50
* 25100630	EROSION CONTROL BLANKET	SQ YD	1635
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	250
28000300	TEMPORARY DITCH CHECKS	EACH	7
28000400	PERIMETER EROSION BARRIER	FOOT	1760
28100107	STONE RIPRAP, CLASS A4	SQ YD	512
28200200	FILTER FABRIC	SQ YD	512
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	377
40600300	AGGREGATE (PRIME COAT)	TON	8
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	633
40600990	TEMPORARY RAMP	SQ YD	159
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	279
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N50	TON	199
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	48
40800030	AGGREGATE (PRIME COAT)	TON	1
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	73
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	42
44000100	PAVEMENT REMOVAL	SQ YD	94
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	104
44000700	APPROACH SLAB REMOVAL	SQ YD	182
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	464
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	33.6
50200100	STRUCTURE EXCAVATION	CU YD	245
50300100	FLOOR DRAINS	EACH	20
50300225	CONCRETE STRUCTURES	CU YD	100.7

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY RURAL TWO-LANE ROADWAY 80% FEDERAL 20% STATE X071-2A
50300255	CONCRETE SUPERSTRUCTURE	CU YD	336.9
50300260	BRIDGE DECK GROOVING	SQ YD	776
50300280	CONCRETE ENCASEMENT	CU YD	12.1
50300300	PROTECTIVE COAT	SQ YD	1005
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500505	STUD SHEAR CONNECTORS	EACH	2232
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	84780
50800515	BAR SPLICERS	EACH	873
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	839
51202305	DRIVING PILES	FOOT	839
51203200	TEST PILE METAL SHELLS	EACH	3
51205200	TEMPORARY SHEET PILING	SQ FT	1172
51500100	NAME PLATES	EACH	1
52100520	ANCHOR BOLTS, 1"	EACH	36
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	77
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	145
* 63000001	STEEL PLATE BEAM GUARDRAIL , TYPE A, 6 FOOT POSTS	FOOT	375.0
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	3
63200310	GUARDRAIL REMOVAL	FOOT	921
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	50.0
66503400	BARBED WIRE FENCE REMOVAL	FOOT	515
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	7
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	90
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2030
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	855
70400100	TEMPORARY CONCRETE BARRIER	FOOT	512.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	437.5

\* DENOTES SPECIALTY ITEM

FILE NAME = c:\pw\work\PW1001\STUL.TS\W\d0101439\057	USER NAME = stults,jr	DESIGNED -	REVISED -
	0429-sh+500 Rev.dgn	DRAWN -	REVISED -
	PLOT SCALE = 48.000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 8/17/2009	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.
--------	-------------------------	------	---------

F.A.P. RTE. 71	SECTION (121BR)BR	COUNTY DEWITT	TOTAL SHEETS 75	SHEET NO. 3
CONTRACT NO. 70429				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				