

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SHEET 1 OF 6

- (205,57,105)RS-2
- CHAMPAIGN & DOUGLAS

LOCATION OF WORK:	FAP 808	FAP 808	FAP 808	FAP 808
	IL RTE. 130	IL RTE. 130	IL RTE. 130	IL RTE. 130
COUNTY:	RURAL TWO LANE	RURAL TWO LANE	RURAL TWO LANE	RURAL TWO LANE
	DOUGLAS	CHAMPAIGN	CHAMPAIGN	CHAMPAIGN
	STA. 297+50.00	STA. 1000+00.00 AH	STA. 1145+38.00	STA. 2224+94.00
	TO	TO		
	STA. 320+90.82 BK	STA. 2309+00.00	S.N. 010-2036	S.N. 010-2035
FUNDING BREAKOUT:	80% FED	80% FED	80% FED	80% FED
	20% STATE	20% STATE	20% STATE	20% STATE
CONSTRUCTION TYPE CODE:	1000	1000	X028-2A	X028-2A

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
54213654	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 8"	EACH	1.00		1.00		
* X0326696	SIGN AND POST	EACH	31.00	1.00	30.00		
X6022020	MANHOLES, TYPE A, 4-DIAMETER, FLAT SLAB TOP	EACH	5.00		5.00		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	283.00		283.00		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	266.00		266.00		
20200100	EARTH EXCAVATION	CU YD	30676.00	1349.00	29327.00		
20800150	TRENCH BACKFILL	CU YD	493.00	9.00	484.00		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1155.00		997.00	96.00	62.00
20900110	POROUS GRANULAR BACKFILL	CU YD	656.00		656.00		
* 25000100	SEEDING, CLASS 1	ACRE	2.25		2.25		
* 25000200	SEEDING, CLASS 2	ACRE	51.25	2.60	48.65		
* 25000350	SEEDING, CLASS 7	ACRE	53.50	2.60	50.90		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4806.00	231.00	4575.00		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4806.00	231.00	4575.00		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4806.00	231.00	4575.00		
* 25100115	MULCH, METHOD 2	ACRE	53.50	2.60	50.90		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5350.00	260.00	5090.00		
28000300	TEMPORARY DITCH CHECKS	EACH	487.00	21.00	466.00		
28000400	PERIMETER EROSION BARRIER	FOOT	4960.00		4960.00		
28000500	INLET AND PIPE PROTECTION	EACH	144.00	7.00	137.00		
28100107	STONE RIPRAP, CLASS A4	SQ YD	332.00		282.00	50.00	
28100201	STONE RIPRAP, CLASS A1	TON	90.00		90.00		
28200200	FILTER FABRIC	SQ YD	469.00		469.00		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1943.00		1943.00		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	549.00	3.00	546.00		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	68.00		68.00		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1738.00	93.00	1645.00		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	128.00		128.00		
40300602	SEAL COAT AGGREGATE, SPECIAL	TON	319.00	16.00	303.00		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15853.00	790.00	15063.00		
40600300	AGGREGATE (PRIME COAT)	TON	318.00	16.00	302.00		
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N50	TON	7806.00	330.00	7476.00		
40600895	CONSTRUCTING TEST STRIP	EACH	1.00		1.00		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3645.00	162.00	3483.00		
40600990	TEMPORARY RAMP	SQ YD	333.00	17.00	316.00		

* SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Sheet 1 of 6

SCALE: NOT TO SCALE DRAWN BY: B.B.P.
 DATE: 07/31/09 CHECKED BY: G.A.E.

PLOT DATE = 8/17/2009
 PLOT SCALE = 42.3579 / IN.
 USER NAME = ceprlockjd