

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SHEET 3 OF 6

LOCATION OF WORK:	FAP 808	FAP 808	FAP 808	FAP 808
	IL RTE. 130	IL RTE. 130	IL RTE. 130	IL RTE. 130
	RURAL TWO LANE	RURAL TWO LANE	RURAL TWO LANE	RURAL TWO LANE
COUNTY:	DOUGLAS	CHAMPAIGN	CHAMPAIGN	CHAMPAIGN
	STA. 297+50.00	STA. 1000+00.00 AH	STA. 1145+38.00	STA. 2224+94.00
	TO	TO		
	STA. 320+90.82 BK	STA. 2309+00.00	S.N. 010-2036	S.N. 010-2035
FUNDING BREAKOUT:	80% FED	80% FED	80% FED	80% FED
	20% STATE	20% STATE	20% STATE	20% STATE
CONSTRUCTION TYPE CODE:	I000	I000	X028-2A	X028-2A

- (205,57,105)RS-2
- ** CHAMPAIGN & DOUGLAS

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
54001005	BOX CULVERT END SECTION, CULVERT NO.5	EACH	2.00		2.00		
54001006	BOX CULVERT END SECTION, CULVERT NO.6	EACH	2.00		2.00		
54001007	BOX CULVERT END SECTION, CULVERT NO.7	EACH	2.00		2.00		
54001008	BOX CULVERT END SECTION, CULVERT NO.8	EACH	2.00		2.00		
54001009	BOX CULVERT END SECTION, CULVERT NO.9	EACH	2.00		2.00		
54001010	BOX CULVERT END SECTION, CULVERT NO.10	EACH	2.00		2.00		
54001011	BOX CULVERT END SECTION, CULVERT NO.11	EACH	2.00				2.00
54001012	BOX CULVERT END SECTION, CULVERT NO.12	EACH	2.00		2.00		
54001013	BOX CULVERT END SECTION, CULVERT NO.13	EACH	2.00		2.00		
54001014	BOX CULVERT END SECTION, CULVERT NO.14	EACH	2.00		2.00		
54010503	PRECAST CONCRETE BOX CULVERT 5' X 3'	FOOT	116.00		116.00		
54020602	PRECAST CONCRETE BOX CULVERT 6' X 2' (M273)	FOOT	78.00		78.00		
54020705	PRECAST CONCRETE BOX CULVERT 7' X 5' (M273)	FOOT	42.00		42.00		
54020802	PRECAST CONCRETE BOX CULVERT 8' X 2' (M273)	FOOT	42.00		42.00		
54020804	PRECAST CONCRETE BOX CULVERT 8' X 4' (M273)	FOOT	88.00		88.00		
54021002	PRECAST CONCRETE BOX CULVERT 10' X 2' (M273)	FOOT	128.00		48.00		80.00
54021004	PRECAST CONCRETE BOX CULVERT 10' X 4' (M273)	FOOT	84.00			84.00	
54021202	PRECAST CONCRETE BOX CULVERT 12' X 2' (M273)	FOOT	117.00		117.00		
54021203	PRECAST CONCRETE BOX CULVERT 12' X 3' (M273)	FOOT	88.00		88.00		
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	140.00		140.00		
54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	98.00		98.00		
54200436	PIPE CULVERTS, TYPE 1 RCCP 21"	FOOT	93.00		93.00		
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	261.00		261.00		
54201303	PIPE CULVERTS, TYPE 2 RCCP 48"	FOOT	72.00		72.00		
54206739	PIPE CULVERTS, TYPE 1, CONCRETE, EQUIVALENT ROUND-SIZE 24"	FOOT	252.00		252.00		
54213447	END SECTIONS 12" <i>REINFORCED</i>	EACH	8.00		8.00		
54213450	END SECTIONS 15"	EACH	52.00		52.00		
54213453	END SECTIONS 18"	EACH	42.00		42.00		
54213456	END SECTIONS 21"	EACH	10.00		10.00		
54213459	END SECTIONS 24"	EACH	36.00	8.00	28.00		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2.00		2.00		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	6.00		6.00		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4.00		4.00		
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	4.00		4.00		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	12.00		12.00		

* SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Sheet 3 of 6

SCALE: NOT TO SCALE
DATE: 07/31/09

DRAWN BY: B.B.P.
CHECKED BY: G.A.E.