

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	24
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• (205,57,105)RS-2 ** CHAMPAIGN & DOUGLAS				

SCHEDULE OF QUANTITIES – RURAL CHAMPAIGN COUNTY

SHEET 3 OF 27

PARTIAL DEPTH PAVEMENT PATCHING

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	EXISTING OVERLAY THICKNESS (INCH)	X4401705	X4421000
					PARTIAL DEPTH REMOVAL (SQ YD)	PARTIAL DEPTH PATCHING (TONS)
320+89	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
320+89	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1002+93	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1002+93	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1007+76	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1008+94	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1009+91	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1009+91	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1015+93	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1015+93	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1017+92	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1017+92	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1020+08	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1020+08	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1022+91	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
1022+91	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
1025+92	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1025+92	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1027+94	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1032+93	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1032+93	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1034+94	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1034+94	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1037+93	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1037+93	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1041+93	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1041+93	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
1047+96	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1047+96	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1050+93	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
1050+93	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
1071+97	NORTHBOUND	10.00	15.00	5.25	16.67	7.70
1071+97	SOUTHBOUND	10.00	15.00	5.25	16.67	7.70
1083+01	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
1083+01	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
1088+00	NORTHBOUND	10.00	15.00	5.25	16.67	7.70
1088+00	SOUTHBOUND	10.00	15.00	5.25	16.67	7.70
1090+05	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
1090+05	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
1116+92	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
1116+92	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
1118+97	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1118+97	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1120+96	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1120+96	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1121+94	NORTHBOUND	10.00	15.00	5.25	16.67	7.70
1121+94	SOUTHBOUND	10.00	15.00	5.25	16.67	7.70
1122+97	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
1122+97	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
1123+94	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
1123+94	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2028+32	NORTHBOUND	6.00	15.00	5.25	10.00	4.62

PARTIAL DEPTH PAVEMENT PATCHING (CON'T)

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	EXISTING OVERLAY THICKNESS (INCH)	X4401705	X4421000
					PARTIAL DEPTH REMOVAL (SQ YD)	PARTIAL DEPTH PATCHING (TONS)
2028+32	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2041+73	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2041+73	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2048+86	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2053+22	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2053+22	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2066+83	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2066+83	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2072+98	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2072+98	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2096+64	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2096+64	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2098+24	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2098+24	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2100+66	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2100+66	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2105+16	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2105+16	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2117+07	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2117+07	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2122+14	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2122+14	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2128+14	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2128+14	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2137+83	SOUTHBOUND	12.00	6.00	5.25	8.00	3.70
2138+06	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2138+06	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2138+77	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2140+66	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2140+66	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2143+65	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2143+65	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2144+13	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2149+13	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2149+13	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2154+66	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2156+26	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2156+26	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2161+05	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2161+05	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2165+67	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2165+67	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2166+87	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2166+87	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2170+90	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2170+90	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2178+73	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2178+73	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2179+74	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2179+74	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2181+00	NORTHBOUND	10.00	15.00	5.25	16.67	7.70
2181+00	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16

PARTIAL DEPTH PAVEMENT PATCHING (CON'T)

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	EXISTING OVERLAY THICKNESS (INCH)	X4401705	X4421000
					PARTIAL DEPTH REMOVAL (SQ YD)	PARTIAL DEPTH PATCHING (TONS)
2184+99	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2184+99	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2187+46	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2191+39	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2191+39	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2195+04	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2195+04	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2202+38	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2202+38	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2203+44	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2203+44	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2205+92	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2205+92	SOUTHBOUND	16.00	15.00	5.25	26.67	12.32
2213+49	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2213+49	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2214+21	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2214+21	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2215+13	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2215+13	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2223+40	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2223+40	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2231+57	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2231+57	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2240+05	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2240+05	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2241+10	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2241+10	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2242+61	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2242+61	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2244+33	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2244+33	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2246+62	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2246+62	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2248+08	NORTHBOUND	10.00	15.00	5.25	16.67	7.70
2248+08	SOUTHBOUND	10.00	15.00	5.25	16.67	7.70
2250+24	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2250+24	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2251+69	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2251+69	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2255+73	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2255+73	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2258+32	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
2263+21	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2263+21	SOUTHBOUND	10.00	15.00	5.25	16.67	7.70
2264+54	NORTHBOUND	8.00	15.00	5.25	13.33	6.16
2264+54	SOUTHBOUND	8.00	15.00	5.25	13.33	6.16
2281+97	NORTHBOUND	6.00	15.00	5.25	10.00	4.62
2281+97	SOUTHBOUND	6.00	15.00	5.25	10.00	4.62
TOTAL =					1768.00	816.82
USE =					1768.00	817.00
					(SQ YD)	(TON)

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES-RURAL
CHAMPAIGN COUNTY

PLOT DATE = 8/12/2009
 FILE NAME = G:\DW\work\K\PIWDOT\PERSONNEL\000445\70623-sht+schedule-champaign.dgn
 USER NAME = pfersonbr