

SCHEDULE OF QUANTITIES – RURAL CHAMPAIGN COUNTY

SHEET 5 OF 27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	26
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• (205,57,105)RS-2 ** CHAMPAIGN & DOUGLAS				

PIPE CULVERT SCHEDULE FOR ENTRANCES, (CON'T.)

STATION	DESCRIPTION	PROPOSED TREATMENT	50105220	N/A	542D0217	542D0220	542D0223	542D0226	542D0229	542D5473	54213447	54213450	54213453	54213456	54213459	54214293	20800150
			PIPE CULVERT REMOVAL (FOOT)	PROPOSED PIPE SIZE (INCH)	PIPE CULVERT CLASS D TYPE 1, 12: (FOOT)	PIPE CULVERT CLASS D TYPE 1, 15" (FOOT)	PIPE CULVERT CLASS D TYPE 1, 18" (FOOT)	PIPE CULVERT CLASS D TYPE 1, 21" (FOOT)	PIPE CULVERT CLASS D TYPE 1, 24" (FOOT)	PIPE CULVERT CLASS D EQRS, 18" (FOOT)	END SECTION 12" (EACH)	END SECTION 15" (EACH)	END SECTION 18" (EACH)	END SECTION 21" (EACH)	END SECTION 24" (EACH)	END SECTION EQRS, 18" (EACH)	TRENCH BACKFILL (CU YD)
LT. 2028+19.50	20' F.E.	NO PIPE															
LT. 2035+72.30	12.5' P.E.	NEW CULVERT W / E.S.	40.30	18			40.00						2.0				6.30
RT. 2049+42.50	30' F.E.	NEW CULVERT W / E.S.	28.60	15		52.00						2.00					
RT. 2057+10.70	MBTO	NO PIPE															
LT. 2057+10.70	24' P.E.	NEW CULVERT W / E.S.	28.40	15		44.00						2.00					
RT. 2060+75.00	30' F.E.	NEW CULVERT W / E.S.	28.40	15		48.00						2.00					
LT. 2070+75.00	30' F.E.	NEW CULVERT W / E.S.	29.00	18			48.00						2.00				
RT. 2074+07.00	F.E.	REMOVE ENTRANCE															
LT. 2088+16.00	16' P.E.	NEW CULVERT W / E.S.	45.60	24					40.00						2.00		
RT. 2088+93.00	14' P.E. W / MBTO	NEW CULVERT W / E.S.	53.90	24					44.00						2.00		
LT. 2089+24.00	14' P.E.	NEW CULVERT W / E.S.	41.30	24					40.00						2.00		
LT. 2089+90.00	30' F.E.	NEW CULVERT W / E.S.		24					54.00						2.00		
RT. 2094+14.50	30' F.E.	NEW CULVERT W / E.S.	28.80	18			50.00						2.00				
LT. 2109+07.01	30' F.E.	NEW CULVERT W / E.S.	40.50	15		50.00						2.00					
RT. 2115+21.00	F.E.	REMOVE ENTRANCE	40.00														
RT. 500+87.00	30' F.E. / (500N)	NEW CULVERT W / E.S.	54.00	12	44.00						2.00						
LT. 500+87.00	30' F.E. / (500N)	NEW CULVERT W / E.S.		12	44.00						2.00						
RT. 2115+95.00	F.E.	REMOVE ENTRANCE	18.00														
LT. 2116+15.00	F.E.	REMOVE ENTRANCE	40.00														
LT. 2117+40.00	30' F.E.	NEW CULVERT W / E.S.		18			48.00						2.00				
RT. 2128+86.00	30' F.E.	NEW CULVERT W / E.S.	28.50	18			50.00						2.00				
LT. 2129+94.12	30' F.E.	NEW CULVERT W / E.S.	28.60	18			50.00						2.00				
RT. 2131+49.25	N/A	ADD CULVERT		18			56.00						1.00				
RT. 2132+82.30	12' P.E.	NEW CULVERT W / E.S.	28.50	18			76.00										4.80
RT. 2133+08.20	12' P.E.	NEW CULVERT W / E.S.	28.60	18			42.00						1.00				4.80
LT. 2142+13.70	N/A	REMOVE ENTRANCE	28.50														
RT. 2147+59.70	N/A	REMOVE ENTRANCE	28.50														
RT. 2148+30.00	30' F.E.	NEW CULVERT W / E.S.		15		48.00						2.00					
RT. 2167+54.00	MBTO	DELETE MBTO / DELETE PIPE	12.60														
RT. 2166+49.00	DITCH CULVERT	NEW CULVERT W / E.S.		15		50.00						1.00					
RT. 2167+01.00	DITCH CULVERT	NEW CULVERT W / E.S.		15		98.00											
RT. 2168+01.00	DITCH CULVERT	NEW CULVERT W / E.S.		15		46.00						1.00					
LT. 2168+65.00	F.E.	REMOVE ENTRANCE	25.00														
RT. 599+13.00	30' F.E. / (600N)	NEW CULVERT W / E.S.		15		46.00						2.00					
LT. 2169+35.00	F.E.	REMOVE ENTRANCE	16.00														
LT. 2173+75.00	30' F.E.	NEW CULVERT W / E.S.		24					50.00					2.00			
LT. 2175+64.30	F.E.	REMOVE ENTRANCE	29.00														
LT. 2182+45.00	30' F.E.	NEW CULVERT W / E.S.	29.00	24					52.00						2.00		
RT. 2184+84.10	16' P.E.	NEW CULVERT W / E.S.	29.00	21				40.00						2.00			
RT. 2186+76.50	16' P.E.	NEW CULVERT W / E.S.	32.50	21				40.00						2.00			
RT. 2188+45.00	30' C.E.	NEW CULVERT W / E.S.	38.00	21					52.00						2.00		
LT. 2195+54.24	30' F.E.	NEW CULVERT W / E.S.		21				50.00						2.00			
RT. 2197+00.00	30' F.E.	NEW CULVERT W / E.S.		21				50.00						2.00			
RT. 2201+96.20	F.E.	REMOVE ENTRANCE	29.00														

PLOT DATE = 8/12/2009
 FILE NAME = G:\DWG\WORK\PIV\DOT\PERSONNEL\0001445\70623-sht-5-schedule-champaign.dgn
 USER NAME = pier-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES-RURAL
CHAMPAIGN COUNTY

SCALE: N/A
 DATE: 07/17/09

DRAWN BY: B.B.P.
 CHECKED BY: G.A.E.