

SCHEDULE OF QUANTITIES – RURAL CHAMPAIGN COUNTY

SHEET 6 OF 27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	27
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• (205,57,105)RS-2 ** CHAMPAIGN & DOUGLAS				

PIPE CULVERT SCHEDULE FOR ENTRANCES. (CONT.)

STATION	DESCRIPTION	PROPOSED TREATMENT	50105220	N/A	542D0217	542D0220	542D0223	542D0226	542D0229	542D5473	54213447	54213450	54213453	54213456	54213459	54214293	20800150
			PIPE CULVERT REMOVAL (FOOT)	PROPOSED PIPE SIZE (INCH)	PIPE CULVERT CLASS D TYPE 1, 12: (FOOT)	PIPE CULVERT CLASS D TYPE 1, 15" (FOOT)	PIPE CULVERT CLASS D TYPE 1, 18" (FOOT)	PIPE CULVERT CLASS D TYPE 1, 21" (FOOT)	PIPE CULVERT CLASS D TYPE 1, 24" (FOOT)	PIPE CULVERT CLASS D EQRS, 18" (FOOT)	END SECTION 12" (EACH)	END SECTION 15" (EACH)	END SECTION 18" (EACH)	END SECTION 21" (EACH)	END SECTION 24" (EACH)	END SECTION EQRS, 18" (EACH)	TRENCH BACKFILL (CU YD)
LT.	2201+97.00	F.E.	REMOVE ENTRANCE	28.80													
LT.	2212+61.80	F.E.	REMOVE ENTRANCE	27.00													
LT.	2215+55.00	30' F.E.	NEW CULVERT W / E.S.		15		48.00					2.00					
RT.	2216+30.20	F.E.	REMOVE ENTRANCE	28.20													
LT.	2216+42.70	F.E.	REMOVE ENTRANCE	28.00													
RT.	2218+54.80	MBTO	NO PIPE / REMOVE MBTO														
LT.	2218+68.70	18' P.E.	NEW CULVERT W / E.S.	32.30	15		40.00					2.00					
RT.	701+50.00	30' F.E. / (700N)	NEW CULVERT W / E.S.		15		48.00					2.00					
LT.	2235+31.02	30' F.E.	REMOVE PIPE / SUMMIT	28.40													
RT.	2235+45.50	30' F.E.	REMOVE ENTRANCE	28.40													
RT.	2248+10.00	30' F.E.	NEW CULVERT W / E.S.		18			48.00					2.00				
LT.	2248+44.00	30' F.E.	NEW CULVERT W / E.S.	28.40	15		46.00					2.00					
LT.	2255+02.40	30' F.E.	NEW CULVERT W / E.S.	24.00	15		46.00					2.00					
RT.	2255+12.90	F.E.	REMOVE ENTRANCE	28.40													
LT.	2256+31.60	30' F.E.	NEW CULVERT W / E.S.		15		50.00					2.00					
RT.	2259+08.00	MBTO	NO PIPE / REMOVE MBTO														
LT.	2259+21.90	18' P.E.	NEW CULVERT W / E.S.	28.60	15		40.00					2.00					
LT.	2261+95.00	30' F.E.	NEW CULVERT W / E.S.	28.50	15		48.00					2.00					
RT.	2268+34.00	F.E.	NO PIPE / REMOVE ENTRANCE														
LT.	2268+43.00	30' F.E.	NEW CULVERT W / E.S.	28.40	18					46.00						2.00	
RT.	800+78.00	30' F.E. / (800N)	NEW CULVERT W / E.S.		12	44.00					2.00						
LT.	2275+53.00	F.E.	REMOVE ENTRANCE	21.00													
LT.	2275+90.00	30' F.E.	NEW CULVERT W / E.S.		18			56.00					2.00				
RT.	2279+31.00	F.E.	REMOVE ENTRANCE	28.80													
RT.	2279+60.00	30' F.E.	NEW CULVERT W / E.S.		18			52.00				2.00					
RT.	2281+98.00	14' P.E.	NEW CULVERT W / E.S.	28.60	18			40.00				2.00					
TOTAL =			2499.20	N/A	176.00	1250.00	1170.00	230.00	888.00	46.00	8.00	52.00	40.00	10.00	28.00	2.00	22.00
USE =			2499.00	N/A	176.00	1250.00	1170.00	230.00	888.00	46.00	8.00	52.00	40.00	10.00	28.00	2.00	22.00
			(FOOT)	N/A	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(CU YD)

PLOT DATE = 8/12/2009
 FILE NAME = G:\DW\work\K\PIWIDOT\PERSONNEL\0001445\70623-sht-schedule-champaign.dgn
 USER NAME = pier_sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
**SCHEDULE OF QUANTITIES-RURAL
CHAMPAIGN COUNTY**
 SCALE: N/A
 DATE: 07/17/09
 DRAWN BY: B.B.P.
 CHECKED BY: G.A.E.