

SCHEDULE OF QUANTITIES – RURAL CHAMPAIGN COUNTY

SHEET 7 OF 27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	28
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• (205,57,105)RS-2 ** CHAMPAIGN & DOUGLAS				

PIPE CULVERT SCHEDULE FOR SIDEROADS

STATION	DESCRIPTION	PROPOSED TREATMENT	50105220	N/A	54200430	54200433	54200436	54200439	54213660	54213663	54213666	54213669	20900110	44201741
			PIPE CULVERT REMOVAL (FOOT)	PROPOSED PIPE SIZE (INCH)	PIPE CULVERT RCCP TYPE 1, 15" (FOOT)	PIPE CULVERT RCCP TYPE 1, 18" (FOOT)	PIPE CULVERT RCCP TYPE 1, 21" (FOOT)	PIPE CULVERT RCCP TYPE 1, 24" (FOOT)	CONC END SECTION 15" (EACH)	CONC END SECTION 18" (EACH)	CONC END SECTION 21" (EACH)	CONC END SECTION 24" (EACH)	POROUS GRANULAR BACKFILL (CU YD)	CLASS D PATCH TYPE II, 8 INCH (SQ YD)
LT. 1000+00.16	T.R. 1B / 1550 N	NEW CULVERT W / E.S.	48.00	21			47.00				2.00		10.00	13.40
RT. 1000+01.51	T.R. 1B / 1550 N	NEW CULVERT W / E.S.	50.00	21			46.00				2.00		13.30	16.00
RT. 1053+03.86	T.R. 307A / 100 N	NO PIPE												
LT. 1053+20.70	T.R. 307A / 100 N	NO PIPE												
LT. 1106+14.92	F.A.S. 527 / 200 N	NO PIPE												
RT. 1106+18.00	T.R. 303 / 200 N	NEW CULVERT W / E.S.	92.00	24				54.00				2.00	20.70	29.60
RT. 2005+55.63	F.A.S. 526 / BONGARD RD.	NO PIPE												
LT. 2009+03.04	T.R. 295B / 300N	NO PIPE												
RT. 2062+70.28	T.R. 285 / 400 N	NEW CULVERT W / E.S.	56.00	15	48.00				2.00				11.10	25.00
LT. 2062+89.00	T.R. 285 / 400 N	NEW CULVERT W / E.S.	53.40	15	46.00				2.00				10.60	26.60
LT. 2115+64.89	T.R. 275B / 500 N	NO PIPE												
RT. 2115+68.59	T.R. 275B / 500 N	NO PIPE												
LT. 2168+99.59	T.R. 269A / 600 N	NO PIPE												
RT. 2169+03.13	T.R. 269A / 600 N	NO PIPE												
LT. 2222+03.21	T.R. 265B / 700 N	NO PIPE												
RT. 2222+05.48	T.R. 265B / 700 N	NEW CULVERT W / E.S.	127.00	15	46.00				2.00				10.40	25.00
RT. 2275+01.96	ROOSEVELT RD. / 800 N	NEW CULVERT W / E.S.	127.60	18		48.00				2.00			9.50	13.40
LT. 2275+02.19	ROOSEVELT RD. / 800 N	NEW CULVERT W / E.S.	54.00	18		50.00				2.00			9.70	13.40
TOTAL =			608.00	N/A	140.00	98.00	93.00	54.00	6.00	4.00	4.00	2.00	95.30	162.40
USE =			608.00	N/A	140.00	98.00	93.00	54.00	6.00	4.00	4.00	2.00	95.00	162.00
			(FOOT)	N/A	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(CU YD)	(SQ YD)

PLOT DATE = 8/12/2009
 FILE NAME = G:\DW\work\K\PWDOT\PERSONNEL\DO01445\70623-sht7-schedule-champaign.dgn
 USER NAME = piersonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
**SCHEDULE OF QUANTITIES-RURAL
 CHAMPAIGN COUNTY**

SCALE: N/A
 DATE: 07/29/09

DRAWN BY: B.B.P.
 CHECKED BY: G.A.E.