

# SCHEDULE OF QUANTITIES – RURAL CHAMPAIGN COUNTY

SHEET 9 OF 27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	30
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
• (205,57,105)RS-2 ** CHAMPAIGN & DOUGLAS				

### ACROSS ROAD BOX CULVERT SCHEDULE

DESCRIPTION	STATION	54010503	54020602	54020705	54020802	54020804	54021002	54021004	54021202	54021203	44201747	50200100	20700220	51500100
		PCBC 5' X 3'  (FT)	PCBC 6' X 2' (M273)  (FT)	PCBC 7' X 5' (M273)  (FT)	PCBC 8' X 2' (M273)  (FT)	PCBC 8' X 4' (M273)  (FT)	PCBC 10' X 2' (M273)  (FT)	PCBC 10' X 4' (M273)  (FT)	PCBC 12' X 2' (M273)  (FT)	PCBC 12' X 3' (M273)  (FT)	CLASS D PATCH TYPE IV, 8 INCH  (SQ YD)	STRUCTURE EXCAVATION  (CU YD)	POROUS GRANULAR EMBANKMENT  (CU YD)	NAME PLATES  (EACH)
CULVERT NO. 1	1109+00.00	57.00									72.00	171.00	100.00	
CULVERT NO. 2	1114+71.00	59.00									80.00	200.00	130.00	
CULVERT NO. 3	1145+38.00							84.00			126.00	261.00	96.00	1.00
CULVERT NO. 4	2013+50.00			42.00							80.00	119.00	99.00	1.00
CULVERT NO. 5	2025+00.00									45.00	92.00	174.00	94.00	1.00
CULVERT NO. 6	2030+82.00									43.00	90.00	213.00	87.00	1.00
CULVERT NO. 7	2116+20.00								39.00		74.00	157.00	54.00	1.00
CULVERT NO. 8	2140+90.00		78.00								74.00	127.00	45.00	1.00
CULVERT NO. 9	2169+55.00								39.00		74.00	159.00	53.00	1.00
CULVERT NO. 10	2171+00.00								39.00		74.00	150.00	46.00	1.00
CULVERT NO. 11	2224+94.00						80.00				106.00	192.00	62.00	1.00
CULVERT NO. 12	2237+60.00						48.00				84.00	155.00	113.00	1.00
CULVERT NO. 13	2264+91.00					88.00					112.00	251.00	121.00	1.00
CULVERT NO. 14	2280+50.00				42.00						58.00	115.00	55.00	1.00
<b>TOTAL =</b>		116.00 (FT)	78.00 (FT)	42.00 (FT)	42.00 (FT)	88.00 (FT)	128.00 (FT)	84.00 (FT)	117.00 (FT)	88.00 (FT)	1196.00 (SQ YD)	2444.00 (CU YD)	1155.00 (CU YD)	12.00 (EACH)

**NOTE:**  
 A CLASS D PATCH, 8 INCH WILL BE USED WITH POROUS GRANULAR EMBANKMENT AS SHOWN IN THE POROUS GRANULAR DETAIL FOR EACH STRUCTURE.  
 THE REMOVAL OF THE EXISTING 13 1/4" PAVEMENT WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CLASS D PATCH OF THE TYPE AND SIZE SPECIFIED.

### ACROSS ROAD BOX CULVERT SCHEDULE, (CON'T)

DESCRIPTION	STATION	54001001	54001002	54001003	54001004	54001005	54001006	54001007	54001008	54001009	54001010	54001011	54001012	54001013	54001014
		BOX CULVERT END SECTION CULVERT NO. 1  (EACH)	BOX CULVERT END SECTION CULVERT NO. 2  (EACH)	BOX CULVERT END SECTION CULVERT NO. 3  (EACH)	BOX CULVERT END SECTION CULVERT NO. 4  (EACH)	BOX CULVERT END SECTION CULVERT NO. 5  (EACH)	BOX CULVERT END SECTION CULVERT NO. 6  (EACH)	BOX CULVERT END SECTION CULVERT NO. 7  (EACH)	BOX CULVERT END SECTION CULVERT NO. 8  (EACH)	BOX CULVERT END SECTION CULVERT NO. 9  (EACH)	BOX CULVERT END SECTION CULVERT NO. 10  (EACH)	BOX CULVERT END SECTION CULVERT NO. 11  (EACH)	BOX CULVERT END SECTION CULVERT NO. 12  (EACH)	BOX CULVERT END SECTION CULVERT NO. 13  (EACH)	BOX CULVERT END SECTION CULVERT NO. 14  (EACH)
CULVERT NO. 1	1109+00.00	2.00													
CULVERT NO. 2	1114+71.00		2.00												
CULVERT NO. 3	1145+38.00			2.00											
CULVERT NO. 4	2013+50.00				2.00										
CULVERT NO. 5	2025+00.00					2.00									
CULVERT NO. 6	2030+82.00						2.00								
CULVERT NO. 7	2116+20.00							2.00							
CULVERT NO. 8	2140+90.00								2.00						
CULVERT NO. 9	2169+55.00									2.00					
CULVERT NO. 10	2171+00.00										2.00				
CULVERT NO. 11	2224+94.00											2.00			
CULVERT NO. 12	2237+60.00												2.00		
CULVERT NO. 13	2264+91.00													2.00	
CULVERT NO. 14	2280+50.00														2.00
<b>TOTAL =</b>		2.00 (EACH)	2.00 (EACH)	2.00 (EACH)	2.00 (EACH)	2.00 (EACH)	2.00 (EACH)	2.00 (EACH)	2.00 (EACH)	2.00 (EACH)	2.00 (EACH)	2.00 (EACH)	2.00 (EACH)	2.00 (EACH)	2.00 (EACH)

PLOT DATE = 8/12/2009  
 FILE NAME = G:\DWG\WORK\PIVOT\PERSONNEL\0001445\70623-sht-9-schedule-ctampain.dgn  
 USER NAME = piersonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES-RURAL  
 CHAMPAIGN COUNTY**  
 SCALE: N/A  
 DATE: 07/29/09  
 DRAWN BY: B.B.P.  
 CHECKED BY: G.A.E.