

# SCHEDULE OF QUANTITIES – RURAL CHAMPAIGN COUNTY

SHEET 14 OF 27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	35
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
• (205,57,105)RS-2 ** CHAMPAIGN & DOUGLAS				

**INCIDENTAL HOT-MIX ASPHALT SURFACE SCHEDULE**

STATION	DESCRIPTION	INCIDENTAL AREA (SQ FT)	AVERAGE THICKNESS (INCH)	40800050	40800010	40800030	40800982	44000196	35101400	44000200	40200800	REMARKS
				INCIDENTAL HOT-MIX ASPHALT SURFACING (TON)	BIT MAT'L PRIME COAT (GALLONS)	AGGREGATE PRIME COAT (TON)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL - SPECIAL (SQ YD)	AGGREGATE BASE COURSE, TYPE B (TON)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	AGGREGATE SURFACE COURSE, TYPE B (TON)	
LT. 1000+00.16	T.R. 1B / 1550N	2441.00	2.50	37.97	27.12	0.54	59.00	52.00	23.00			IMPROVE TURNING RADIUS
RT. 1000+01.51	T.R. 1B / 1550N	1396.00	2.25	19.54	15.51	0.31	44.00	47.00	8.00			IMPROVE TURNING RADIUS
LT. 1550+90.00	30' F.E. / 1550N			0.00	0.00	0.00					18.00	6" AGG TO ROW
LT. 1002+69.00	16' P.E.	415.00	2.00	5.16	4.61	0.09		36.00	6.00	9.00	3.00	10 FT BIT / 15 FT AGG
RT. 1002+70.00	30' F.E.									10.00	31.00	REMOVE APRON / 6" AGG TO ROW
RT. 1013+26.30	30' F.E.									8.00	31.00	REMOVE APRON / 6" AGG TO ROW
LT. 1013+50.70	F.E.									8.00		REMOVE ENTRANCE
LT. 1025+80.00	30' F.E.										31.00	NEW ENTRANCE / 6" AGG TO ROW
RT. 1027+00.00	30' F.E.										31.00	NEW ENTRANCE / 6" AGG TO ROW
RT. 1030+30.00	30' F.E.										31.00	NEW ENTRANCE / 6" AGG TO ROW
RT. 1033+18.40	F.E.									16.00		REMOVE ENTRANCE
LT. 1039+62.70	30' F.E.									9.00	31.00	REMOVE APRON / 6" AGG TO ROW
RT. 1039+83.00	F.E.									9.00		REMOVE ENTRANCE
LT. 1051+70.00	30' F.E.										31.00	NEW ENTRANCE / 6" AGG TO ROW
RT. 1053+03.86	T.R. 307A / 100N	2417.00	3.00	45.12	26.86	0.54	59.00	40.00	25.00			IMPROVE TURNING RADIUS
LT. 1053+20.70	T.R. 307A / 100N	2288.00	2.75	39.15	25.42	0.51	51.00	37.00	23.00			IMPROVE TURNING RADIUS
RT. 100+87.00	30' F.E.										12.00	6" AGG TO ROW
RT. 1053+42.10	F.E.											REMOVE ENTRANCE
RT. 1054+30.00	30' F.E.										31.00	6" AGG TO ROW
RT. 1065+15.05	18' P.E.	445.00	6.00	16.61	4.94	0.10			4.00	14.00	9.00	10 FT BIT / 15 FT AGG
RT. 1068+15.00	20' P.E.	455.00	2.25	6.37	5.06	0.10		28.00	9.00	11.00	3.00	10 FT BIT / 15 FT AGG
LT. 1068+15.00	MBTO	180.00	2.25	2.52	2.00	0.04			8.00			ADD APRON
RT. 1069+75.00	30' F.E.									11.00	31.00	REMOVE APRON / 6" AGG TO ROW
LT. 1072+93.40	30' F.E.										31.00	6" AGG TO ROW
LT. 1080+00.00	30' F.E.										31.00	6" AGG TO ROW
LT. 1091+94.60	14' P.E.	712.00	2.25	9.97	7.91	0.16	55.00		10.00	9.00		RESURFACE TO ROW
RT. 1092+77.60	30' F.E.									12.00	31.00	REMOVE APRON / 6" AGG TO ROW
LT. 1092+84.50	14' P.E. W/ MBTO	524.00	2.25	7.34	5.82	0.12			21.00	16.00	2.00	10 FT BIT / 15 FT AGG
LT. 1096+58.50	16' P.E. W / MBTO	528.00	5.50	18.07	5.87	0.12			16.00	21.00	3.00	10 FT BIT / 15 FT AGG
LT. 1098+96.10	16' P.E.	416.00	2.25	5.82	4.62	0.09		31.00	7.00	23.00	2.00	10 FT BIT / 15 FT AGG
LT. 1102+53.00	MBTO	182.00	2.25	2.55	2.02	0.04			8.00	10.00		HMA FOR MBTO
LT. 1103+14.60	14' P.E.	476.00	4.50	13.33	5.29	0.11			12.00	11.00	3.00	10 FT BIT / 15 FT AGG
LT. 1103+63.00	P.E.									22.00		REMOVE APRON
RT. 1104+86.50	14' P.E.	374.00	3.50	8.14	4.16	0.08			9.00	10.00	2.00	10 FT BIT / 15 FT AGG
LT. 1106+14.92	F.A.S. 527 / 200N	4755.00	2.00	59.17	52.83	1.06	524.00		4.00			RESURFACE TO BACK OF RADIUS
RT. 1106+18.00	T.R. 303 / 200N	1831.00	2.50	28.48	20.34	0.41	92.00		7.00			IMPROVE TURNING RADIUS
LT. 1119+69.10	20' F.E.									12.00	27.00	REMOVE APRON / 6" AGG TO FENCE
RT. 1123+41.50	30' F.E.									10.00	31.00	REMOVE APRON / 6" AGG TO 40'
RT. 1126+62.00	30' F.E.									8.00	31.00	REMOVE APRON / 6" AGG TO ROW
RT. 1132+71.20	16' P.E.	415.00	6.00	15.49	4.61	0.09			7.00	8.00	5.00	10 FT BIT / 15 FT AGG
LT. 1132+71.20	MBTO	179.00	2.25	2.51	1.99	0.04			4.00	15.00		HMA FOR MBTO
RT. 1133+53.50	16' P.E.	554.00	4.00	13.79	6.16	0.12			13.00	12.00	7.00	10 FT BIT / 15 FT AGG
LT. 1133+61.00	20' F.E.									6.00	21.00	REMOVE APRON / 6" AGG TO FENCE
RT. 1133+69.80	14' F.E.											COMBINED ENTRANCE
LT. 1141+32.00	20' F.E.									6.00	23.00	REMOVE APRON / 6" AGG TO FENCE
RT. 1147+09.68	30' F.E.									14.00	31.00	REMOVE APRON / 6" AGG TO ROW
LT. 2005+20.00	30' F.E.									6.00	31.00	REMOVE APRON / 6" AGG TO ROW
RT. 2005+55.63	F.A.S. 526 / BONGARD RD.	5776.00	2.00	71.88	64.18	1.28	604.00		17.00			RESURFACE PER DETAIL SHEETS
LT. 2009+03.04	T.R. 295B / 300N	2330.00	2.25	32.62	25.89	0.52	100.00					RESURFACE PER DETAIL SHEETS
RT. 2016+40.30	14' P.E.	410.00	2.25	5.74	4.56	0.09		33.00	6.00	24.00	3.00	10 FT BIT / 15 FT AGG

PLOT DATE = 8/12/2009  
 FILE NAME = G:\DW\WORK\PROJECTS\70623-SHT-SCHEDULE-CHAMPAIGN.DGN  
 USER NAME = pier\_sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES-RURAL**  
**CHAMPAIGN COUNTY**  
 SCALE: N/A  
 DATE: 07/22/09  
 DRAWN BY: B.B.P.  
 CHECKED BY: G.A.E.