

SCHEDULE OF QUANTITIES – RURAL CHAMPAIGN COUNTY

SHEET 15 OF 27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	36
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• (205,57,105)RS-2 ** CHAMPAIGN & DOUGLAS				

INCIDENTAL HOT-MIX ASPHALT SURFACE SCHEDULE, (CON'T)

STATION	DESCRIPTION	INCIDENTAL AREA (SQ FT)	AVERAGE THICKNESS (INCH)	40800050	40800010	40800030	40600982	44000196	35101400	44000200	40200800	REMARKS
				INCIDENTAL HOT-MIX ASPHALT SURFACING (TON)	BIT MAT'L PRIME COAT (GALLONS)	AGGREGATE PRIME COAT (TON)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL - SPECIAL (SQ YD)	AGGREGATE BASE COURSE, TYPE B (TON)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	AGGREGATE SURFACE COURSE, TYPE B (TON)	
RT. 2018+62.00	20' F.E.									10.00	23.00	REMOVE APRON / 6" AGG TO ROW
RT. 2027+12.50	18' P.E.	660.00	2.25	9.24	7.33	0.15	50.00		10.00	7.00		RESURFACE TO ROW
LT. 2028+19.50	20' F.E.									5.00	24.00	REMOVE APRON / 6" AGG TO ROW
LT. 2035+72.30	12.5' P.E.	690.00	2.25	9.66	7.67	0.15	60.00		8.00	8.00		RESURFACE TO ROW
RT. 2049+42.50	30' F.E.									8.00	34.00	REMOVE APRON / 6" AGG TO ROW
RT. 2057+10.70	MBTO	180.00	2.25	2.52	2.00	0.04		18.00	2.00	11.00		HMA FOR MBTO
LT. 2057+10.70	24' P.E.	495.00	3.00	9.24	5.50	0.11		27.00	11.00	12.00	4.00	10 FT BIT / 15 FT AGG
RT. 2060+75.00	30' F.E.										34.00	6" AGG TO ROW
RT. 2062+70.28	T.R. 285 / 400N	2400.00	3.00	44.80	26.67	0.53	47.00	37.00	30.00			IMPROVE TURNING RADIUS
LT. 2062+89.00	T.R. 285 / 400N	2263.00	3.00	42.24	25.14	0.50	41.00	55.00	28.00			IMPROVE TURNING RADIUS
RT. 400+87.00	30' F.E.										12.00	NEW ENTRANCE / 6" AGG TO ROW
LT. 400+87.00	30' F.E.										12.00	NEW ENTRANCE / 6" AGG TO ROW
LT. 2070+75.00	30' F.E.									10.00	31.00	REMOVE APRON / 6" AGG TO ROW
RT. 2074+07.00	F.E.									11.00		REMOVE APRON
LT. 2088+16.00	16' P.E.	420.00	3.00	7.84	4.67	0.09		7.00	9.00	9.00	4.00	10 FT BIT / 20 FT AGG
RT. 2088+93.00	14' P.E. W/ MBTO	523.00	2.25	7.32	5.81	0.12		10.00	16.00	16.00	5.00	10 FT BIT / 18 FT AGG
LT. 2089+24.00	14' P.E.	395.00	5.00	12.29	4.39	0.09		9.00	11.00	11.00	3.00	10 FT BIT / 20 FT AGG
LT. 2089+90.00	30' F.E.										34.00	ADD ENTRANCE
RT. 2094+14.50	30' F.E.										34.00	6" AGG TO ROW
LT. 2109+07.01	30' F.E.										34.00	6" AGG TO ROW
RT. 2115+21.00	F.E.											REMOVE ENTRANCE
LT. 2115+64.89	T.R. 275B / 500N	2410.00	3.00	44.99	26.78	0.54	62.00		16.00			IMPROVE TURNING RADIUS
RT. 2115+68.59	T.R. 275B / 500N	2372.00	3.00	44.28	26.36	0.53	51.00	29.00	25.00			IMPROVE TURNING RADIUS
RT. 500+87.00	30' F.E.										11.00	6" AGG TO ROW
LT. 500+87.00	30' F.E.										12.00	6" AGG TO ROW
RT. 2115+95.00	F.E.											REMOVE ENTRANCE
LT. 2116+15.00	F.E.											REMOVE ENTRANCE
LT. 2117+40.00	30' F.E.										31.00	6" AGG TO ROW
RT. 2128+86.00	30' F.E.									11.00	31.00	REMOVE APRON / 6" AGG TO ROW
LT. 2128+94.12	30' F.E.										31.00	6" AGG TO ROW
RT. 2132+62.30	12' P.E. W/ MBTO	670.00	2.50	10.42	7.44	0.15	57.00		9.00	14.00		RESURFACE TO ROW
RT. 2133+08.20	12' P.E.	552.00	2.50	8.59	6.13	0.12	44.00		8.00	8.00		RESURFACE TO ROW
LT. 2142+13.70	F.E.									6.00		REMOVE ENTRANCE
RT. 2147+59.70	F.E.									10.00		REMOVE ENTRANCE
RT. 2148+30.00	30' F.E.										31.00	NEW ENTRANCE / 6" AGG TO ROW
RT. 2167+54.00	MBTO									30.00		REMOVE MBTO
LT. 2168+65.00	F.E.											REMOVE ENTRANCE
RT. 599+13.00	30' F.E. / (600N)										21.00	NEW ENTRANCE / 6" AGG TO ROW
LT. 2168+99.59	T.R. 269A / 600N	2494.00	2.50	38.80	27.71	0.55	68.00		12.00			IMPROVE TURNING RADIUS
RT. 2169+09.13	T.R. 269A / 600N	2461.00	2.50	38.28	27.34	0.55	64.00		13.00			IMPROVE TURNING RADIUS
LT. 2173+75.00	30' F.E.										31.00	NEW ENTRANCE / 6" AGG TO ROW
LT. 2175+64.30	F.E.									8.00		REMOVE ENTRANCE
LT. 2182+45.00	30' F.E.										31.00	6" AGG TO ROW
RT. 2184+84.10	16' P.E.	415.00	2.50	6.46	4.61	0.09		25.00	9.00	9.00	3.00	10 FT BIT / 15 FT AGG
RT. 2186+76.50	16' P.E.	415.00	2.50	6.46	4.61	0.09		25.00	9.00	8.00	3.00	10 FT BIT / 15 FT AGG
RT. 2188+45.00	30' C.E.	555.00	2.50	8.63	6.17	0.12		50.00	6.00	11.00	5.00	10 FT BIT / 15 FT AGG
LT. 2195+54.24	30' F.E.										31.00	NEW ENTRANCE / 6" AGG TO ROW
RT. 2197+00.00	30' F.E.										34.00	NEW ENTRANCE / 6" AGG TO ROW
RT. 2201+96.20	F.E.									10.00		REMOVE ENTRANCE
LT. 2201+97.00	F.E.									8.00		REMOVE ENTRANCE

PLOT DATE = 8/12/2009
 FILE NAME = G:\DW\WORK\PROJECTS\70623-SHT-SCHEDULE-CHAMPAIGN.dgn
 USER NAME = pier sonbr