

# SCHEDULE OF QUANTITIES - RURAL CHAMPAIGN COUNTY

SHEET 21 OF 27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	42
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
• (205,57,105)RS-2 ** CHAMPAIGN & DOUGLAS				

## SEEDING SCHEDULE

STATION	TO	STATION	LOCATION	25000200 SEEDING, CLASS 2 (SQ FT)	25000400 NITROGEN (90.0 LB / ACRE)	25000500 PHOSPHORUS (90.0 LB / ACRE)	25000600 POTASSIUM (90.0 LB / ACRE)	25100115 MULCH (SQ FT)
RT. 1548+75.00	TO	RT. 1549+60.00	T.R. 1B / 1150N	976.00	2.02	2.02	2.02	976.00
LT. 1548+75.00	TO	LT. 1549+60.00	T.R. 1B / 1150N	1554.00	3.21	3.21	3.21	1554.00
RT. 1550+40.00	TO	RT. 1551+25.00	T.R. 1B / 1150N	1088.00	2.25	2.25	2.25	1088.00
LT. 1550+40.00	TO	LT. 1551+25.00	T.R. 1B / 1150N	1666.00	3.44	3.44	3.44	1666.00
RT. 1000+30.00	TO	RT. 1052+80.00	IL RTE. 130	119543.00	246.99	246.99	246.99	119543.00
LT. 1000+30.00	TO	LT. 1053+00.00	IL RTE. 130	120315.00	248.58	248.58	248.58	120315.00
RT. 98+75.00	TO	RT. 99+60.00	T.R. 307A / 100N	812.00	1.68	1.68	1.68	812.00
LT. 98+75.00	TO	LT. 99+60.00	T.R. 307A / 100N	941.00	1.94	1.94	1.94	941.00
RT. 100+40.00	TO	RT. 101+25.00	T.R. 307A / 100N	1153.00	2.38	2.38	2.38	1153.00
LT. 100+40.00	TO	LT. 101+25.00	T.R. 307A / 100N	1527.00	3.15	3.15	3.15	1527.00
RT. 1053+20.00	TO	RT. 1106+00.00	IL RTE. 130	120155.00	248.25	248.25	248.25	120155.00
LT. 1053+40.00	TO	LT. 1105+80.00	IL RTE. 130	119679.00	247.27	247.27	247.27	119679.00
RT. 198+75.00	TO	RT. 199+50.00	F.A.S. 527 / 200N	2503.00	5.17	5.17	5.17	2503.00
LT. 198+75.00	TO	LT. 199+50.00	F.A.S. 527 / 200N	1933.00	3.99	3.99	3.99	1933.00
RT. 200+50.00	TO	RT. 201+25.00	T.R.303 / 200N	1010.00	2.09	2.09	2.09	1010.00
LT. 200+50.00	TO	LT. 201+25.00	T.R.303 / 200N	1414.00	2.92	2.92	2.92	1414.00
RT. 1106+50.00	TO	RT. 1149+47.99 (BK)	IL RTE. 130	119169.00	246.22	246.22	246.22	119169.00
LT. 1106+40.00	TO	LT. 1149+47.99 (BK)	IL RTE. 130	121230.00	250.48	250.48	250.48	121230.00
RT. 1997+74.14 (AH)	TO	RT. 2005+15.00	IL RTE. 130	19492.00	40.27	40.27	40.27	19492.00
LT. 1997+74.14 (AH)	TO	LT. 2008+50.00	IL RTE. 130	25066.00	51.79	51.79	51.79	25066.00
RT. 301+00.00	TO	RT. 301+75.00	F.A.S 526 / BONGARD RD	1597.00	3.30	3.30	3.30	1597.00
LT. 300+50.00	TO	LT. 301+50.00	F.A.S 526 / BONGARD RD	1842.00	3.81	3.81	3.81	1842.00
RT. 299+00.00	TO	RT. 299+50.00	T.R.295B / 300N	942.00	1.95	1.95	1.95	942.00
LT. 299+00.00	TO	LT. 299+50.00	T.R.295B / 300N	800.00	1.65	1.65	1.65	800.00
RT. 2005+70.00	TO	RT. 2062+50.00	IL RTE. 130	135222.00	279.38	279.38	279.38	135222.00
LT. 2009+40.00	TO	LT. 2062+70.00	IL RTE. 130	126711.00	261.80	261.80	261.80	126711.00
RT. 399+00.00	TO	RT. 399+60.00	T.R. 285 / 400N	804.00	1.66	1.66	1.66	804.00
LT. 399+00.00	TO	LT. 399+60.00	T.R. 285 / 400N	754.00	1.56	1.56	1.56	754.00
RT. 400+40.00	TO	RT. 401+25.00	T.R. 285 / 400N	1024.00	2.12	2.12	2.12	1024.00
LT. 400+40.00	TO	LT. 401+25.00	T.R. 285 / 400N	1082.00	2.24	2.24	2.24	1082.00
RT. 2062+90.00	TO	RT. 2076+00.00	IL RTE. 130	32380.00	66.90	66.90	66.90	32380.00
LT. 2063+10.00	TO	LT. 2076+00.00	IL RTE. 130	31471.00	65.02	65.02	65.02	31471.00

## SEEDING SCHEDULE, (CONT)

STATION	TO	STATION	LOCATION	25000200 SEEDING, CLASS 2 (SQ FT)	25000400 NITROGEN (90.0 LB / ACRE)	25000500 PHOSPHORUS (90.0 LB / ACRE)	25000600 POTASSIUM (90.0 LB / ACRE)	25100115 MULCH (SQ FT)
RT. 2083+00.00	TO	RT. 2115+50.00	IL RTE. 130	86291.00	178.29	178.29	178.29	86291.00
LT. 2083+00.00	TO	LT. 2115+50.00	IL RTE. 130	84310.00	174.19	174.19	174.19	84310.00
RT. 498+75.00	TO	RT. 499+60.00	T.R. 275B / 500N	863.00	1.78	1.78	1.78	863.00
LT. 498+75.00	TO	LT. 499+60.00	T.R. 275B / 500N	1837.00	3.80	3.80	3.80	1837.00
RT. 500+40.00	TO	RT. 501+25.00	T.R. 275B / 500N	1148.00	2.37	2.37	2.37	1148.00
LT. 500+40.00	TO	LT. 501+25.00	T.R. 275B / 500N	1099.00	2.27	2.27	2.27	1099.00
RT. 2115+90.00	TO	RT. 2168+85.00	IL RTE. 130	117476.00	242.72	242.72	242.72	117476.00
LT. 2115+90.00	TO	LT. 2168+80.00	IL RTE. 130	119717.00	247.35	247.35	247.35	119717.00
RT. 598+75.00	TO	RT. 599+60.00	T.R. 269A / 600N	1895.00	3.92	3.92	3.92	1895.00
LT. 598+75.00	TO	LT. 599+60.00	T.R. 269A / 600N	1889.00	3.90	3.90	3.90	1889.00
RT. 600+40.00	TO	RT. 601+00.00	T.R. 269A / 600N	810.00	1.67	1.67	1.67	810.00
LT. 600+40.00	TO	LT. 601+00.00	T.R. 269A / 600N	1115.00	2.30	2.30	2.30	1115.00
RT. 2169+30.00	TO	RT. 2221+80.00	IL RTE. 130	128275.00	265.03	265.03	265.03	128275.00
LT. 2169+30.00	TO	LT. 2221+80.00	IL RTE. 130	116467.00	240.63	240.63	240.63	116467.00
RT. 698+75.00	TO	RT. 699+57.00	T.R. 265B / 700N	1130.00	2.33	2.33	2.33	1130.00
LT. 698+75.00	TO	LT. 699+57.00	T.R. 265B / 700N	1116.00	2.31	2.31	2.31	1116.00
RT. 700+43.00	TO	RT. 701+85.00	T.R. 265B / 700N	2197.00	4.54	4.54	4.54	2197.00
LT. 700+43.00	TO	LT. 701+25.00	T.R. 265B / 700N	955.00	1.97	1.97	1.97	955.00
RT. 2222+30.00	TO	RT. 2274+80.00	IL RTE. 130	135669.00	280.31	280.31	280.31	135669.00
LT. 2222+30.00	TO	LT. 2274+80.00	IL RTE. 130	129087.00	266.71	266.71	266.71	129087.00
RT. 798+75.00	TO	RT. 799+60.00	ROOSEVELT RD / 800N	957.00	1.98	1.98	1.98	957.00
LT. 798+75.00	TO	LT. 799+60.00	ROOSEVELT RD / 800N	1409.00	2.91	2.91	2.91	1409.00
RT. 800+43.00	TO	RT. 801+25.00	ROOSEVELT RD / 800N	1085.00	2.24	2.24	2.24	1085.00
LT. 800+43.00	TO	LT. 801+25.00	ROOSEVELT RD / 800N	1249.00	2.58	2.58	2.58	1249.00
RT. 2275+25.00	TO	RT. 2285+00.00	IL RTE. 130	27786.00	57.41	57.41	57.41	27786.00
LT. 2275+25.00	TO	LT. 2285+00.00	IL RTE. 130	29112.00	60.15	60.15	60.15	29112.00
LT. 8+70.00	TO	LT. 9+60.00	SWALE / STA. 2237+60.00	3610.00	7.46	7.46	7.46	3610.00
LT. 18+75.00	TO	LT. 19+40.00	SWALE / STA. 2264+91.00	3258.00	6.73	6.73	6.73	3258.00
<b>CHAMPAIGN COUNTY TOTAL =</b>				2117667.00	4375.35	4375.35	4375.35	2117667.00
<b>USE =</b>				48.65	4375.00	4375.00	4375.00	48.65
				(ACRE)	(LB)	(LB)	(LB)	(ACRE)

### 25000350 SEEDING, CLASS 7

SEEDING, CLASS 7 IS CALCULATED FOR THE SAME AREAS AS SEEDING, CLASS 2

TOTAL =	2117667.00	SQ FT
USE =	48.65	ACRE

### 28000250 TEMPORARY EROSION CONTROL SEEDING

APPLICATION RATE = 100 LB / ACRE  
TEMPORARY EROSION CONTROL SEEDING IS CALCULATED FOR THE SAME AREAS AS SEEDING, CLASS 2

TOTAL =	48.65	ACRE
USE =	4865.00	LB

PLOT DATE = 8/12/2009  
 FILE NAME = G:\DW\work\K\PIWIDOT\PERSONNEL\000445\70623-sht+schedule-champaign.dgn  
 USER NAME = pier\_sombir

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES-RURAL  
CHAMPAIGN COUNTY**

SCALE: N/A  
DATE: 07/30/09  
DRAWN BY: B.B.P.  
CHECKED BY: G.A.E.