

SCHEDULE OF QUANTITIES – RURAL CHAMPAIGN COUNTY

SHEET 22 OF 27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	43
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• (205,57,105)RS-2 ** CHAMPAIGN & DOUGLAS				

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	QUANTITY (FT)
RT. 1127+20.73		RT. 1131+70.22	449.49
LT. 1128+31.99		LT. 1132+33.17	401.18
RT. 1143+63.75		RT. 1145+89.85	226.10
LT. 1144+13.87		LT. 1147+27.76	313.89
RT. 2011+45.80		RT. 2014+22.78	276.98
LT. 2012+76.70		LT. 2015+52.53	275.83
RT. 2262+96.92		RT. 2265+73.94	277.02
LT. 2264+08.98		LT. 2266+86.80	277.82
TOTAL =			2,498.31 FT
USE =			2,500.00 FT

63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS

STATION	TO	STATION	QUANTITY (FT)
RT. 1128+00.00		RT. 1131+00.00	300.00
LT. 1128+75.00		LT. 1131+50.00	275.00
RT. 1143+63.00		RT. 1145+00.50	137.50
LT. 1144+50.50		LT. 1145+00.50	50.00
RT. 1145+75.50		RT. 1146+13.00	37.50
LT. 1145+75.50		LT. 1147+13.00	137.50
RT. 2011+37.25		RT. 2013+12.25	175.00
LT. 2012+50.25		LT. 2013+25.25	75.00
RT. 2013+74.75		RT. 2014+49.75	75.00
LT. 2013+87.75		LT. 2015+62.75	175.00
RT. 2263+03.50		RT. 2264+53.50	150.00
LT. 2263+91.00		LT. 2264+53.50	62.50
RT. 2265+28.50		RT. 2265+91.00	62.50
LT. 2265+28.50		LT. 2266+78.50	150.00
TOTAL =			1862.50 FT

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

STATION	TO	STATION	QUANTITY (FT)
RT. 1145+00.50		RT. 1145+25.50	25.00
LT. 1145+00.50		LT. 1145+25.50	25.00
RT. 1145+50.50		RT. 1145+75.50	25.00
LT. 1145+50.50		LT. 1145+75.50	25.00
RT. 2013+12.25		RT. 2013+37.25	25.00
LT. 2013+25.25		LT. 2013+50.25	25.00
RT. 2013+49.75		RT. 2013+74.75	25.00
LT. 2013+62.75		LT. 2013+87.75	25.00
RT. 2264+53.50		RT. 2264+78.50	25.00
LT. 2264+53.50		LT. 2264+78.50	25.00
RT. 2265+03.50		RT. 2265+28.50	25.00
LT. 2265+03.50		LT. 2265+28.50	25.00
TOTAL =			300.00 FT

63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURE

STATION	TO	STATION	QUANTITY (FT)
RT. 1145+25.50		RT. 1145+50.50	25.00
LT. 1145+25.50		LT. 1145+50.50	25.00
RT. 2013+37.25		RT. 2013+49.75	12.50
LT. 2013+50.25		LT. 2013+62.75	12.50
RT. 2264+78.50		RT. 2265+03.50	25.00
LT. 2264+78.50		LT. 2265+03.50	25.00
TOTAL =			125.00 FT

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

STATION	TO	STATION	QUANTITY (EACH)
RT. 1127+50.00		RT. 1128+00.00	1.00
LT. 1128+25.00		LT. 1128+75.00	1.00
RT. 1131+00.00		RT. 1131+50.00	1.00
LT. 1131+50.00		LT. 1132+00.00	1.00
RT. 1143+13.00		RT. 1143+63.00	1.00
LT. 1144+00.50		LT. 1144+50.50	1.00
RT. 1146+13.00		RT. 1146+63.00	1.00
LT. 1147+13.00		LT. 1147+63.00	1.00
RT. 2010+87.25		RT. 2011+37.25	1.00
LT. 2012+00.25		LT. 2012+50.25	1.00
RT. 2014+49.75		RT. 2014+99.75	1.00
LT. 2015+62.75		LT. 2016+12.75	1.00
RT. 2262+53.50		RT. 2263+03.50	1.00
LT. 2263+41.00		LT. 2263+91.00	1.00
RT. 2265+91.00		RT. 2266+41.00	1.00
LT. 2266+78.50		LT. 2267+28.50	1.00
TOTAL =			16.00 EACH

78200405 GUARDRAIL MARKERS

STATION	TO	STATION	QUANTITY (EACH)
RT. 1128+00.00		RT. 1131+00.00	5.00
LT. 1128+75.00		LT. 1131+50.00	5.00
RT. 1143+63.00		RT. 1146+13.00	5.00
LT. 1144+50.50		LT. 1147+13.00	5.00
RT. 2011+37.25		RT. 2014+49.75	5.00
LT. 2012+50.25		LT. 2015+62.75	5.00
RT. 2263+03.50		RT. 2265+91.00	5.00
LT. 2263+91.00		LT. 2266+78.50	5.00
TOTAL =			40.00 EACH

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	QUANTITY (EACH)
RT. 1127+50.00	1.00
LT. 1128+25.00	1.00
RT. 1131+50.00	1.00
LT. 1132+00.00	1.00
RT. 1143+13.00	1.00
LT. 1144+00.50	1.00
RT. 1146+63.00	1.00
LT. 1147+63.00	1.00
RT. 2010+87.25	1.00
LT. 2012+00.25	1.00
RT. 2014+99.75	1.00
LT. 2016+12.75	1.00
RT. 2262+53.50	1.00
LT. 2263+41.00	1.00
RT. 2266+41.00	1.00
LT. 2267+28.50	1.00
TOTAL = 16.00 EACH	

X0324043 GRATING FOR CONCRETE HEADWALL

STATION	QUANTITY (EACH)
RT. 2025+00.00	1.00
LT. 2025+00.00	1.00
RT. 2030+82.00	1.00
LT. 2030+82.00	1.00
TOTAL = 4.00 EACH	

PLOT DATE = 8/12/2009
 FILE NAME = G:\DW\work\K\PIWIDOT\PERSONNEL\0000445\70623-sht+schedule-champain.dgn
 PLOT FILE = 02-3523 / IN.
 USER NAME = pier_sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION	
SCHEDULE OF QUANTITIES-RURAL	
CHAMPAIGN COUNTY	
SCALE: N/A	DRAWN BY: B.B.P.
DATE: 07/11/09	CHECKED BY: G.A.E.