

# SCHEDULE OF QUANTITIES – RURAL CHAMPAIGN COUNTY

SHEET 26 OF 27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	47
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* (205,57,105)RS-2 ** CHAMPAIGN & DOUGLAS				

**Z0022800 FENCE REMOVAL**

STATION	OFFSET (FT)	TO	STATION	OFFSET (FT)	PARCEL #	QUANTITY (FT)
1106+61.50	50.00	RT.	1106+63.50	62.00	N/A	12.00
1106+61.50	50.00	RT.	1106+73.50	50.00	N/A	12.00
1126+75.37	39.73	RT.	1130+55.56	40.50	5527011	383.00
2009+45.91	42.23	LT.	2013+34.88	41.29	5527014	391.00
2013+75.09	34.13	LT.	2024+10.50	36.35	5527014	1040.00
2021+19.13	34.31	LT.	2021+19.13	43.00	5527014	9.00
2024+05.00	43.00	LT.	2024+10.50	36.35	5527014	9.00
2024+10.50	36.35	LT.	2028+12.40	34.81	5527016	403.00
2028+26.90	34.51	LT.	2030+02.45	35.37	5527016	177.00
2301+55.06	35.90	RT.	2301+54.98	63.06	N/A	28.00
<b>TOTAL =</b>						<b>2484.00 FT</b>

**TREE REMOVAL**

STATION	OFFSET	RT.	20100110		20100210	
			6-15 UNITS DIAMETER (UNIT)	OVER 15 UNITS DIAMETER (UNIT)	6-15 UNITS DIAMETER (UNIT)	OVER 15 UNITS DIAMETER (UNIT)
1105+85.35	43.72	RT.	6.00			
1105+93.41	42.91	RT.	6.00			
1105+95.40	53.54	RT.	6.00			
1113+06.62	42.60	RT.			20.00	
1114+70.90	45.28	RT.	13.00			
1115+38.58	48.17	RT.	8.00			
1115+44.02	46.77	RT.	7.00			
1127+03.95	39.00	RT.	6.00			
1127+05.69	39.34	RT.	8.00			
1127+19.83	39.74	RT.	8.00			
1127+21.59	39.97	RT.	10.00			
1127+25.37	39.76	RT.	10.00			
1127+26.50	39.35	RT.	12.00			
1127+71.31	40.07	RT.	15.00			
1130+36.11	35.64	RT.			16.00	
1130+80.33	47.48	RT.			28.00	
1131+22.88	57.75	RT.	12.00			
1131+27.36	54.64	RT.	12.00			
1131+36.96	54.61	RT.	8.00			
1131+44.13	39.14	RT.	14.00			
1131+60.85	53.08	RT.	9.00			
1131+64.16	41.86	RT.	9.00			
2013+36.12	35.53	RT.	15.00			
2032+98.33	33.71	LT.	6.00			
2033+16.28	32.25	LT.			17.00	
2033+38.00	32.51	LT.	6.00			
2033+61.26	32.55	LT.			17.00	
2033+96.85	32.65	LT.	12.00			
2033+99.84	32.81	LT.			22.00	
2034+02.43	32.64	LT.			23.00	
2034+22.53	33.06	LT.	8.00			
2034+42.48	32.19	LT.			18.00	
2034+45.39	32.30	LT.			18.00	
2034+66.68	32.30	LT.	10.00			
2034+86.85	33.03	LT.	6.00			
2035+12.00	32.12	LT.	6.00			
2035+20.80	32.15	LT.	11.00			
2035+35.63	32.99	LT.			19.00	
2035+99.95	30.97	LT.	12.00			
2036+15.01	31.81	LT.	12.00			
2132+10.91	35.61	RT.			20.00	
2303+54.02	24.13	RT.			16.00	
2303+65.18	23.88	RT.			16.00	
2304+21.36	25.21	RT.			16.00	
<b>TOTAL =</b>			<b>283.00 UNIT</b>	<b>266.00 UNIT</b>		

**Z0064600 SELECTIVE CLEARING**

STATION	OFFSET (FT)	TO	STATION	OFFSET (FT)	PARCEL #	QUANTITY (ACRE)
1120+00.00	LT. 34 - 40		1127+60.00	LT. 34 - 40	5527011	0.10
1127+60.00	LT. 54 - 60		1132+00.00	LT. 54 - 60	5527011	0.06
1132+00.00	LT. 34 - 40		1147+00.00	LT. 34 - 40	5527011	0.21
2021+20.00	LT. 33 - 43		2024+20.00	LT. 33 - 43	5527014	0.07
2024+20.00	LT. 33 - 43		2031+00.00	LT. 33 - 43	5527016	0.16
<b>TOTAL =</b>						<b>0.60 ACRE</b>

**NOTES:**

- 1) SEE SPECIAL PROVISIONS FOR DESCRIPTION OF SELECTIVE CLEARING.
- 2) WITHIN THE SELECTIVE CLEARING LIMITS THERE ARE SEVERAL TREES THAT NEED TO BE SAVED. THEY ARE LISTED BELOW WITH STATION AND OFFSET.

**TREES TO BE SAVED**

STATION	OFFSET	STATION	OFFSET
1135+99.85	LT. 39.35	2022+91.02	LT. 41.08
1136+78.96	LT. 38.00	2023+00.91	LT. 43.61
1137+59.39	LT. 37.39	2023+00.92	LT. 43.67
2021+34.39	LT. 35.91	2023+02.14	LT. 38.61
2021+39.07	LT. 43.55	2023+13.67	LT. 42.33
2021+70.54	LT. 33.34	2023+29.22	LT. 41.95
2021+74.05	LT. 43.05	2023+44.03	LT. 39.66
2021+81.75	LT. 38.56	2023+66.97	LT. 42.37
2021+86.30	LT. 32.05	2024+45.30	LT. 36.19
2021+87.13	LT. 39.48	2024+70.77	LT. 38.18
2021+92.48	LT. 34.57	2025+31.78	LT. 38.06
2021+96.75	LT. 42.89	2025+64.58	LT. 41.45
2022+08.68	LT. 43.26	2025+80.95	LT. 34.56
2022+15.78	LT. 43.25	2025+84.28	LT. 35.59
2022+22.11	LT. 36.07	2026+26.71	LT. 34.96
2022+50.23	LT. 40.98	2026+30.27	LT. 36.64
2022+59.52	LT. 39.28	2026+40.84	LT. 34.02
2022+74.57	LT. 36.52	2026+64.04	LT. 33.81
2022+77.79	LT. 43.35	2027+71.93	LT. 34.16
2022+90.83	LT. 41.27	2028+04.84	LT. 33.51

**NOTE:**

COST TO SAVE TREES SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED WITH THE COST FOR THE VARIOUS TREE REMOVAL PAY ITEMS.

PLOT DATE = 8/12/2009  
 FILE NAME = G:\DW\WORK\K\PWIDOT\PERSONNEL\0001445\70623-sht+schedule-champain.dgn  
 USER NAME = pier\_sombir

ILLINOIS DEPARTMENT OF TRANSPORTATION	
<b>SCHEDULE OF QUANTITIES-RURAL</b>	
<b>CHAMPAIGN COUNTY</b>	
SCALE: N/A	DRAWN BY: B.B.P.
DATE: 08/01/09	CHECKED BY: G.A.E.