

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55		MCLEAN	210	8
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT		
* (57-4)R, HBY, HBR, (57-4)BIDM CONTRACT #10757				

LOCATION OF WORK:

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	1	2	3	4	3	5	6	7	8	9
				90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	
				CONSTRUCTION TYPE CODE									
				J000-2A ROADWAY I-55	I000-2A ROADWAY LINDEN ST.	X271-2A STRUCTURE BUS. RT. 51	X171-2A STRUCTURE S.P.C.S.L.	X271-2A STRUCTURE LINDEN ST.	SFTY-3J STRUCTURE TOWANDA	Y030-1E LIGHTING	Y002-1C SIGNING	Y002-1C SIGNING	Y045 BIKE PATH
M3021500	LIME	MTON	3,881.0	3,881.0									
M3110010	SUB-BASE GRANULAR MATERIAL, TYPE A	MTON	457.0		457.0								
M3112010	SUB-BASE GRANULAR MATERIAL, TYPE C	MTON	914.0		914.0								
M3120500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 100MM	SQ M	140,267.0	140,267.0									
M3510010	AGGREGATE BASE COURSE, TYPE A	MTON	1,020.0										1,020.0
M3552200	HOT-MIX ASPHALT BASE COURSE	MTON	4,234.0	4,234.0									
M4020010	AGGREGATE SURFACE COURSE, TYPE A	MTON	23.0		23.0								
M4021200	AGGREGATE FOR TEMPORARY ACCESS	MTON	20.0		20.0								
M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	14,912.0	2,451.0	8,327.0								4,134.0
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ M	138.0		138.0								
M4063305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	MTON	331.0										331.0
M4063315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	MTON	180.0	180.0									
M4075240	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 240MM	SQ M	1,061.0		1,061.0								
M4075280	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 280MM	SQ M	2,694.0		2,694.0								
M4205000	BRIDGE APPROACH PAVEMENT	SQ M	706.0					706.0					
M4205050	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ M	742.0			742.0							
M4210300	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 300MM	SQ M	62,313.0	62,313.0									
M4210330	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 330MM	SQ M	24,536.0	24,536.0									
M4214300	PAVEMENT REINFORCEMENT 300MM	SQ M	62,313.0	62,313.0									
M4214330	PAVEMENT REINFORCEMENT 330MM	SQ M	24,536.0	24,536.0									
M4215040	WIDE FLANGE BEAM TERMINAL JOINT COMPLETE 10.8 METER	EACH	2.0	2.0									
M4218000	PROTECTIVE COAT	SQ M	142,572.0	142,572.0									
M4400735	HOT-MIX ASPHALT SURFACE REMOVAL, 35MM	SQ M	2,147.0	2,147.0									
M4402000	PAVEMENT REMOVAL	SQ M	61,804.0	57,376.0	3,617.0								811.0
M4402060	APPROACH SLAB REMOVAL	SQ M	2,024.0	2,024.0									
M4402530	PAVED SHOULDER REMOVAL *SPECIALTY ITEMS	SQ M	23,393.0	23,393.0									

6/10/2009
PFL/EA

LAYOUT	JAR	
DRAWN	JAR	
REVIEWED	DJH	03/12/04

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 55
SECTION (57-4)R, HBY, HBR, (57-4)BIDM
MCLEAN COUNTY

REVISIONS	
NAME	DATE



JOB NO.
9452063
DATE
8/21/2009