

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55		MCLEAN	310	12
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT		
* (57-4)R, HBY, HBR, (57-4)BIDM CONTRACT #70757				

LOCATION OF WORK:

McLEAN CO.	1	2	3	4	3	5	6	7	8	9
	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	100% STATE	90% FED. 10% STATE

CODE NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE														
				J000-2A ROADWAY I-55	I000-2A ROADWAY LINDEN ST.	X271-2A STRUCTURE BUS. RT. 51	X171-2A STRUCTURE S.P.C.S.L.	X271-2A STRUCTURE LINDEN ST.	SFTY-3J STRUCTURE TOWANDA	Y030-1E LIGHTING	Y002-1C SIGNING	Y002-1C SIGNING	Y045 BIKE PATH					
*M7800415	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 150MM	METER	4,843.0	4,843.0														
M7830100	PAVEMENT MARKING REMOVAL	SQM	143.0	143.0														
M7830105	PAVEMENT MARKING REMOVAL	METER	10,001.0	9,522.0	479.0													
*M8100060	CONDUIT IN TRENCH, 50MM DIA., GALVANIZED STEEL	METER	1,105								1,105							
*M8101050	CONDUIT PUSHED, 50MM DIA., GALVANIZED STEEL	METER	135.0								135.0							
*M8110160	CONDUIT ATTACHED TO STRUCTURE, 50MM DIA., GALVANIZED STEEL	METER	48.0								48.0							
*M8120230	CONDUIT EMBEDDED IN STRUCTURE, 50 MM DIA. PVC	METER	2,452.0								2,452.0							
*M8120270	CONDUIT EMBEDDED IN STRUCTURE, 100 MM DIA. PVC	METER	4,360.0	4,360.0														
*M8130185	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 300MM X 250MM X 150MM	EACH	2.0								2.0							
*M8130228	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 400MM X 400MM X 150MM	EACH	1.0								1.0							
*M8130445	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 450MM X 150MM X 150MM	EACH	5								5							
*M8160230	UNIT DUCT, 2#6XLP, 1#6 XLP GROUND 25MM POLYETHYLENE	METER	340								340							
*M8170040	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	METER	7,725.0								7,725.0							
*M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	765								765							
*M8307900	LIGHT POLE, GALVANIZED STEEL, 9.0M M.H., TENON MOUNT	EACH	2.0								2.0							
*M8307940	LIGHT POLE, GALVANIZED STEEL, 15.2M M.H., TENON MOUNT	EACH	1.0								1.0							
*M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	3.4								3.4							
*M8360200	LIGHT POLE FOUNDATION, 750MM DIAMETER	METER	2.0								2.0							
*MX030149	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	METER	55.7									55.7						
*MX030463	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	METER	16.3									16.3						
MX032646	TREE REMOVAL AND CLEARING	HA	0.1															0.1
MX033509	CONCRETE RETAINING WALL	SQM	87.2															87.2
MX033738	DUCTILE IRON WATER CLASS 52 WITH POLYETHYLENE ENCASEMENT, 300MM DIA. MAIN	METER	138.0		138.0													
*MX033757	URETHANE PAVEMENT MARKING - LINE 100 MM	METER	19,258.0	19,258.0														
*MX033758	URETHANE PAVEMENT MARKING - LINE 200 MM	METER	1,727.0	1,727.0														
MX033761	ANCHOR BOLTS, M30	EACH	36.0					36.0										
MX033780	WORK ZONE PAVEMENT MARKING REMOVAL	METER	42,280.0	40,434.0	1,846.0													
MX502030	STRUCTURE EXCAVATION, RETAINING WALL *SPECIALTY ITEMS	CUM	192.0															192.0

8/20/2009
#FILES

LAYOUT	JUH	03/18/04
DRAWN	JUH	
REVIEWED	DEK	

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 55
SECTION (57-4)R, HBY, HBR, (57-4)BIDM
MCLEAN COUNTY

REVISIONS	
NAME	DATE



JOB NO.
94S2063
DATE
8/20/2009