

DRAINAGE SCHEDULE I-55

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	MCLEAN	310	34
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* (57-4)R, HBY, HBR, (57-4)B)DM CONTRACT #70757				

STRUCT. NO.	LOCATION		METAL END SECTIONS 300 mm (EACH)	END SECTIONS 375 mm (EACH)	DRAINAGE STRUCTURES		TYPE 1, W/ 2 TYPE 20 F & G (EACH)	TYPE 2, W/ 2 TYPE 22 F & G (EACH)	TYPE D INLET BOX (EACH)	CONNECT TO EXISTING OUTLET **	RIM OR FRAME & GRATE ELEVATION	CONCRETE THRUST BLOCKS (EACH)
	STATION	OFFSET			MH TYPE A, 1.2 M DIA. TYPE 1 CLOSED LID (EACH)	MH TYPE A, 1.2 M DIA. TYPE 20 F & G (EACH)						
I-55												
M-89	36+561.5	0.0					1			1	257.460	
M-90	36+642.2	0.0					1				257.862	
M-91	36+722.9	0.0					1				258.265	
M-92	36+803.6	0.0					1			1	258.668	
M-92A	36+803.6	3.122 LT			1					1		
M-93	36+927.0	0.0					1				259.694	
M-93A	36+927.0	3.122 LT			1							
M-94	36+966.5	0.0					1				260.191	
M-95	37+048.0	0.0					1			1	261.376	
M-96	37+125.6	0.0					1				262.514	
M-96A	37+125.6	3.122 LT			1							
M-97	37+203.2	0.0					1				263.653	
M-97A	37+203.2	3.122 LT			1							
M-98	37+280.8	0.0					1				264.791	
M-99	37+358.4	0.0					1				265.763	
M-100	37+436.0	SEE DETAIL					1				266.395	
M-101	NOT USED											
M-102	37+592.0	0.0					1				266.071	
M-103	37+672.0	0.0					1				265.481	
M-104	37+752.0	0.0					1				264.960	
M-105	37+775.5	0.0					1				264.915	
M-106	37+779.5	0.0						1			264.915	
M-107	37+810.4	0.0					1			1	264.972	
M-108	37+832.1	0.0					1				265.080	
M-109	37+912.1	0.0					1				265.968	
M-110	37+992.1	0.0					1			1	267.554	
M-111	38+072.7	0.0					1				269.279	
M-112	38+153.4	0.0					1				270.790	
M-113	38+234.0	0.0					1				271.898	
M-114	38+292.0	0.0					1				272.323	
M-115	38+446.0	0.0					1				272.207	
M-116	38+502.7	0.0					1			1	271.620	
M-117	38+506.0	0.0					1				271.675	
M-118	38+582.0	0.0					1				270.630	
M-119	38+636.4	0.0					1				269.503	
M-120	38+706.3	0.0					1				267.861	
M-121	38+776.2	0.0					1				265.891	
M-122	38+846.1	0.0					1			1	263.814	
M-123	38+934.9	0.0					1				261.326	
M-124	39+013.7	0.0					1				259.211	
M-125	39+097.5	0.0					1				257.765	
M-125A	39+097.5	3.122 LT			1						257.890	
M-126	39+181.3	0.0					1			1	256.989	
M-126A	39+181.3	3.122 LT			1						257.114	
M-127	39+248.3	0.0					1				256.659	
M-128	39+315.3	0.0					1				256.330	
M-128A	39+315.3	3.122 LT			1						256.455	
M-129	39+382.3	0.0					1				256.001	
M-129A	39+382.3	3.122 LT			1						256.126	
M-130	39+449.3	0.0					1				255.671	
M-130A	39+449.3	3.122 LT			1						255.796	
M-131	39+516.5	0.0					1			1	255.341	
M-131A	39+516.5	3.122 LT			1						255.466	
M-132	39+589.7	0.0					1				254.982	
M-133	39+662.9	0.0					1				254.622	
M-133A	39+662.9	3.122 LT			1						254.747	
M-134	39+736.1	0.0					1				254.267	
M-134A	39+736.1	3.122 LT			1						254.392	
M-135	39+809.3	0.0					1				253.907	
M-135A	39+809.3	3.122 LT			1						254.032	
M-136	39+882.3	0.0					1			1	253.549	
M-136A	39+882.3	3.122 LT			1						253.674	
M-137	39+966.1	0.0					1				253.137	
M-138	40+049.9	0.0					1				252.536	
M-138A	40+049.9	3.122 LT			1						252.661	
M-139	40+133.7	0.0					1				251.676	
M-139A	40+133.7	3.122 LT			1						251.801	
M-140	40+217.6	0.0					1			1	251.643	
M-140A	40+217.6	3.122 LT			1						251.768	
M-141A	40+171.4	0.0					1				251.555	
M-141B	40+175.1	0.0					1				251.555	
M-141C	40+175.1	3.122 LT			1						251.680	
S-37	38+572.4	0.0 RT								1	270.881	
S-37A	38+572.4	35.0 RT	1									1
S-38	38+570.8	0.0 LT								1	270.907	
S-38A	38+570.8	37.5 LT	1									1
LINDEN STREET												
L-1	1+080.0	5.1 LT			1							
L-2	1+145.0	5.1 LT			1							
I-55 SUBTOTALS			2		18	1	51	1	2	12		2
LINDEN STREET SUBTOTALS				2								
GRAND TOTALS			2	2	18	1	51	1	2	12		2

** COST INCLUDED IN PROPOSED PIPE

NOTE: SEE BIKE PATH DRAINAGE SCHEDULE FOR BIKE PATH DRAINAGE ITEMS.

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 55
SECTION (57-4)R, HBY, HBR, (57-4)B)DM
MCLEAN COUNTY

DRAINAGE SCHEDULE

REVISIONS	
NAME	DATE



JOB NO.
9452063
DATE
6/18/2009

LAYOUT: JSH 03/16/04
 DRAWN: JSH 03/16/04
 REVIEWED: DLH 03/18/04
 6/18/2009
 #FILE#