

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	80% FEDERAL 20% STATE IL 185			SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT		1000-2A			CODE NO.		UNIT			
21400100	GRADING AND SHAPING DITCHES	FOOT	300	300								
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	75	75								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	61	61								
40600300	AGGREGATE (PRIME COAT)	TON	286	286								
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	5,485	5,485								
40600895	CONSTRUCTING TEST STRIP	EACH	1	1								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	7,049	7,049								
40600990	TEMPORARY RAMP	SQ YD	122	122								
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	11,488	11,488								
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	676	676								
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	865	865								
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	12,823	12,823								
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	121,925	121,925								
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	150	150								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,307	3,307								
48203100	HOT-MIX ASPHALT SHOULDERS	TON	568	568								
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 <sup>FOOT</sup> POSTS	FOOT	50	50								
63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	10	10								
63200310	GUARDRAIL REMOVAL	FOOT	500	500								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4								
67100100	MOBILIZATION	L SUM	1	1								
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1								
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1								
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1								
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12,331	12,331								
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	126,346	126,346								
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	105	105								
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	690	690								
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	32	32								
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,395	1,395								
72000100	SIGN PANEL-TYPE 1	SQ FT	9	9								
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	14	14								
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	6,661	6,661								
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	105	105								
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	52	52								
78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	119,685	119,685								
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	638	638								
78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	32	32								
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	577	577								
78200410	GUARDRAIL MARKERS, TYPE A	EACH	20	20								
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	10	10								
<b>78300200</b>	<b>RAISED REFLECTIVE PAVEMENT MARKER REMOVAL</b>	<b>EACH</b>	<b>582</b>	<b>582</b>								

\*SPECIALTY ITEM