

SCHEDULE OF QUANTITIES

HOT-MIX ASPHALT SURFACE REMOVAL,

LOCATION	BUTT JT (SQ YD)	1 1/2" (SQ YD)	2 1/4" (SQ YD)	VAR DP (SQ YD)
F. A. P. 777 (IL 185)				
STA. 399+66.92 TO STA. 399+86.92	57.78			
STA. 399+86.92 TO STA. 429+64.00				8,600.45
STA. 429+64.00 TO STA. 430+62.00				364.78
STA. 430+62.00 TO STA. 431+65.00				457.78
STA. 431+65.00 TO STA. 432+00.00				155.56
STA. 432+00.00 TO STA. 435+37.00			1,497.78	
STA. 435+37.00 TO STA. 435+87.00			144.44	
STA. 435+87.00 TO STA. 439+00.00			1,391.11	
STA. 439+00.00 TO STA. 439+35.00				155.56
STA. 439+35.00 TO STA. 440+62.00				564.44
STA. 440+62.00 TO STA. 441+62.00				372.22
STA. 441+62.00 TO STA. 462+75.00				6,104.22
STA. 462+75.00 TO STA. 466+40.00				1,297.78
STA. 466+40.00 TO STA. 467+25.00				273.89
STA. 467+25.00 TO STA. 478+80.00				3,336.67
STA. 478+80.00 TO STA. 486+67.00				2,535.89
STA. 486+67.00 TO STA. 488+09.00				410.22
STA. 488+09.00 TO STA. 490+38.00				763.33
STA. 490+38.00 TO STA. 490+85.00				177.56
STA. 490+85.00 TO STA. 491+00.00				56.67
Resurfacing fr. 2 1/4" to 1 1/2" @ 490+85.00 (No Milling)				
STA. 492+18.09 TO STA. 492+48.09	113.33			
LIMITS OF IMPROVEMENT - 492+48.09				
BRIDGE OMISSION - S. N. 068-0027				
LIMITS OF IMPROVEMENT - STA. 492+91.29				
STA. 492+91.29 TO STA. 493+21.29	113.33			
STA. 499+04.95 TO STA. 499+34.95	126.67			
LIMITS OF IMPROVEMENT - STA. 499+34.95				
BRIDGE OMISSION - S. N. 068-0505				
LIMITS OF IMPROVEMENT - STA. 501+51.95				
STA. 501+51.95 TO STA. 501+81.95	113.33			
Resurfacing fr. 1 1/2" to 2 1/4" @ 505+64.50 (Begin Milling)				
STA. 505+50.00 TO STA. 505+65.00				56.67
STA. 505+65.00 TO STA. 507+83.00				823.56
STA. 507+83.00 TO STA. 508+74.00				303.33
STA. 508+74.00 TO STA. 740+20.00				66,866.22
STA. 740+20.00 TO STA. 743+70.00				1,127.78
STA. 743+70.00 TO STA. 788+20.00				12,855.56
STA. 788+20.00 TO STA. 789+30.00				186.39
PROJECT SUBTOTAL	524	0	3,033	107,847

HOT-MIX ASPHALT SURFACE REMOVAL, (CONT.)

LOCATION	BUTT JT (SQ YD)	1 1/2" (SQ YD)	2 1/4" (SQ YD)	VAR DP (SQ YD)
F. A. P. 777 (IL 185)				
STA. 789+30.00 TO STA. 789+65.00				63.19
STA. 789+65.00 TO STA. 791+00.00			495.00	
STA. 791+00.00 TO STA. 796+50.00			2,444.44	
STA. 796+50.00 TO STA. 797+00.00			227.78	
STA. 797+00.00 TO STA. 805+00.00			3,733.33	
STA. 805+00.00 TO STA. 806+98.00			748.00	
STA. 806+98.00 TO STA. 807+97.00			170.50	
STA. 807+97.00 TO STA. 808+32.00				101.11
STA. 808+32.00 TO STA. 848+83.00				11,702.89
STA. 848+83.00 TO STA. 849+18.00				101.11
STA. 849+18.00 TO STA. 849+50.00			103.11	
STA. 849+50.00 TO STA. 854+75.00			1,866.67	
STA. 854+75.00 TO STA. 855+10.00				124.44
STA. 855+10.00 TO STA. 859+40.70				1,531.38
STA. 859+40.70 TO STA. 860+98.00				454.42
STA. 860+98.00 TO STA. 861+18.00	57.78			
Mulberry Grove Rd.				
STA. 9+87.00 TO STA. 8+73.00	Area=	865		
STA. 8+73.00 TO STA. 8+63.00	28.89			
INCIDENTAL BITUMINOUS SURFACING				
ENTRANCES	5,128.72			
SIDE ROADS	1,308.67			
PROJECT TOTAL	7,049	865	12,823	121,925

GRADING AND SHAPING DITCHES

LOCATION	QUANTITY (FOOT)
F. A. P. 777 (IL 185)	
STA. 787+00.00 TO STA. 790+00.00 LT	300.00
PROJECT TOTAL	300