

SCHEDULE OF QUANTITIES

STEEL PLATE BEAM GUARDRAIL, TYPE A, 6' POSTS

LOCATION	QUANTITY (FOOT)
F. A. P. 777 (IL 185)	
DAMAGED RAILING	
STA. 484+19.00 TO STA. 484+69.00 RT	50.0
PROJECT TOTAL	50

TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

LOCATION	QUANTITY (EACH)
F. A. P. 777 (IL 185)	
STA. 462+75.00 TO STA. 463+25.00 LT	1
STA. 462+90.00 TO STA. 463+40.00 RT	1
STA. 463+40.00 TO STA. 463+90.00 RT	1
STA. 464+52.50 TO STA. 465+02.50 RT	1
STA. 465+90.00 TO STA. 466+40.00 RT	1
STA. 466+75.00 TO STA. 467+25.00 LT	1
STA. 479+69.00 TO STA. 480+19.00 RT	1
STA. 485+69.00 TO STA. 486+19.00 RT	1
LIMITS OF IMPROVEMENT - 492+48.09	
BRIDGE OMISSION - S. N. 068-0027	
LIMITS OF IMPROVEMENT - STA. 492+91.29	
LIMITS OF IMPROVEMENT - STA. 499+34.95	
BRIDGE OMISSION - S. N. 068-0505	
LIMITS OF IMPROVEMENT - STA. 501+51.95	
STA. 739+70.00 TO STA. 740+20.00 LT	1
STA. 743+70.00 TO STA. 744+20.00 LT	1
PROJECT TOTAL	10

GUARDRAIL REMOVAL

LOCATION	QUANTITY (FOOT)
F. A. P. 777 (IL 185)	
STA. 462+75.00 TO STA. 463+25.00 LT	50
STA. 462+90.00 TO STA. 463+90.00 RT	100.00
STA. 464+52.50 TO STA. 465+02.50 RT	50
STA. 465+90.00 TO STA. 466+40.00 RT	50
STA. 466+75.00 TO STA. 467+25.00 LT	50
STA. 479+69.00 TO STA. 480+19.00 RT	50
DAMAGED RAILING	
STA. 484+19.00 TO STA. 484+69.00 RT	50
STA. 485+69.00 TO STA. 486+19.00 RT	50
LIMITS OF IMPROVEMENT - 492+48.09	
BRIDGE OMISSION - S. N. 068-0027	
LIMITS OF IMPROVEMENT - STA. 492+91.29	
LIMITS OF IMPROVEMENT - STA. 499+34.95	
BRIDGE OMISSION - S. N. 068-0505	
LIMITS OF IMPROVEMENT - STA. 501+51.95	
STA. 739+95.00 TO STA. 740+20.00 LT	25
STA. 743+70.00 TO STA. 743+95.00 LT	25
PROJECT TOTAL	500

TELESCOPING STEEL SIGN SUPPORT

LOCATION	QUANTITY (FOOT)
F. A. P. 777 (IL 185) (Sta. 806+11.00, 29.27' LT)	
5' -Post Above Ground	
5' -Post Below Ground	
3' Sign Support	
1' for Adjustments	14
PROJECT TOTAL	14

GUARDRAIL MARKERS, TYPE A

LOCATION	QUANTITY (EACH)
F. A. P. 777 (IL 185)	
TWO-WAY GUARDRAIL MARKERS	
STA. 462+75.00 TO STA. 463+25.00 LT	2@ 30' SP
STA. 462+77.50 TO STA. 463+27.50 RT	2@ 30' SP
STA. 463+52.00 TO STA. 464+02.50 RT	2@ 30' SP
STA. 464+52.50 TO STA. 465+02.50 RT	2@ 30' SP
STA. 465+90.00 TO STA. 466+40.00 RT	2@ 30' SP
STA. 466+75.00 TO STA. 467+25.00 LT	2@ 30' SP
STA. 479+69.00 TO STA. 480+19.00 RT	2@ 30' SP
STA. 485+69.00 TO STA. 486+19.00 RT	2@ 30' SP
LIMITS OF IMPROVEMENT - 492+48.09	
BRIDGE OMISSION - S. N. 068-0027	
LIMITS OF IMPROVEMENT - STA. 492+91.29	
LIMITS OF IMPROVEMENT - STA. 499+34.95	
BRIDGE OMISSION - S. N. 068-0505	
LIMITS OF IMPROVEMENT - STA. 501+51.95	
STA. 739+70.00 TO STA. 740+20.00 LT	2@ 30' SP
STA. 743+70.00 TO STA. 744+20.00 LT	2@ 30' SP
PROJECT TOTAL	20

SIGN PANEL-TYPE 1

LOCATION	QUANTITY (SQ FT)
F. A. P. 777 (IL 185) (Sta. 806+11.00, 29.27' LT)	
(Double Yellow Sign)	
W1-7 / 36" x 18"	4.50
(Reflector Panels)	
OM1-3 / 18" x 18" (2 Panels)	4.50
PROJECT TOTAL	9

FILE NAME =	USER NAME = coxjm	DESIGNED - JWC	REVISED -
ca:\pwork\PMIDOT\COXJW\dms22861\Shs5of	edules.dgn	DRAWN - JWC	REVISED -
PLOT SCALE = 1/8" = 1' IN.	CHECKED - RSC	DATE - 7/14/09	REVISED -
PLOT DATE = Aug-13-2009 10:29:23AM			

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO. 3 OF 7 SHEETS	STA.	TO STA.

F.A.P. RTE. 777	SECTION IORS-5	COUNTY Montgomery	TOTAL SHEETS 54	SHEET NO. 15
CONTRACT NO. 72A68				
ILLINOIS FED. AID PROJECT				