

SCHEDULE OF QUANTITIES

THERMOPLASTIC PAVEMENT MARKING - LINE

RAISED REFLECTIVE PAVEMENT MARKING REMOVAL

LOCATION	5"			8"	12"
	YELLOW			WHITE	WHITE
	SOLID (FOOT)	SKIP-DASH (FOOT)	DBL SOLID (FOOT)	SOLID (FOOT)	SOLID (FOOT)
F. A. P. 777 (IL 185)					
STA. 399+66.92 TO STA. 400+50.00	83.08				
STA. 399+66.92 TO STA. 427+00.00		683.27		5,466.16	
LIMITS OF IMPROVEMENT - 492+48.09					
BRIDGE OMISSION - S.N. 068-0027					
LIMITS OF IMPROVEMENT - STA. 492+91.29					
LIMITS OF IMPROVEMENT - STA. 499+34.95					
BRIDGE OMISSION - S.N. 068-0505					
LIMITS OF IMPROVEMENT - STA. 501+51.95					
Mulberry Grove Rd.					
STA. 9+87.00 TO STA. 8+63.00				248	
STA. 9+53.00 TO STA. 8+63.00			180		
Painted Median @ Mulberry Grove Rd./IL 185 Intersection					
STA. 9+86.00 TO STA. 9+53.00				105.06	
Chevrons on Painted Median @ Mulberry Grove Rd./IL 185 Intersection					
STA. 9+86.00 TO STA. 9+53.00					52.08
PROJECT SUB-TOTAL	83.08	683.27	180	5,714.16	105.06
PROJECT TOTAL	6,661			105	52

LOCATION	QUANTITY (EACH)
F. A. U. 777 (IL 185)	
Beginning of Project to Ash St.	7
Ash St. to Walnut St.	6
Walnut St. to Happy Ln.	40
Happy Ln. to Merry Ln.	39
Merry Ln. to E. 18th St.	22
E. 18th St. to Battle Tr.	17
Battle Tr. To E. 19th Rd.	57
E. 19th Rd. to Harvey Tr.	13
Harvey Tr. To Kays Tr.	45
Kays Tr. To Dads Tr.	9
Dads Tr. To Landers Tr. Rt./Horse Tr. Lt	57
Landers Tr. Rt./Horse Tr. Lt to Oak Tr.	31
Oak Tr. To N. 3rd Ave.	66
N. 3rd Ave. to Burg Tr.	59
Burg Tr. To Burg Rd.	24
Burg Rd. to Mulberry Grove Rd.	19
Mulberry Grove Rd. to Wyant Ln.	52
Wyant Ln. to E. 24th Rd.	16
E. 24th Rd. to End of Project	3
PROJECT TOTAL	582