TEMPORARY EROSION CONTROL SCHEDULE

STATION	OFFSET (FT)	LOCATION	PERIMETER EROSION BARRIER (FT)	TEMPORARY EROSION CONTROL SEEDING (POUND)	AGGREGATE (EROSION CONTROL) (TON)
319+00 TO 325+42		RT	685		
315+64 TO 337+61.40				500	
318+80 TO 325+42		LT	677		
316+73.98	34.28	RT			4
317+55.39	33.39	LT			4
317+73.98	34.28	RT			4
318+55.39	33.39	LT			4
318+66.68	35.63	LT			4
318+73.98	32.58	RT			4
318+88.74	35.6	RT			4
326+55 TO 329+95		RT	356		
326+55 TO 334+50		LT	804		
329+89.66	39.65	RT			4
329+97.76	36.57	RT			4
330+97.76	37.61	RT			4
331+97.76	36.97	RT			4
332+97.76	36.48	RT			4
333+97.76	35.68	RT			4
334+42.10	42.92	LT			4
334+51.40	39.9	LT			4
334+91.76	35.4	RT			4
335+51.16	32.95	LT			4
335+97.76	35.4	RT			4
336+51.16	33.31	LT			4
336+95.96	38.97	RT			4
337+05.56	41.17	LT			4
			2522	500	84

PERMANENT EROSION CONTROL SCHEDULE

LOCATION		LT/RT	HEAVY DUTY EXCELSIOR BLANKET	STONE RIPRAP, CLASS A4, 16"	FILTER FABRIC
STATION	TO STATION		(SQ YD)	(SQ YD)	(SQ YD)
319+50.00	325+40.41	RT	1836		
319+50.00	325+40.47	LT	1081		
324+88.71	325+08.71	LT/RT		47	47
326+81.29	327+01.29	LT/RT		47	47
326+55.24	333+50.00	LT	1026		
326+55.28	328+50.00	RT	276		
336+88.46	337+29.08	LT		41	
337+28.06	337+66.74	RT			41
TOTALS			3219	135	135

CULVERT EXTENSION SCHEDULE

STATION	OFFSET	LOCATION	TO	STATION	OFFSET	LOCATION	BOX CULVERT END SECTION (CU YD)	CONCRETE BOX CULVERTS (CU YD)
337+10.77	29.21'	LT	TO				1.5	
337+11.36	28.19'	LT	TO	337+15.34	21.24'	LT		2
337+40.35	22.55'	RT	TO	337+44.33	29.50'	RT		2
337+44.94	30.56'	RT	TO				1.5	
							3	4

PLAN
NOTE BOOK NO. ____
SURVEYED ____
PLOTTED ____
ALIGNMENT CHECKED ____
RT. OF WAY CHECKED ____
CADD FILE NAME ____
BY
DATE

PROFILE
NOTE BOOK NO. ____
SURVEYED ____
PLOTTED ____
GRADES CHECKED ____
B.M. NOTED ____
STRUCTURE NOTAT'NS CHK'D
BY
DATE